

Addendum No. 1

December 5, 2023

To Contract Documents for

CURTIS HALL RENOVATIONS

Castine, ME

Maine Maritime Academy

1 Pleasant Street, Castine, ME 04421

CHA Project Number 076982

BGS Project Number 3397



Prepared by:
CHA Architecture, P.C.
49 Dartmouth Street
Portland, Maine 04101
207-775-1059
www.chasolutions.com



**Curtis Hall Renovations
Maine Maritime Academy
1 Pleasant Street, Castine, Maine 04421
Addendum #1
Date: December 5, 2023**

This Addendum modifies, amends and supplements designated parts of the
Contract Documents, Project Manual and Drawings for

Curtis Hall Renovations at Maine Maritime Academy, dated November 22, 2023
and is hereby made a part thereof by reference and shall be as binding as though inserted in its entirety in the locations
specified herein. It shall be the responsibility of the Contractor to notify all Subcontractors and Suppliers they
propose to use for the various parts of the work of any changes or modifications contained in this Addendum.

INDEX

	General Information
PART I	Addendum for Civil Specifications and Drawings
PART II	Addendum for Structural Specifications and Drawings
PART III	Addendum for Architectural Project Manual and Drawings
PART IV	Addendum for Mechanical Specifications and Drawings
PART V	Addendum for Electrical Specifications and Drawings

GENERAL INFORMATION

1. Note: The original Project Manual posted on the BGS website was a draft specification and was replaced with the correct full Project Manual on Nov. 29 2023.

PART I- ADDENDUM FOR CIVIL SPECIFICATIONS AND DRAWINGS:

1. None

PART II- ADDENDUM FOR STRUCTURAL SPECIFICATIONS AND DRAWINGS:

1. CHANGES TO THE SPECIFICATIONS

- a. NONE

2. CHANGES TO THE DRAWINGS

- a. Drawing S000 Structural – General Information: Added masonry Notes.
- b. Drawing S101.1Phase 1 First Floor Structural Plans: Minor notes and Plan Reference Modifications
- c. Drawing S101.2Phase 1 Second Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- d. Drawing S101.3Phase 1 Third Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- e. Drawing S101.4 Phase 1 Fourth Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- f. Drawing S101.5 Phase 1 Roof Level Structural Plans: Added note regarding no access or available information relative to existing roof framing, deck removal and putback, masonry demo and put back modifications, finalized dunnage member sizing and detail callouts, and Plan Reference Modifications.
- g. Drawing S101.G Phase 1 First Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- h. Drawing S102.1 Phase 2 First Floor Structural Plans: Existing Framing sizes annotated, minor notes and Plan Reference Modifications



Curtis Hall Renovations
Maine Maritime Academy
1 Pleasant Street, Castine, Maine 04421
Addendum #1
Date: December 5, 2023

- i. Drawing S102.2 Phase 2 Second Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- j. Drawing S102.3 Phase 2 Third Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- k. Drawing S102.4 Phase 2 Roof Level Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- l. Drawing S102.5 Phase 2 Added note regarding no access or available information relative to existing roof framing, masonry demo and put back modifications, finalized dunnage member sizing and detail callouts, and Plan Reference Modifications.
- m. Drawing S103.1 Phase 3 First Floor Structural Plans: Existing Framing sizes annotated, Floor Hatch location identified, Slab demo extents revised, minor notes and Plan Reference Modifications
- n. Drawing S103.2 Phase 3 Second Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- o. Drawing S103.3 Phase 3 Third Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- p. Drawing S103.4 Phase 3 Roof Level Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- q. Drawing S103.5 Phase 3 Roof Level Structural Plan: Added note regarding no access or available information relative to existing roof framing, deck removal and putback, masonry demo and put back modifications, finalized dunnage member sizing and detail callouts, and Plan Reference Modifications.
- r. Drawing S104.2 Phase 4 Second Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- s. Drawing S104.3 Phase 4 Third Floor Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- t. Drawing S104.4 Phase 4 Fourth Level Structural Plans: Existing Framing sizes annotated, masonry demo and put back modifications, and Plan Reference Modifications.
- u. Drawing S104.5 Phase 4 Roof Level Structural Plan: Added note regarding no access or available information relative to existing roof framing, deck removal and putback, masonry demo and put back modifications, finalized dunnage member sizing and detail callouts, and Plan Reference Modifications.
- v. Drawing S202 DELETE in its entirety.
- w. Drawing S401 Enlarged Structural Framing Part Plans: Completed annotation and section callouts for roof and condenser dunnage configurations.
- x. Drawing S402 Entry Canopy Structural Framing Plan: Updated detailing.
- y. Drawing S500 Structural Details: Revised details.
- z. Drawing S501 Structural Details: Completed annotation and section callouts for roof and condenser dunnage configurations, added details.

PART III- ADDENDUM FOR ARCHITECTURAL PROJECT MANUALS AND DRAWINGS:

1. CHANGES TO THE SPECIFICATIONS

- a. Section 017400 – CONSTRUCTION WASTE MANAGEMENT with revised version attached with changes noted in **Bold. REPLACE** the section in its entirety.
- b. Section 028210-ASBESTOS ABATEMENT - **ADD** the section in its entirety.
- c. Section 00110-TABLE OF CONTENTS changes indicated in Bold adding Asbestos Abatement - **REPLACE** the section in its entirety.
- d. Appendix 1 – Hazardous Materials Assessment for Curtis Hall - **ADD** the section in its entirety.
- e. Appendix 2 – Supplemental ACM Roof Sample Results for Curtis Hall - **ADD** the section in its entirety.



2. CHANGES TO THE DRAWINGS

- a. Drawing COVER SHEET - **REPLACE** the sheet in its entirety. Includes additions and deletions to the drawing list.
- b. Drawing A000.1 – GENERAL - **REPLACE** the sheet in its entirety. includes updates to general notes, keynote legends, and alternate language.
- c. Drawing A203 -EXTERIOR ELEVATIONS – LOBBY - **REPLACE** the sheet in its entirety. Includes updates to sheet title, storefront tags placed, mullion added to window, exterior elevation view adjusted to show windows.
- d. Drawing A210 – INTERIOR ELEVATIONS, **REPLACE** the sheet in its entirety. includes updates to notes added to views
- e. Drawing A401 – TYPICAL ENLARGED PLANS – BATHROOMS. **REPLACE** the sheet in its entirety.
- f. Drawing H100 – GROUND FLOOR IDENTIFIED ASBESTOS-CONTAINING MATERIALS. **ADD** the sheet in its entirety
- g. Drawing H101-FIRST FLOOR IDENTIFIED ASBESTOS-CONTAINING MATERIALS. **ADD** the sheet in its entirety
- h. Drawing H102-SECOND FLOOR IDENTIFIED ASBESTOS-CONTAINING MATERIALS. **ADD** the sheet in its entirety
- i. Drawing H103-THIRD FLOOR IDENTIFIED ASBESTOS-CONTAINING MATERIALS. **ADD** the sheet in its entirety
- j. Drawing H104-FOURTH FLOOR IDENTIFIED ASBESTOS-CONTAINING MATERIALS. **ADD** the sheet in its entirety

PART IV- ADDENDUM FOR MECHANICAL SPECIFICATIONS AND DRAWINGS:

1. CHANGES TO THE SPECIFICATIONS

- a. Section 211000 – Fire-Suppression Sprinkler System: **ADD** the section in its entirety.

2. CHANGES TO THE DRAWINGS

Revised Mechanical drawings: pipe sizes, duct sizes, keyed notes, refrigerant piping layouts, expansion joints, view scale, schedules, etc.

- a. MEP000
- b. M101.G
- c. M101.0
- d. MH101.1
- e. MP101.1
- f. M101.2
- g. M101.3
- h. M101.4
- i. M101.5
- j. MH102.1
- k. MP102.1
- l. M102.2
- m. M102.3
- n. M102.4
- o. M102.5
- p. MH103.1
- q. MP103.1
- r. M103.2
- s. M103.3
- t. M103.4
- u. M103.5
- v. M104.G



**Curtis Hall Renovations
Maine Maritime Academy
1 Pleasant Street, Castine, Maine 04421
Addendum #1
Date: December 5, 2023**

- w. MH104.1
- x. MP104.1
- y. M104.2
- z. M104.3
- aa. M104.4
- bb. M104.5
- cc. M601
- dd. M603
- a. Revised Fire Protection drawings: hatched soffit callouts, notes, etc.
 - a. FP100.0
 - b. FP100.1
 - c. FP100.2
 - d. FP100.3
 - e. FP100.4

PART V- ADDENDUM FOR ELECTRICAL SPECIFICATIONS AND DRAWINGS:

1. CHANGES TO SPECIFICATIONS

- a. None

2. CHANGES TO DRAWINGS

- a. All EL- series drawings:
- b. updated keynotes for clarity; updated stairwell layouts; updated various missing keynotes on plans; added missing EBUs; revised fixture types
- c. EP101.5, EP102.5, EP103.5, EP104.5 – added service receptacles at equipment
- d. EP101.0 – updated view title for consistency
- e. EP102.1 – updated courtyard horn/strobe candela rating
- f. EP103.1 – updated main entry fire alarm, door operator, and card reader
- g. EP104.3 – removed duplicate panel
- h. E400 – updated typical room layouts
- i. E600 – added technology matrix symbology
- j. E601 – updated mechanical equipment schedule
- k. E602, E603 – updated panel schedules

END OF ADDENDUM

PROJECT MANUAL

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

Document 002113	Instructions to Bidders
Document 004113	Contractor Bid Form
Document 005213	Contract Agreement
Document 006113.13	Contractor Performance Bond
Document 006113.16	Contractor Payment Bond
Document 007100	Definitions
Document 007213	General Conditions
Document 007346	Wage Determination Schedule

DIVISION 01 - GENERAL REQUIREMENTS

Section 011000	General Requirements
Section 011080	Health and Safety Procedures
Section 012100	Allowances
Section 012200	Unit Prices
Section 012300	Alternates
Section 013220	Photographic Documentation
Section 014000	Special Inspections
Section 016200	Substitution Request Form
Section 017400	Construction Waste Management
Section 018120	Construction Indoor Air Quality (IAQ) Management

DIVISION 02 - EXISTING CONDITIONS

Section 024100	Demolition
Section 028210	Asbestos Abatement

DIVISION 03 - CONCRETE

Section 033000	Cast-In-Place Concrete
Section 037300	Concrete Rehabilitation

DIVISION 04 - MASONRY

Section 042000	Unit Masonry
Section 047200	Cast Stone Masonry

DIVISION 05 - METALS

Section 051200	Structural Steel
Section 052100	Steel Joists
Section 053100	Steel Deck
Section 054000	Cold-Formed Metal Framing
Section 055000	Metal Fabrications

DIVISION 06 - WOOD, PLASTICS AND COMPOSITES

Section 061000	Rough Carpentry
----------------	-----------------

Section 061600	Sheathing
Section 064020	Interior Architectural Woodwork
Section 064200	Paneling

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

Section 070150	Modifications to Existing Roofing
Section 072100	Thermal Insulation
Section 072419	Exterior Insulation and Finish System (EIFS)
Section 072700	Air Barriers
Section 074200	Metal Wall Panels
Section 075300	EPDM Roofing
Section 076200	Sheet Metal Flashing and Trim
Section 077100	Roof Specialties
Section 077200	Roof Accessories
Section 078410	Penetration Firestopping
Section 078440	Fire-Resistive Joint Systems
Section 079200	Joint Sealants

DIVISION 08 - OPENINGS

Section 081110	Hollow Metal Doors and Frames
Section 081210	Interior Aluminum Frames
Section 081400	Flush Wood Doors
Section 083110	Access Doors and Frames
Section 084110	Aluminum-Framed Entrances and Storefronts
Section 085110	Aluminum Windows
Section 087100	Door Hardware
Section 088000	Glazing

DIVISION 09 - FINISHES

Section 092110	Gypsum Board Assemblies
Section 092120	Gypsum Board Shaft-Wall Assemblies
Section 093000	Tiling
Section 095100	Acoustical Ceilings
Section 096513	Resilient Wall Base and Accessories
Section 096800	Carpeting
Section 097200	Wall Coverings
Section 099000	Painting and Coating

DIVISION 10 - SPECIALTIES

Section 101100	Visual Display Surfaces
Section 101400	Signage
Section 102800	Toilet Accessories
Section 102819	Shower Enclosures
Section 104400	Fire Protection Specialties

DIVISION 11 – EQUIPMENT (NOT USED)

DIVISION 12 - FURNISHINGS

Section 122400	Shades
Section 124810	Entrance Floor Mats and Frames

DIVISION 21 – FIRE SUPPRESSION

Section 211000 Fire-Suppression Sprinklers

DIVISION 22 – PLUMBING

Section 220700 Plumbing Insulation
Section 220800 Commissioning of Plumbing
Section 221116 Domestic Water Piping
Section 221316 Plumbing Sanitary and Storm Piping
Section 223500 Domestic-Water Heat Exchangers
Section 224000 Plumbing Fixtures

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

Section 230500 Common Work Results for Mechanical
Section 230593 Testing, Adjusting, And Balancing for Hvac
Section 230700 Mechanical Insulation
Section 230800 Commissioning of HVAC
Section 230900 Instrumentation and Control for Hvac
Section 230993 Sequence of Operations
Section 232113 Hydronic HVAC Piping
Section 232123 Hydronic Pumps
Section 232213 Steam and Condensate Piping
Section 232300 Refrigerant Piping
Section 233113 Ductwork
Section 233423 Power and Gravity Ventilators
Section 233424 Exhaust Capture Systems
Section 233713 Diffusers, Registers, And Grilles
Section 235700 Steam to Hot Water Converters
Section 237200 Air-To-Air Energy Recovery Equipment
Section 237433 Dedicated Outdoor-Air Units
Section 238129 Variable-Refrigerant-Flow Hvac Systems
Section 238216 Duct Mounted Hot Water Heating Coils
Section 238219 Fan-Coil Units
Section 238233 Convection Heating Units
Section 238239 Cabinet Unit Heaters

DIVISION 26 – ELECTRICAL

Section 260010 Supplemental Requirements for Electrical
Section 260100 Basic Electrical Requirements
Section 260513 Medium-Voltage Cables
Section 260519 Low-Voltage Electrical Power Conductors and Cables
Section 260526 Grounding and Bonding for Electrical Systems
Section 260529 Hangers and Supports for Electrical Systems
Section 260533 Raceways and Boxes for Electrical Systems
Section 260543 Underground Ducts and Raceways for Electrical Systems
Section 260544 Sleeves and Sleeve Seals for Electrical Raceways and Cabling
Section 260548 Seismic Controls for Electrical Systems
Section 260553 Identification for Electrical Systems
Section 260572 Overcurrent Protective Device Short-Circuit Study
Section 260573 Overcurrent Protective Device Coordination Study

Section 260574	Overcurrent Protective Device Arc-Flash Study
Section 260800	Commissioning of Electrical Systems
Section 260923	Lighting Control Devices
Section 261219	Pad-Mounted, Liquid-Filled, Medium-Voltage Transformers
Section 262413	Switchboards
Section 262416	Panelboards
Section 262713	Electricity Metering
Section 262726	Wiring Devices
Section 262813	Fuses
Section 262816	Enclosed Switches and Circuit Breakers
Section 262913	Enclosed Controllers
Section 263213.13	Diesel Emergency Engine Generators
Section 263600	Transfer Switches
Section 265119	LED Interior Lighting
Section 265600	Exterior Lighting

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

Section 280513	Conductors and Cables for Electronic Safety and Security
Section 283111	Digital, Addressable Fire-Alarm System
Section 283115	Emergency Responder Radio Antenna/Repeater System

DIVISION 31 – EARTHWORK

Section 311000	Site Clearing
Section 312213	Rough Grading
Section 312316	Excavation
Section 312317	Trenching
Section 312318	Rock Removal
Section 312323	Backfill
Section 322513	Erosion Controls
Section 313800	Geotextiles

DIVISION 32 – EXTERIOR IMPROVEMENTS

Section 321216	Asphaltic Paving
Section 323119	Decorative Metal Fences and Gates
Section 329219	Seeding

DIVISION 33 – UTILITIES

Section 331113	Public Water Utility Distribution Piping
Section 331216	Water Utility Distribution Valves
Section 331300	Disinfection of Water Utility Systems
Section 333100	Sanitary Sewage Systems
Section 337119	Electrical Underground Ducts, Ductbanks, and Manholes

APPENDICES

Appendix 1	Hazardous Materials Assessment for Curtis Hall
Appendix 2	Supplemental ACM Roof Sample Results for Curtis Hall

END OF TABLE OF CONTENTS

SECTION 017400

CONSTRUCTION WASTE MANAGEMENT

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS, which are hereby made a part of this Section of the Specifications.

1.2 SUMMARY

- A. This Section includes requirements for the Contractor's implementation of waste management controls and systems for the duration of the Work.
- B. Develop a waste management plan, quantifying material diversion by either weight or volume to recycle and/or salvage non-hazardous construction and demolition debris.

1.3 INTENT

- A. The Owner and Architect have established that this Project shall generate the least amount of waste practical and that processes that ensure the generation of as little waste as possible due to error, poor planning, breakage, mishandling, contamination, or other factors shall be employed.
- B. With regard to these goals the Contractor shall develop, for the Architect's review, a Construction Waste Management Plan (CWMP) for this Project.
- C. Each Subcontractor shall be responsible for segregating his own waste into different dumpsters as directed by the Contractor.
- D. Contractor shall be responsible for ensuring that debris will be disposed of at appropriately designated licensed solid waste disposal facilities, as defined by MGL Chapter 111, Section 150A.

1.4 SUBMITTALS

- A. Waste Management Plan (WMP): Submit within 21 calendar days after receipt of Notice to Proceed, in a format acceptable to the Owner.
 - 1. Analysis of the proposed jobsite waste to be generated, including types and rough quantities.
 - 2. Landfill Options: The name of the landfills where trash and building debris will be disposed of, the applicable landfill tipping fees, and the projected cost of disposing of all Project waste in the landfills.
 - 3. Landfill Certification: Contractor's statement of verification that landfills proposed for use are licensed for types of waste to be deposited and have sufficient capacity to receive waste from this project.

4. Alternatives to Landfilling: A list of each material proposed to be salvaged or recycled during the course of the Project. Include the following and any additional items proposed:
 - a. Cardboard and paper products.
 - b. Clean dimensional wood.
 - c. Beverage containers.
 - d. Concrete.
 - e. Slurry wall materials.
 - f. Bricks and masonry.
 - g. Asphalt.
 - h. Metals from framing, banding, stud trim, ductwork, piping, rebar, roofing, other trim, steel, iron, galvanized sheet steel, stainless steel, aluminum, copper, zinc, lead, brass, and bronze.
 - i. Mechanical and electrical equipment.
 - j. Building components which can be removed relatively intact from existing construction.
 - k. Packaging materials, including cardboard, boxes, plastic sheet and film, polystyrene packaging, wood crates, plastic pails.
 - l. Glass.
 - m. Scraps from new gypsum wall board.
 - n. Carpet and pad.
 - o. Acoustical ceiling panels.
 - p. Plastics.
 5. Meetings: A description of the regular meetings to be held to address waste management.
 6. Materials Handling Procedures: A description of the means by which any waste materials identified above will be protected from contamination, and a description of the means to be employed in recycling the above materials consistent with requirements for acceptance by designated facilities.
 7. Transportation: A description of the means of transportation of the recyclable materials (whether materials will be site-separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site) and destination of materials.
- B. Waste Management Progress Reports: Concurrent with each Application for Payment, submit a written Waste Management Progress Report in the same format as required for Final Report.
- C. Waste Management Final Report: Prior to Substantial Completion, submit a written Waste Management Final Report summarizing the types and quantities of materials recycled and disposed of under the Waste Management Plan. Include the name and location of disposal facilities.
1. Material category.
 2. Generation point of waste.
 3. Total quantity of waste, by weight.
- D. Other Submittals:
1. Records of Donations: Indicate receipt and acceptance of salvageable waste donated to individuals and organizations. Indicate whether organization is tax exempt.
 2. Records of Sales: Indicate receipt and acceptance of salvageable waste sold to individuals and organizations. Indicate whether organization is tax exempt.

3. Recycling and Processing Facility Records: Indicate receipt and acceptance of recyclable waste by recycling and processing facilities licensed to accept them. Include manifests, weight tickets, and/or receipts.
4. Landfill and Incinerator Disposal Records: Indicate receipt and acceptance of waste by landfills and incinerator facilities licensed to accept them. Include manifests, weight tickets, and/or receipts.
5. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.
6. **Bills of lading, manifests, and/or certificates of recycling and/or recovery of Universal Wastes as defined by EPA and Maine Department of Environmental Protection (MDEP) regulations.**

1.5 CONTRACTORS

- A. Contractor may subcontract work of this Section to a sub-contractor specializing in recycling and salvaging of construction waste.
- B. Gypsum Wallboard Recycling: New, paper-faced gypsum wallboard scrap (cuts from construction - not demolition waste) generated at project shall be recycled. Keep scrap dry.
- C. Acoustical Ceiling Panel Recycling: Demolition and construction waste pulpable mineral fiber ceiling panels may be recycled by Armstrong World Industries and US Gypsum. Contact Armstrong at 1-877-ARMSTRONG (1-877-276-7876) or www.armstrong.com or contact USG at 1-800-USG-4YOU or www.usg.com, to coordinate recycling efforts, apply for product approvals, and receive reclamation procedure requirements.
- D. Carpet Recycling: Demolition and construction waste carpet and carpet padding may be recycled by Carpet America Recovery Effort (CARE). Visit www.carpetrecovery.org to locate carpet reclaimers in local project area and reclamation procedure requirements.

PART 2 - PRODUCTS [Not Used]

PART 3 - EXECUTION

3.1 PLAN IMPLEMENTATION

- A. General: Implement Waste Management Plan as approved by the Architect. Provide containers, storage, signage, transportation, and other items as required to implement WMP for the entire duration of the Contract.

3.2 WASTE MANAGEMENT PLAN IMPLEMENTATION

- A. Manager: The Contractor shall designate an on-site person responsible for instructing workers and overseeing and documenting results of the Waste Management Plan for the Project.
- B. Distribution: The Contractor shall distribute copies of the Waste Management Plan to the Job Site Foreman, each Subcontractor, the Owner and the Architect.

- C. Instruction: The Contractor shall provide on-site instruction of appropriate separation, handling, and recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the Project.
- D. Separation Facilities: The Contractor shall lay out and label a specific area to facilitate separation of materials for recycling, salvage, reuse, and return. Recycling and waste bin areas are to be kept neat and clean and clearly marked in order to avoid contamination of materials. Location shall be acceptable to the Architect.
- E. Hazardous Wastes: Any unforeseen hazardous wastes shall be separated, stored, and disposed of according to local regulations and as directed by the Owner.

END OF SECTION

SECTION 028210 - ASBESTOS ABATEMENT

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 GENERAL REQUIREMENTS and DIVISION 02 EXISTING CONDITIONS which are hereby made a part of this Section of the Specifications.

1.2 SUMMARY

- A. This Section includes furnishing labor, materials, equipment, supplies, and performing all operations necessary to complete the removal of asbestos-containing materials (ACM) by a qualified ASBESTOS ABATEMENT SUBCONTRACTOR with competent persons willing, trained, knowledgeable and qualified in the techniques of asbestos abatement, handling and disposal of ACM and asbestos-contaminated materials and the subsequent cleaning of contaminated areas, and complying with all applicable federal, state, and local regulations in accordance with the attached drawings and these specifications.

1.3 SCOPE OF WORK

- A. Remove identified and similar ACM impacted by the planned phased renovation work at Curtis Hall located on the Maine Maritime Academy (MMA) campus in Castine, Maine as identified in Figures H100, H101, H102, H103 and H104. These figures provide general coordination of information only, are schematic in nature, and do not identify individual items to be removed as required by the phased renovation project. ASBESTOS ABATEMENT SUBCONTRACTOR is responsible for confirming actual quantities of ACM and non-ACM building materials to be removed under this Contract.
- B. The work to be performed under this Contract consists of the removal and disposal of ACM present on the interior and exterior of the building impacted by the planned phased renovation of the building as described in Section 1.4 - Summary of Materials, **Table 1: Summary of Identified Asbestos Containing Materials (ACM) and Estimated Quantities, Curtis Hall, Maine Maritime Academy, Castine, Maine.** The ASBESTOS ABATEMENT SUBCONTRACTOR is responsible for identifying and confirming the actual quantities of ACM to be removed as part of the phased renovations prior to submission of a proposal or bid.
- C. The ASBESTOS ABATEMENT SUBCONTRACTOR shall be responsible for the preparation of a site-specific asbestos abatement project design and work plan for each work area. An Asbestos Abatement Design Consultant licensed by the Maine Department of Environmental Protection (MDEP) will prepare the design. The site-specific asbestos abatement project design and work plan will be signed by the licensed Asbestos Abatement Design Consultant prior to approval to proceed with work.
- D. The ASBESTOS ABATEMENT SUBCONTRACTOR shall be responsible for the submission of all appropriate Federal, State and local notifications and fees.
- E. The ASBESTOS ABATEMENT SUBCONTRACTOR shall be responsible for providing a MDEP licensed independent air monitor for all visual evaluations and air clearances.

The ASBESTOS ABATEMENT SUBCONTRACTOR shall be responsible for conducting personal exposure monitoring on their employees during abatement activities.

1.4 SUMMARY OF MATERIALS

- A. See **TABLE 1: Summary of Identified Asbestos Containing Materials (ACM) and Estimated Quantities, Curtis Hall, Maine Maritime Academy, Castine, Maine.**



**TABLE 1 | SUMMARY OF IDENTIFIED ASBESTOS CONTAINING MATERIALS (ACM) AND ESTIMATED QUANTITIES
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE, MAINE**

Room Section/Number	Sample #:	Pipe Insulation and Associated Mud Pipe Fittings (LF)	Tank Insulation (SF)	Mud Pipe Fittings Insulation on Fiberglass-insulated lines (EA)	Gasket on stored equipment (SF)	Asphalt Vapor Barrier (SF)	Floor Tile Adhesive beneath Non-ACM Floor Tile (SF)	Floor Tile and associated ACM adhesive (SF)	Exterior Caulk Associated with Window Frames (EA)	Comment
GROUND FLOOR										
Boiler Room - Mezzanine	PH1-002C	30								
	PH1-003A									
	PH1-004A			25						
	PH1-005A		50							
Boiler Room	PH1-004A			26						
Electrical Room	PH1-004A			7						
Armory Chase	PH1-004A			10						
	PH2-043A					40				
Armory	PH2-043A					60				
Rifle Range (B34)	PH2-043A					180				
	PH2-041A				2					
Hallway (B10)	PH1-012A			4						Above ceiling tiles
The Bilge (G1)	PH4-047A						625			
Kitchen (G2)	PH4-047A						55			
Men's Room (G4)	PH1-012A			20						Chase inaccessible
Women (G5)	PH1-012A			5						located within a pipe enclosure
Bookstore Storage (G17)	PH1-012A			10						
Bookstore (G106)	PH1-012A			7						
FIRST FLOOR										
Tele Equip TE001	PH1-016A							60		
Storage S111	PH1-016A							50		
Conf Dept Office (F115)	PH1-016A							180		



**TABLE 1 | SUMMARY OF IDENTIFIED ASBESTOS CONTAINING MATERIALS (ACM) AND ESTIMATED QUANTITIES
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE, MAINE**

Room Section/Number	Sample #:	Pipe Insulation and Associated Mud Pipe Fittings (LF)	Tank Insulation (SF)	Mud Pipe Fittings on Fiberglass-insulated lines (EA)	Gasket on stored equipment (SF)	Asphalt Vapor Barrier (SF)	Floor Tile Adhesive beneath Non-ACM Floor Tile (SF)	Floor Tile and associated ACM adhesive (SF)	Exterior Caulk Associated with Window Frames (EA)	Comment
Hallway near F107	PH1-012A			15						
Anchor Lounge (R101)	PH1-012A			4						
SECOND FLOOR										
H203	PH1-012A			2						
Hallway outside T235/T236	PH1-012A			4						
T202	PH1-012A			3						
Hallway outside T204	PH1-012A			2						
Hallway outside S203	PH1-012A			2						
S207	PH1-012A			2						
THIRD FLOOR										
T319				4						
H303				1						
Hall outside T338				4						
FOURTH FLOOR										
Hall outside L404				2						
EXTERIOR										
Exterior	PH1-030A								475	
TOTALS:		30	50	159	2	280	680	290	475	

1.5 RELATED REQUIREMENTS

- A. Drawings, Project Manual, and general provisions of the Contract, including, without limitation, General Conditions of the Contract, additional General Conditions of the Contract, and Division 00 and Division 01 specification sections, apply to this Section.
- B. 024100 Demolition

1.6 REFERENCES

- A. Applicable Code of Federal Regulations (CFR):
 1. 29 CFR 1910.1001 - General Industry Standard for Asbestos
 2. 29 CFR 1926.1101 - Construction Standard for Asbestos
 3. 29 CFR 1910.134 - General Industry Standard for Respiratory Protection
 4. 29 CFR 1910.1200 - Hazard Communication.
 5. 40 CFR 61 - Subpart M National Emission Standards for Hazardous Air Pollutants - Asbestos
- B. Applicable Code of Maine Rules (C.M.R.):
 1. 06-096 C.M.R.Ch. 425 - Asbestos Management Regulations
 2. 06-096 C.M.R.Ch. 411 - Non-Hazardous Waste Transporter Licensing Regulations
 3. 06-096 C.M.R.Ch. 405 - Solid Waste Management Regulations

1.7 SUBMITTALS

- A. Submittals will be received by the OWNER in accordance with this section before material or equipment is purchased or work is performed. The ASBESTOS ABATEMENT SUBCONTRACTOR shall submit to the OWNER, for review, two copies of the information required herein. The adequacy and accuracy of submittals and their compliance with contract documents are the responsibility of the ASBESTOS ABATEMENT SUBCONTRACTOR. All reviewing actions taken by the OWNER will in no way relieve the ASBESTOS ABATEMENT SUBCONTRACTOR of quality control requirements.

B. General

The ASBESTOS ABATEMENT SUBCONTRACTOR shall submit:

1. A list of proposed subcontractors with their addresses, specialties, and qualifications.
2. Certificate(s) of Insurance indicating coverage for asbestos abatement work.

C. Work Practices and Procedures:

1. Design and Work Plan: The ASBESTOS ABATEMENT SUBCONTRACTOR shall be responsible for the preparation of a site-specific asbestos abatement project design and work plan for each work area. An Asbestos Abatement Design Consultant licensed by the MDEP will prepare and sign the design.

The ASBESTOS ABATEMENT SUBCONTRACTOR shall submit a written work plan and sketches of the work procedures to be used in the removal, disposal and replacement of materials. The abatement plan will, at a minimum, include location of

asbestos control area, decontamination area, equipment decontamination enclosure, interface of trades involved in the construction, sequencing of asbestos-related work, disposal plan, type of wetting agent and sealant to be used, site specific air monitoring plan, personal air monitoring program and a description of the method to be employed to reduce fiber releases. For each work area, the abatement plan will show the point of controlled access to the building for transporting ACM from the regulated area to the exterior of the building. The abatement plan will show auxiliary make-up air points, location of HEPA exhaust ventilation units, location of HEPA exhaust, and location of pressure differential monitors.

2. Project Log: The ASBESTOS ABATEMENT SUBCONTRACTOR shall maintain a Project Log throughout the project. The log will contain notes concerning accidents that may happen and deviation from standard work procedures and project information. At project completion, the original log will be submitted to the OWNER.
3. Waste Disposal: The ASBESTOS ABATEMENT SUBCONTRACTOR shall identify the proposed waste disposal landfill for the project and provide a copy of the state approval certification Permits. The ASBESTOS ABATEMENT SUBCONTRACTOR shall provide a list of all permits, licenses, or manifests to be applied for, including notification of the MDEP.
4. The ASBESTOS ABATEMENT SUBCONTRACTOR shall prepare, for signature by the OWNER, an MDEP *Project Monitoring Disclosure Form*.
5. The ASBESTOS ABATEMENT SUBCONTRACTOR shall prepare for signature by the OWNER, an MDEP Asbestos Consultant Independent Business Relationship Disclosure Form.

D. Product and Equipment Data

1. Submit manufacturers' literature, catalog cuts, and product data sheets for products and equipment to be used in the asbestos abatement project. Attach Safety Data Sheets (SDS) to Product Data Sheets.
2. Submit SDS for products containing chemicals the ASBESTOS ABATEMENT SUBCONTRACTOR may be using on the project.
3. The ASBESTOS ABATEMENT SUBCONTRACTOR shall submit to the CONTRACTOR AND OWNER, two copies of the SDS attached to the Product Data sheet for new products brought on site for which an SDS has not been previously submitted. These submissions do not relieve the ASBESTOS ABATEMENT SUBCONTRACTOR of the OSHA requirements or ASBESTOS ABATEMENT SUBCONTRACTOR responsibilities with reference to the SDS nor does it relieve the ASBESTOS ABATEMENT SUBCONTRACTOR of responsibility for the subsequent proper use of the product.

E. Personnel, Training, Medical, and Respiratory Fit Test Documentation

The ASBESTOS ABATEMENT SUBCONTRACTOR shall submit the following:

1. Experience Summary: Submit name and experience summary of project supervisors and foremen.
2. Personnel: Submit copies of Personnel Training Certificates, Medical Examinations, Medical Questionnaires, and Respirator Fit Tests:
 - a. Summary Sheet: Submit a summary sheet of employees, listed in alphabetical order, to include name, social security number, classification, MDEP certificate number, and dates of training, medical examinations, medical questionnaires and respirator fit tests.

- F. ASBESTOS ABATEMENT SUBCONTRACTOR's License: Submit a copy of the ASBESTOS ABATEMENT SUBCONTRACTOR's MDEP license and the name of the ASBESTOS ABATEMENT SUBCONTRACTOR's project Contract Representative.
- G. Independent Asbestos Abatement Project Monitor (APM): Submit the name, associated firm and copy of MDEP license of the independent APM.

1.8 QUALITY ASSURANCE

- A. Job Site References: The ASBESTOS ABATEMENT SUBCONTRACTOR shall have on site, at all times, at least one copy of each of the following:
 - 1. Project Manual including Drawings and Specifications.
 - 2. Guidance for Controlling Asbestos Containing Materials in Building (EPA 560/5-85-024), June 1985.
 - 3. Asbestos Waste Management Guidance (EPA/530-SW-85-007) May 1985.
 - 4. A Guide to Respiratory Protection for the Asbestos Abatement Industry (EPA-560-OPTS-86-001), September 1986.
 - 5. OSHA Workplace Safety Standards, (29 CFR Parts 1910 and 1926).
 - 6. NESHAPs Asbestos Regulations (40 CFR Part 61 Subpart M).
 - 7. MDEP Asbestos Management Regulations (06-096 C.M.R. Chapter 425 (2011)).
- B. Safety Compliance: The ASBESTOS ABATEMENT SUBCONTRACTOR shall, in addition to detailed requirements of this specification:
 - 1. Comply with laws, ordinances, rules and regulations of federal, state, regional and local authorities regarding handling, storing, transporting ,and disposing of asbestos waste materials.
 - 2. Comply with the applicable requirements of the current issue of 29 CFR 1910.1001; 40 CFR 61, Subparts M and 29 CFR 1926.1101.
 - 3. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting work. Where the requirements of this specification and referenced documents vary, the most stringent requirement will apply.
- C. Respirator Program: The ASBESTOS ABATEMENT SUBCONTRACTOR shall establish a respirator program as required by 29 CFR 1910.1001 and 1926.1101. This program will comply with all paragraphs of 29 CFR 1910.134.

1.9 AUTHORITY TO STOP WORK

- A. The OWNER has the authority to stop the abatement work at any time that conditions are not within the specifications and applicable regulations. The stoppage of work will continue until conditions have been corrected and corrective steps have been taken to the satisfaction of the OWNER. The standby time required for the ASBESTOS ABATEMENT SUBCONTRACTOR's personnel and the APM to resolve violations will be at the ASBESTOS ABATEMENT SUBCONTRACTOR's expense.
- B. Stop-Work Airborne Fiber Levels will be as follows:
 - 1. Inside Contained Work Area (Removal): 0.5 f/cc (with wet methods).
 - 2. Outside Contained Work Area: 0.01 f/cc as measured in clean room and/or the HEPA exhaust.

- C. Stop work orders will be issued for, but not be limited, to the following:
1. Excessive airborne fiber concentrations inside and/or outside the work area.
 2. Breaks in containment barriers.
 3. Loss of negative air pressure (0.02 inches of water – minimum negative pressure to be maintained).
 4. Failure of workers to wear appropriate respiratory protection.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. The ASBESTOS ABATEMENT SUBCONTRACTOR shall furnish materials as necessary to perform the work specified herein and to comply with current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011).

2.2 GENERAL EQUIPMENT TO BE PROVIDED BY ASBESTOS ABATEMENT SUBCONTRACTOR

- A. The ASBESTOS ABATEMENT SUBCONTRACTOR shall furnish equipment, including personnel protective equipment, as necessary to perform the work specified herein and to comply with current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011).
- B. Workers and authorized visitors exposed to airborne concentrations of asbestos fibers will be provided with disposable, protective, whole-body clothing, head coverings, gloves, and foot coverings, and use of tape. Protective clothing will be provided to all workers and authorized visitors in sizes adequate to accommodate movement without tearing. Goggles will be provided in accordance with ANSI Z87.1 to personnel engaging in certain asbestos operations when a full-face respirator is not required.
- C. The ASBESTOS ABATEMENT SUBCONTRACTOR shall provide connections to existing water and electrical service provided by the OWNER as necessary to perform asbestos abatement related activities.

2.3 ENCAPSULANTS

- A. Encapsulants will not be used on this project. Should it be determined that encapsulation is necessary, a spray type encapsulant will be used as a lockdown of exposed surfaces and piping, only if previously approved by the OWNER. Any encapsulant used must be able to withstand heat and have the capacity to be applied pre-heated.

2.4 ELECTRICAL

- A. Electrical installations or modifications (including de-energization for the purposes of demolition of electrical components) are the responsibility of the ASBESTOS ABATEMENT SUBCONTRACTOR. The ASBESTOS ABATEMENT SUBCONTRACTOR shall coordinate all electrical work with the CONTRACTOR AND OWNER.
- B. Ground fault circuit interrupters (GFCI) will be provided for all electrical equipment to be installed outside the work area so that there is no live GFCI-protected electrical wiring inside the work area. The ASBESTOS ABATEMENT SUBCONTRACTOR shall furnish and install a portable GFCI Power Supply Board and receptacles including the following:

1. All circuits individually GFCI-protected.
2. Weatherproof enclosure NEMA 3 (rain-tight) with receptacle covers.
3. Construction durable, 16-gauge steel construction.
4. At least two 20-amp circuits (for APM).
5. Main circuit breaker.
6. Components UL listed.

- C. The Decontamination Facility will be furnished with a power supply board with one 20-amp circuit for the APM.

PART 3 - EXECUTION

3.1 WORKER PROTECTION

A. General:

1. Asbestos abatement work will be performed in accordance with current OSHA standards 29 CFR 1910.1001, 29 CFR 1926.1101, and current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011), and as specified herein.
2. The ASBESTOS ABATEMENT SUBCONTRACTOR shall provide all authorized visitors with protective clothing, headgear, eye protection, footwear, and hard hats as in the procedures described herein and afford them the use of all facilities to hold them free of contamination of asbestos fibers.
3. All authorized visitors shall be responsible for providing their own respirators with current copies of their medical clearance and fit test records prior to being allowed to enter the containment.
4. The ASBESTOS ABATEMENT SUBCONTRACTOR shall provide the decontamination and work procedures to be followed by workers, as well as the results of the personal air monitoring. This information must be posted outside of the clean room.

B. Respiratory Protection:

1. Respiratory protection will be worn by all persons potentially exposed to asbestos from the initiation of the asbestos abatement project until all areas have been given clearance. Clearance will be obtained by visual observation and air monitoring conducted by the APM.
2. Personal samples will be collected within the worker's breathing zone. Personal sampling will be the responsibility of the ASBESTOS ABATEMENT SUBCONTRACTOR. Personal sampling results will be available on site no later than 24 hours after sampling.
3. The filters provided for respirators used during this work will be NIOSH approved for asbestos fibers.

C. Protective Clothing:

1. The ASBESTOS ABATEMENT SUBCONTRACTOR shall provide to all workers, foreman and superintendents, protective disposable clothing consisting of full body coveralls, head covers, gloves and 18-inch-high boot-type covers, and reusable footwear.
2. The ASBESTOS ABATEMENT SUBCONTRACTOR shall provide eye protection and hard hats as required by job conditions and safety regulations.

3. Reusable footwear, hard hats, and eye protection devices will be left in the "contaminated equipment room" until the end of the asbestos abatement work.
4. Upon completion of asbestos abatement, the footwear will be disposed of as contaminated waste or cleaned thoroughly inside and out using soap and water before removing it from the work area or from the equipment and access area.
5. All disposable protective clothing will be discarded and disposed of as asbestos waste when the wearer exits from the workspace to the outside through the decontamination facilities.
6. The color of the disposable clothing worn outside the work area will be a different color than the disposable clothing worn inside the work area.

3.2 DECONTAMINATION FACILITY

- A. For each abatement area the ASBESTOS ABATEMENT SUBCONTRACTOR shall provide decontamination facilities located in an area established in the Asbestos Abatement Design.
- B. The decontamination facility will be constructed and maintained as specified herein and in compliance with current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011)

3.3 MAINTENANCE OF THE WORK AREA

- A. The ASBESTOS ABATEMENT SUBCONTRACTOR shall maintain the work area as specified herein and in compliance with current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011).

3.4 ASBESTOS CONTROL AREA CONSTRUCTION

- A. The ASBESTOS ABATEMENT SUBCONTRACTOR shall prepare and maintain the asbestos control area (e.g., the Containment Area) as necessary to perform the work specified herein and in compliance with current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011).
- B. The ASBESTOS ABATEMENT SUBCONTRACTOR shall prepare and maintain the asbestos control area (e.g., the Containment Area) as necessary to perform the work specified herein and in compliance with current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011).

3.5 ACM ABATEMENT METHODS

- A. ACM Removal:
 1. The ASBESTOS ABATEMENT SUBCONTRACTOR shall conduct ACM removal as specified herein and in compliance with current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011).
 2. The ASBESTOS ABATEMENT SUBCONTRACTOR shall be responsible for obtaining work practice variances from MDEP as necessary to complete the work.

3.6 FINAL CLEANUP AND INSPECTION PROCEDURE

- A. Each work area will be evaluated for completion following the removal of visible residue from surfaces of equipment, floors and walls, and the removal of containers and equipment. Waste containers (except those containers necessary for waste from final

cleanup) will be packed, cleaned, and removed from the work area prior to final cleanup and monitoring. This evaluation will be completed by the ASBESTOS ABATEMENT SUBCONTRACTOR's Supervisor, subsequent to the completion of successful asbestos abatement clearance inspection, sampling, and analysis for each work area.

Visual evaluation protocol will include:

1. Entering the work area where the abatement/clean-up/remediation activity was performed.
2. Inspection of the surfaces from which ACM and associated residue was removed.
3. Examination of the permanent features within the work area such as walls, floors, ceilings, conduits, pipes, tanks, etc., and attempting to determine whether residual materials or visible debris is present.
4. Examination of the decontamination and waste-load out facilities and observe whether residual material or visible debris is present. The waste will be evaluated to determine proper containerization and labeling.

- B. The ASBESTOS ABATEMENT SUBCONTRACTOR shall re-clean if necessary and the area re-inspected.
- C. The ASBESTOS ABATEMENT SUBCONTRACTOR is responsible for providing final asbestos abatement clearance inspection, sampling, and analysis for each work area. Clearance inspections, sampling, and analysis will be performed in accordance with MDEP regulations by an independent, MDEP licensed APM.
- D. After an area passes the clearance inspection, sampling, and analysis, the work area may be deregulated.

3.7 WASTE DISPOSAL

- A. All waste material shall be properly handled, wetted, containerized, and disposed of in accordance with current MDEP Asbestos Management Regulations, 06-096 C.M.R. Chapter 425 (2011). The ASBESTOS ABATEMENT SUBCONTRACTOR shall count or measure the volume of each filled container leaving the work area and will maintain a written record of such.
- B. Warning labels, having waterproof print and permanent adhesive, will be affixed to the sides of all waste bags or transfer containers. Warning labels will be conspicuous and legible and in accordance with 29 CFR 1926.1101.
- C. Removal of waste (both asbestos and non-asbestos wastes) from the work area will be completed prior to the end of each work shift. Project related waste will not be allowed to accumulate in the work area.
- D. Once a dumpster or waste container is full, the ASBESTOS ABATEMENT SUBCONTRACTOR shall arrange for transportation to the landfill, or to a pre-designated and approved off-site temporary location. Waste will not remain on-site longer than five days following completion of asbestos abatement activities.
- E. Waste Transportation and Disposal Regulations:
 1. It is the responsibility of the ASBESTOS ABATEMENT SUBCONTRACTOR to determine and ensure compliance with the current waste handling regulations applicable to the work site and the current regulations for waste transportation to and

disposal at each ultimate landfill. The ASBESTOS ABATEMENT SUBCONTRACTOR shall comply fully with these regulations and with all U.S. Department of Transportation (DOT) and U.S. Environmental Protection Agency (USEPA) requirements.

2. If required, the ASBESTOS ABATEMENT SUBCONTRACTOR (or Subcontractor), at no additional cost, will maintain a valid hazardous waste transporter's permit and identification number, and will document and fully comply with any hazardous waste manifesting requirements.
 3. The ASBESTOS ABATEMENT SUBCONTRACTOR shall provide legal transportation of this waste to the ultimate disposal landfill and will have the waste hauler and landfill owner complete all other required manifests, dump slips, or other forms. The completed original of the Waste Shipment Record and copies of the other forms will be sent to the OWNER within five calendar days.
 4. Waste may be transported to and temporarily stored at a pre-approved off-site storage area owned by the ASBESTOS ABATEMENT SUBCONTRACTOR, but it must ultimately be disposed of at the specified landfill before any payments are made.
- F.* Waste Disposal Fees: All contaminated waste handling costs, such as waste packaging, on-site/off-site storing and handling, transport and disposal, permitting, recordkeeping, and non-contaminated waste handling, must be included in the ASBESTOS ABATEMENT SUBCONTRACTOR'S proposal or bid as applicable to removal of asbestos materials and/or performance of the related abatement activities.

END OF SECTION

SECTION 211000

FIRE-SUPPRESSION SPRINKLER SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. The fire protection system scope shall provide extensions and alterations to the existing automatic sprinkler system as required to facilitate the renovations. The revisions and alterations shall include but not necessarily be limited to the following:
 - 1. Revisions to the existing head layout at the exterior soffit area to facilitate removal of the existing soffit and installation of a new insulated soffit.
 - 2. Revisions to the sprinkler routing and head placement as required to facilitate the addition of interior soffits to accommodate duct routing, refer to Fire Protection and Architectural drawings for soffit locations.
 - 3. Extend sprinkler coverage within the former Rifle Range (currently Housekeeping Storage) to provide complete coverage throughout the space.
 - 4. Add supervised valves with tamper switches as noted on the Fire Protection Drawings to facilitate zoned sprinkler shutdown in construction areas while maintaining full sprinkler protection throughout the occupied sections of the facility.
- B. All work shall be completed in a manner that maintains complete protection for the facility, in accordance with NFPA 13, local, and State requirements.
- C. Sprinkler coverage shall be maintained at owner occupied sections of the facility at all times, except for limited shutdowns as strictly scheduled with Maine Maritime Academy, limited to one half of one floor at a time, as required to complete alterations within the construction area as specified herein.
- D. This Section includes fire-suppression sprinklers, piping, and equipment.
- E. The Sprinkler Contractor shall place the sprinkler system in service and hand over the sprinkler system to the General Contractor for care and maintenance.
- F. Performance and Design Criteria: Provide products and systems complying with specific performance and design criteria indicated.

1.3 SYSTEM PERFORMANCE REQUIREMENTS

- A. Design sprinklers and obtain approval from authorities having jurisdiction. The design of the automatic sprinkler system shall be complete with all necessary accessories for proper operation.
- B. The system shall be hydraulically calculated in accordance with all provisions of the Contract Documents and any authority having jurisdiction.
- C. The contract documents do not include a fire pump. Provide over-sized piping as required to meet required system hydraulics. Contractor shall review the civil plans, the existing site and existing fire flow data. If the contractor or authority with jurisdiction determines that a fire pump is required: Provide in accordance with NFPA 20, "Stationary Pumps for Fire Protection," for fire pumps, drivers, controllers, accessories, and their installation.
- D. Design sprinkler piping according to the following and obtain approval from authorities having jurisdiction:
 - 1. Include a 5 percent margin of safety for available water flow and pressure.
 - 2. Include losses through water-service piping, valves, and backflow preventers.
- E. Sprinkler Occupancy Hazard Classifications:
 - 1. Light Hazard:
 - a. Office and Public Areas
 - b. Corridors
 - c. Residential living areas
 - 2. Ordinary Hazard, Group 1:
 - a. General Storage Areas
 - b. Mechanical Equipment Rooms
 - c. Building Service Areas.
 - d. Electrical Equipment Rooms
 - e. Laundry areas
- F. Minimum Density for Automatic-Sprinkler Piping Design shall be in accordance with NFPA 13. Maximum Protection Area per Sprinkler shall be in accordance with NFPA 13.

1.4 GENERAL REQUIREMENTS

- A. Components and Installation: Capable of producing piping systems with 175-psig minimum working-pressure rating, unless otherwise indicated.
- B. Seismic Performance: If required by the authority with jurisdiction, fire-suppression piping shall be capable of withstanding the effects of earthquake motions determined according to NFPA 13.
- C. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with fire stop materials. Refer to Division 7 for materials. Seal all penetrations through fire-or smoke-rated wall, partition, ceiling, or roof

assemblies with firestopping system. Refer to Architectural plans for location of rated assemblies.

- D. Contractor shall obtain and pay for required permits.
- E. Any hot work operations that are performed during this project shall be permitted by use of the FM Global Hot Work Permit System. The FM Global Hot Work Permit System shall be used to supervise all hot work operations (cutting, welding, brazing, grinding, soldering, etc.,) performed outside of any designated welding areas. A written policy statement shall specify who has the authority to issue permits on all shifts. In addition, a constant fire watch shall be continued for 1 hr. after work is completed and the area shall be monitored for an additional 3 hrs. after that.

1.5 SUBMITTALS

- A. Shop Drawings: Submit working plans, prepared according to NFPA 13, and hydraulic calculations with cross reference to applicable drawings, water supply data, and equipment schedule with ratings for the system to the Owner's Representative, Insurance Underwriter, and other authorities having jurisdiction.
- B. Product Data: Catalog sheets, specifications, and installation instructions. Indicate UL or FM approval for each product. Include the following additional information:
 - 1. Pipe and fitting materials and methods of joining for sprinkler piping.
 - 2. Pipe hangers and supports.
 - 3. Piping seismic restraints.
 - 4. Valves, including specialty valves, accessories, and devices.
 - 5. Alarm devices. Include electrical data.
 - 6. Electrical Devices: Complete description of intended use, wiring diagrams, data plate information and, in the case of switching devices, whether normally on or normally off. Include motor test data.
 - 7. Mechanical Devices: Complete description of intended use, including normal operating capacities and working pressures.
 - 8. Enclosures: Dimensions, materials, gages of metals; type of door hinges and locks, and methods of securing the enclosure members to the building construction.
 - 9. Hose Threads: Verify that hose threads on fire department connections match threads on equipment used by the local or servicing fire department.
- C. Design Data: The portions of the sprinkler system not sized on the Contract Drawings shall be sized in accordance with NFPA requirements for Hydraulically Designed Systems. Submit drawings and hydraulic calculations for approval.
- D. Delegated-Design Submittal: In addition to Shop Drawings, Product Data, and other required submittals, submit three copies of a statement, signed and sealed by the responsible sprinkler system design professional. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Certification: Submit Contractor's NICET certification and number or PE license number.
- E. Field Test Reports and Certificates: Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13. Include "Contractor's Material and Test Certificate for Aboveground Piping" and "Contractor's Material and Test Certificate for Underground Piping."
- F. Maintenance Data: For each type of sprinkler specialty to include in maintenance manuals specified in Division 1.

1.6 QUALITY ASSURANCE

A. Sprinkler Contractor

1. Installer Qualifications: An experienced installer who has designed and installed fire-suppression piping similar to that indicated for this Project and obtained design approval and inspection approval from authorities having jurisdiction.
2. Engineering Responsibility: Preparation of working plans, calculations, and field test reports by a qualified sprinkler designer. Sprinkler designer shall be legally qualified and licensed to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of fire-suppression piping that are similar to those indicated for this Project in material, design, and extent.
3. Contractor shall be a licensed fire sprinkler contractor.

B. Manufacturer Qualifications:

1. Firms whose equipment, specialties, and accessories are listed by product name and manufacturer in UL's "Fire Protection Equipment Directory" and FM's "Fire Protection Approval Guide" and that comply with other requirements indicated.
2. Sprinkler Components: Listing/approval stamp, label, or other marking by a testing agency acceptable to authorities having jurisdiction.
3. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction.
4. Factory Mutual Engineering Corporation (FM) Approval Guide

C. NFPA Requirements: Year edition per authority of jurisdiction.

1. NFPA #1: Fire Prevention Code
2. NFPA #13: Standard for the Installation of Sprinkler Systems
3. NFPA #101: Life Safety Code

1.7 COORDINATION

- A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for fire-suppression installations.
- B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- C. Coordinate requirements for access panels and doors for fire-suppression items requiring access that are concealed behind finished surfaces. Access panels and doors are specified in Division 8.
- D. Coordinate sprinkler head layout with all other trades.

1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents. Sprinkler Cabinets: Finished, wall-mounting steel cabinet and hinged cover, with space for a minimum of six spare sprinklers plus sprinkler wrench. Include the number of sprinklers required by

NFPA 13 and wrench for sprinklers. Include separate cabinet with sprinklers and wrench for each type of sprinkler on Project.

PART 2 - PRODUCTS

2.1 PIPING

- A. Pipe and fittings shall conform to the requirements of NFPA 13. Pipe shall be listed by UL and be FM approved, and installed per its listing and approval.
- B. Wet sprinkler piping shall be:
 - 1. Black steel Schedule 40 for 1 inch and smaller, and Schedule 10 for 1-½ inch and larger.
- C. System piping shall be substantially supported to the building structure. The installation of hangers and supports shall adhere to the requirements set forth in N.F.P.A. 13. Materials used in the installation or construction of hangers and supports shall be listed and approved for such application.
- D. Provide joining materials in accordance with NFPA 13.
- E. Transition Couplings: AWWA C219, sleeve type, or other manufactured fitting the same size as, with pressure rating at least equal to, and with ends compatible with piping to be joined.

2.2 SPRINKLERS

- A. Fire sprinklers shall be of one manufacturer throughout the building. No mixing of sprinkler brands shall be permitted. Sprinklers shall be of all brass frame construction with a quick response frangible bulb type fusible element.
- B. Automatic Sprinklers: With U.L. listed heat-responsive elements.
- C. Sprinkler Types and Categories: Provide per NFPA 13.
- D. Provide quick response sprinklers.
- E. Institutional Semi-Recessed or "Vandal-Resistant" sprinkler heads as required by application.
- F. Sprinkler Escutcheons: Materials, types, and finishes of sprinklers. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.
- G. Sprinkler Guards: Wire-cage type, including fastening device for attaching to sprinkler.

2.3 SPRINKLER SPECIALTY FITTINGS

- A. Sprinkler specialty fittings shall be UL listed or FMG approved, with 175-psig minimum working-pressure rating, and made of materials compatible with piping.
- B. Sprinkler Drain and Alarm Test Fittings: Cast- or ductile-iron body; with threaded or locking-lug inlet and outlet, test valve, and orifice and sight glass.

- C. Sprinkler Branch-Line Test Fittings: Brass body with threaded inlet, capped drain outlet, and threaded outlet for sprinkler.
- D. Sprinkler Inspector's Test Fitting: Cast- or ductile-iron housing with threaded inlet and drain outlet and sight glass.
- E. Drop-Nipple Fittings: UL 1474, adjustable with threaded inlet and outlet, and seals.
- F. Contractor Option: Provide flexible sprinkler hose with fittings intended for use in sprinkler systems between the branch line and sprinkler. Provide in accordance with NFPA 13 and the manufacturer's installation instructions. Length: 38".
 - 1. U.L. 2443 listed for sprinkler hose application.
 - 2. Flexible Hose: Corrugated Stainless Steel AISI 304
 - 3. Slip Nuts: Brass C3771BC
 - 4. Reducer Fitting: Yellow Zinc/Steel SPPS
 - 5. Special Shoulder Nipple (Inlet): Yellow Zinc/Steel SPPS
 - 6. Reducing Nipple Clamp & Bolt: Galvanized Steel SS41
 - 7. Maximum Working Pressure of Flexible Connection: 200 PSI
 - 8. Test Pressure of Flexible Connection: 400 PSI
 - 9. Maximum Temperature Rating of Flexible Connection: 300 °F
 - 10. Provide ceiling bracket.

2.4 VALVES

- A. Valves shall be UL listed and FMG approved
- B. An NFPA-13 compliant setup including a backflow device, system control valve, flow switch, inspectors test, drain, and pressure gauge may be provided in lieu of an alarm valve.

2.5 WATERFLOW ALARMS

- A. Flow of water equal to or greater than that from a single automatic sprinkler (smallest orifice in system) shall result in an audible alarm on the premises within 5 minutes after such flow begins and until such flow stops.
- B. The alarm apparatus shall consist of a listed alarm check valve or other listed waterflow-indicating device with the necessary attachments to give an alarm.
- C. The apparatus for a dry pipe system shall consist of alarm attachments to the dry pipe valve.

PART 3 - EXECUTION

3.1 EXISTING SYSTEMS

- A. Refer to Division 1 demolition requirements and procedures. Disconnect, demolish, and remove fire-suppression systems, equipment, and components indicated to be removed.
- B. Existing Sprinkler System Shutdown: Follow NFPA 13 and NFPA 25 recommendations. Before shutting down the sprinkler system to perform the Work, notify the Owner's Representative in

writing, the local fire department, and the alarm company, that the system is to be shut down temporarily. Give schedule which states date and time of proposed shut down and the approximate length of time that the system will be out of service. Request instructions for precautions that should be taken during the shutdown period. Do not shut down the system until schedule is approved by the Owner's Representative. Return the existing system to pre-shutdown operation immediately after the Work has been completed. Give written notice to the Director's Representative that the system has been returned to pre-shutdown operation.

3.2 PREPARATION

- A. The nature of the work requires coordination with other trades. Shop fabrication shall be done at the Contractor's risk. Relocation of piping and components to avoid obstructions may be necessary. Relocation, if required, shall be done at the Contractor's expense. The installation shall be performed in a workmanlike manner as determined by the Owner's Representative and in accordance with the Contract Documents, manufacturer's printed installation instructions, and submitted and Owner's Representative reviewed drawings.

3.3 SPRINKLER APPLICATIONS

- A. General: Use sprinklers according to the following applications:
1. Rooms/spaces without Ceilings: Upright sprinklers.
 2. All occupied rooms with Finished Ceilings: Recessed Pendent.
 3. Provide sprinkler guards for heads in mechanical and storage spaces, less than 8 ft. above finished floor subject to mechanical damage.
 4. Low ceilings (under 8 feet): Concealed
 5. Electrical or Data Rooms with finished ceilings: Concealed
 6. Electrical or Data Rooms without ceilings: Provide guard.
 7. Wall Mounting: Sidewall sprinklers.
 8. Special Applications: Use extended-coverage, flow-control, and quick-response sprinklers where indicated.
- B. Finishes
- a. Unfinished spaces not exposed to view: rough bronze.
 - b. Recessed Sprinklers: White
 - c. Provide escutcheons with matching color for finished spaces.

3.4 SYSTEM INSTALLATIONS

- A. Earthquake Protection: Provide piping according to NFPA 13 to protect from earthquake damage.
- B. Water supply control valves shall be electrically supervised and mechanically locked for proper position. Water flow and supervisory circuits shall be in accordance with the requirements of electrical specifications. Electric connections to sprinkler system shall be by Division 26. Furnish wiring diagrams for all equipment.
- C. A sprinkler head wrench of each style and model installed shall be provided to the owner at the completion of the project. A representative sampling of each sprinkler head style and model

shall be provided to the owner and housed in a sprinkler head cabinet at or near the sprinkler riser. The number of sprinkler heads provided to the owner shall be in accordance with NFPA 13.

- D. Provide "Inspector's Test Connections" in sprinkler system piping, complete with shutoff valve, sized and located according to NFPA 13
- E. Provide a vent near a high point in the system to allow air to be removed from that portion of the system.

3.5 SPRINKLER INSTALLATION

- A. Provide sprinklers in suspended ceiling in center of all ceiling tiles.
- B. Do not install pendent or sidewall, wet-type sprinklers in areas subject to freezing. Use dry-type sprinklers with water supply from heated space per NFPA 13.
- C. Provide sprinkler piping with drains for complete system drainage.
- D. Hangers and Supports: Comply with NFPA 13 for hanger materials.

3.6 LABELING AND IDENTIFICATION

- A. Provide labeling and pipe markers on equipment and piping according to requirements in NFPA 13.

3.7 FIELD QUALITY CONTROL

- A. Flush, test, and inspect sprinkler piping according to NFPA 13, "System Acceptance" Chapter.
- B. Verify that specialty valves, trim, fittings, controls, and accessories are installed and operate correctly.
- C. Verify that specified tests of piping are complete.
- D. Verify that damaged sprinklers and sprinklers with paint or coating not specified are replaced with new, correct type.
- E. Verify that sprinklers are correct types, have correct finishes and temperature ratings, and have guards as required for each application.
- F. Verify that potable-water supplies have correct types of backflow preventers.
- G. Verify that fire department connections have same type compatible with local fire department equipment.
- H. Replace piping system components that do not pass test procedures and retest to demonstrate compliance. Repeat procedure until satisfactory results are obtained.
- I. Fill wet-pipe sprinkler piping with water.

- J. Energize circuits to electrical equipment and devices.
- K. Coordinate with fire alarm tests. Operate as required.

3.8 CLEANING

- A. Clean dirt and debris from sprinklers.
- B. Remove and replace sprinklers having paint other than factory finish.
- C. Clean and disinfect fire-suppression water-service piping as follows:
 - 1. Purge new piping systems and parts of existing systems that have been altered, extended, or repaired before use.
 - 2. Use purging and disinfecting procedure prescribed by authorities having jurisdiction or, if method is not prescribed by authorities having jurisdiction, use procedure described in NFPA 24 for flushing of piping. Flush piping system with clean, potable water until dirty water does not appear at points of outlet.
 - 3. Use purging and disinfecting procedure prescribed by authorities having jurisdiction or, if method is not prescribed by authorities having jurisdiction, use procedure described in AWWA C651.
 - 4. Prepare reports.

3.9 PAINTING

- A. Painting of fire-suppression systems, equipment, and components is specified in Division 9.
- B. Damage and Touchup: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.10 PROTECTION

- A. Protect sprinklers from damage until Substantial Completion.

END OF SECTION



HALEY WARD

ENGINEERING | ENVIRONMENTAL | SURVEYING

HAZARDOUS MATERIALS ASSESSMENT

FOR

MAINE MARITIME ACADEMY
CURTIS HALL
CASTINE, MAINE

Prepared For: CHA Architecture, P.C.
49 Dartmouth Street
Portland, Maine 04101

CONTRACTOR COPY

Corporate Office


One Merchants Plaza
Suite 701
Bangor, ME 04401
T: 207.989.4824
F: 207.989.4881

HALEYWARD.COM

SEPTEMBER 19, 2023
JN: 13150.007

Report Prepared By:
Haley Ward, Inc.

One Merchants Plaza, Suite 701 | Bangor, Maine 04401



EXECUTIVE SUMMARY

Haley Ward, Inc. (Haley Ward) completed a limited Hazardous Materials Assessment (HMA) on August 25, 2023, to identify and assess hazardous materials on or within Curtis Hall located on the Maine Maritime Academy campus in Castine, Maine.

This assessment was completed to identify and assess Asbestos-Containing Materials (ACM), Lead-Based Paint (LBP)/lead-containing surface coatings, and Potential Universal Wastes/hazardous materials which would require special handling and disposal or would be regulated prior to or during the planned renovations of the structure as identified on CHA Architecture, P.C. (CHA) Demolition Floor Plans, dated March 24, 2023.

Previously-identified ACM included the following:

- Twelve-inch by twelve-inch (12x12) white floor tile and associated adhesive.

Additional ACM identified during this limited renovation impact survey includes:

- Pipe insulation and associated mud pipe fittings (Boiler room)
- Mud pipe fitting insulation on fiberglass-insulated lines
- Tank insulation (Boiler room)
- 12x12 dark brown mottled floor tile and associated adhesive
- Exterior caulk associated with windows
- Rope gasket
- Vapor barrier
- Floor tile adhesive beneath non-ACM floor tile

LBP/Lead-Containing Surface Coatings

LBP/Lead-containing surface coatings were identified on the interior of the building including:

- Structural steel

LBP/lead-containing surface coatings present on interior surfaces of the building were observed to be in fair condition.

Potential Hazardous Materials/Wastes and Universal Wastes

The following potential Hazardous Materials/Wastes and Universal Wastes were identified on the interior of the building:

- Fluorescent light bulbs
- Fluorescent light ballasts
- Emergency exit signs/batteries
- Mercury-containing thermostats




TABLE OF CONTENTS

	Page
EXECUTIVE SUMMARY	1
1.0 INTRODUCTION.....	1
2.0 ASBESTOS-CONTAINING MATERIALS.....	2
2.1 Asbestos Renovation Impact Survey	2
2.2 Asbestos Sampling Results	4
3.0 LEAD-BASED PAINT/LEAD-CONTAINING SURFACE COATING DETERMINATION	4
4.0 POTENTIAL UNIVERSAL AND/OR HAZARDOUS MATERIALS/WASTES	6
5.0 CONCLUSIONS AND RECOMMENDATIONS	6
6.0 REPORT CERTIFICATION.....	8

FIGURES


H100	Hazardous Materials Assessment – Ground Floor
H101	Hazardous Materials Assessment – First Floor
H102	Hazardous Materials Assessment – Second Floor
H103	Hazardous Materials Assessment – Third Floor
H104	Hazardous Materials Assessment – Fourth Floor

TABLES

Table 1	Summary of Identified Asbestos-Containing Materials
Table 2	Hazardous Materials Inventory

APPENDICES

Appendix A	Asbestos and Lead-Based Paint Risk Assessor Certifications
Appendix B	Asbestos Analytical Laboratory Certifications
Appendix C	Asbestos Laboratory Analytical Results
Appendix D	Photographic Log



1.0 INTRODUCTION


Haley Ward, Inc. (Haley Ward) completed a limited Hazardous Materials Assessment (HMA) on August 25, 2023, to identify and assess hazardous materials on or within Curtis Hall located on the Maine Maritime Academy (MMA) campus in Castine, Maine. Curtis Hall is a five-story residence hall, constructed of masonry and steel, with dormitory rooms, student lounges, laundry facilities, bathrooms, and utility closets on the upper four floors. The ground floor contains the bookstore, recreation facilities and utility rooms with the first floor supporting the Administrative Offices and student and health services. The building includes an Ethylene Propylene Diene Monomer (EPDM) membrane roof system.

The HMA was completed to identify and assess Asbestos-Containing Materials (ACM), Lead-Based Paint (LBP)/lead-containing surface coatings, and Potential Universal Wastes/hazardous materials which would require special handling and disposal or would be regulated prior to or during the planned renovations of the structure as identified on CHA Architecture, P.C. (CHA) Demolition Floor Plans, dated March 24, 2023. The scope of the planned renovation work includes upgrades to mechanical, plumbing, electrical, fire protection, and heating systems and improvements to the building envelope including the roof, windows, and exterior cladding.

Curtis Hall was partially occupied by residents at the time of the survey. Haley Ward coordinated with MMA to identify unoccupied residential units and evaluated approximately twenty five percent of the residential units within the building. Haley Ward also evaluated accessible ceiling plenums, sink enclosures, and access panels in hallways, restrooms, utility closets, and mechanical spaces on each of the floors to determine the existence of suspect ACM.

Haley Ward observed the following:

- Heating and plumbing piping were visible from the ceiling plenums. The piping was observed to be uninsulated or covered with fiberglass insulation.
- In some cases, plumbing piping extended into concrete masonry unit (CMU) most of which was uninsulated or covered with fiberglass. The piping extends approximately one foot into the CMU block and is sealed with concrete.
- Elbows within the ceiling plenum are either uninsulated, covered with vinyl fitting covers, or mud fitting insulation. Based on the analytical results, mud fitting insulation, sampled in various locations throughout the facility, was identified as asbestos-containing. The mud fitting insulation should be assumed as ACM unless proven otherwise through additional sampling and analysis.
- Haley Ward accessed the enclosures beneath the sinks in the restrooms and observed uninsulated piping.



- Fiberglass-insulated piping extends out into the plaster-covered soffit, running adjacent to the building frame.

2.0 ASBESTOS-CONTAINING MATERIALS

2.1 Asbestos Renovation Impact Survey


An asbestos renovation impact survey was conducted in accordance with the Maine Department of Environmental Protection (MDEP) Asbestos Management Regulations (06-096 C.M.R. Chapter 425, 2011) to provide information regarding the presence of ACM within the interior and on the exterior of the building. Ms. Suzanne Yerina and Ms. Deborah Kasik, licensed MDEP Asbestos Inspectors, performed the field survey. A copy of Ms. Yerina's and Ms. Kasik's Asbestos Inspector certifications is included in **Appendix A**.

Completion of the asbestos renovation impact survey included:

- Visual identification of suspect ACM on the interior and/or exterior of the building.
- Assignment of room numbers for sample and identified ACM location(s).
- Collection of 160 bulk samples of suspected ACM in accordance with MDEP regulations.
- Quantification of ACM identified by laboratory analysis.

As with any scientific study, an asbestos renovation impact survey is subject to a variety of limitations. Limitations to be considered when interpreting the results of the survey performed on the structure include the following:

- An asbestos renovation impact survey may not be able to identify all ACM present throughout a facility.
- Variations in building materials used during construction and subsequent renovations.
- Inaccessible rooms and areas within wall cavities, under floors, and above solid ceilings.
- Sampling of the EPDM roof systems was not included in the scope of work for the property, due to accessibility, roof system type (EPDM), and repair requirements. Haley Ward could not determine if the original roof system was removed prior to the installation of the EPDM roof system. Typically, flat, asphalt built-up roof systems are considered suspect ACM. Should the roof system be impacted by future renovations, the presence of the original roof should be identified and, if present, should be sampled to determine if ACM.




A total of one hundred sixty (160) samples of identified suspect ACM were collected from the interior and exterior of the building, including:

- Plaster ceiling material
- Gypsum wall and ceiling material
- Mud pipe fitting insulation on fiberglass-insulated lines
- Pipe insulation and associated mud pipe fittings
- Tank insulation
- Twelve types of floor tiles and associated adhesives
- Flooring adhesive
- Two types of sheet flooring
- Five types of ceiling tiles
- Wall panel adhesive
- Glue daubs
- Carpet adhesive
- Rope gasket
- Firestop caulk
- Vapor barrier
- Joint compound used as surfacing material
- Exterior soffit ceiling plaster
- Exterior column skim coat
- Exterior window glazing
- Exterior caulk associated with windows

The number of samples collected was determined by the number of homogeneous sampling areas identified by the inspector. A homogeneous area is an area which, based on the inspector's judgment, contains materials that are uniform in color and texture and are present on similar building or utility components.

Bulk samples of suspect ACM collected during the survey of the building were submitted to EMSL Analytical, Inc. (EMSL) of South Portland, Maine for analysis. Bulk samples were analyzed using the MDEP required analytical methods: "PLM-EPA 600/R-93/116" (for surfacing, thermal system insulation, and cementitious materials), and "PLM NOB-EPA 600/R-93/116" (for non-friable organically bound materials (NOBs)) (e.g., floor tile, adhesives, and roofing) with "gravimetric reduction." EMSL's laboratory is certified to perform asbestos analysis by both the National Voluntary Laboratory Accreditation Program (NVLAP) and the American Industrial Hygiene Association (AIHA). EMSL is a MDEP licensed Asbestos Analytical Laboratory. Copies of EMSL's laboratory certifications are included as **Appendix B**. Laboratory analytical results and chain of custodies are included as **Appendix C**.



2.2 Asbestos Sampling Results

According to MDEP regulations, locations and occurrences of materials that tested positive and are homogenous in nature (similar in color and texture) are considered as ACM provided the material contains greater than or equal to (\geq) one percent asbestos based on laboratory analysis. A material can only be considered negative for asbestos if analytical results from all bulk samples in a group of samples representing that material indicate an asbestos content of less than one percent ($<1\%$).


ACM identified by laboratory analysis included:

- Pipe insulation and associated mud pipe fitting insulation
- Mud pipe fitting insulation on fiberglass-insulated lines
- Tank insulation
- 12x12 dark brown mottled floor tile and associated adhesive
- Flooring adhesive
- Exterior caulk
- Rope gasket
- Vapor barrier

A summary of identified asbestos and locations are included in **Table 1**. Sample locations and locations of identified ACM are included in **Figures H100 through H104**.

3.0 LEAD-BASED PAINT/LEAD-CONTAINING SURFACE COATING DETERMINATION

An LBP/lead-containing surface coating determination was conducted by Ms. Deborah A. Kasik, a MDEP certified Lead Risk Assessor. A copy of Ms. Kasik's Lead Risk Assessor certification is included in **Appendix A**. The purpose of the determination was to identify LBP/lead-containing surface coatings, if present, on the interior and/or exterior surfaces of the building. The LBP determination was performed in accordance with the established protocols outlined in the MDEP Lead Management Regulation (06-096 C.M.R. Chapter




424 § 7, 2021) and as applicable to this project. The testing provides information on the lead content and an assessment of the condition of the surfaces tested.

The LBP/lead-containing surface coating testing was conducted using a portable X-Ray Fluorescence (XRF) Lead Paint Analyzer (RMD LPA-1), which non-destructively tests for the presence of LBP or other lead-containing surface coatings. The XRF analyzer is licensed with the Maine Department of Human Services Radiation Control Program and operated in accordance with all applicable regulations and conditions of licensure. The determination as to whether a component contains lead is based upon the MDEP Lead Management Regulations. The MDEP defines a component as lead-containing if the XRF result is ≥ 1.0 milligrams per square centimeter (mg/cm^2). A visual assessment of the existing condition of the identified LBP was also completed at the time of the determination.

LBP/lead-containing surface coatings were identified on the structural steel supports of the building. A summary of the XRF results, by building material and including all floors, is outlined below.

**SUMMARY OF XRF RESULTS BY BUILDING COMPONENT
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE, MAINE**

BUILDING COMPONENTS	XRF READING CLASSIFICATION
Ceilings (sheetrock)	Negative
Walls (sheetrock, CMU block)	Negative
Floors	Negative
Doors and associated trim	Negative
Window units (brown) and associated trim	Negative
Piping	Negative
Window units (tan) and associated trim	Negative
Structural Steel Supports	Positive
Access panels	Negative
Ceramic tile walls	Negative
Baffles	Negative
Walls (concrete)	Negative
Exterior plaster ceiling	Negative
Exterior columns	Negative



4.0 POTENTIAL UNIVERSAL AND/OR HAZARDOUS MATERIALS/WASTES

The following potential Hazardous Materials/Wastes and Universal Wastes were identified within the building:

- Fluorescent light bulbs and associated light ballasts
- Emergency exit signs/batteries
- Mercury-containing thermostats

An estimated hazardous materials inventory and the associated removal costs is presented in **Table 3**.

5.0 CONCLUSIONS AND RECOMMENDATIONS

This investigation revealed the following relevant information:

ACM


ACM identified by laboratory analysis included:

- Pipe insulation and associated mud pipe fitting insulation (boiler room)
- Mud pipe fitting insulation on fiberglass-insulated lines
- Tank insulation (boiler room)
- 12x12 dark brown mottled floor tile and associated adhesive
- Exterior Caulk associated with windows
- Rope gasket
- Vapor barrier
- Floor tile adhesive beneath non-ACM floor tile

Previously-identified ACM included the following:

- 12x12 white floor tile and associated adhesive

Current state regulations require that identified ACM which may be impacted by planned renovation/demolition activity be removed by a MDEP licensed asbestos abatement contractor in accordance with applicable state and federal regulations prior to disturbance of ACM by such planned activities. In accordance with National Emissions Standards for Hazardous Air Pollutants (NESHAP) (40 CFR 61), and MDEP Asbestos Management Regulations, a contractor conducting a renovation and/or demolition activity that would disturb regulated ACM must: (1) notify the U.S. Environmental Protection Agency (USEPA) Administrator and the MDEP of such activities, (2) use proper removal procedures, (3) use proper engineering controls to limit emissions of asbestos



fibers, and (4) utilize proper waste disposal. If any hidden suspect ACM (behind walls, in chases, above permanent ceilings, etc.) is uncovered during renovation or demolition activities, work must be stopped, and the material tested for asbestos content. All ACM must be disposed of in accordance with all applicable state and federal requirements.

The building is constructed with a flat EPDM roof system and information as to whether the original roof system was removed or covered over by the EPDM roof system is not available. Should the roof system be impacted by future renovations, the presence of the original roof should be identified and, if present, should be sampled to determine if it's asbestos-containing.

Lead-Based Paint (LBP)/Lead-Containing Surface Coatings

LBP/lead-containing surface coatings were identified on the interior of Curtis Hall property including:

- Structural steel supports

LBP/lead-containing surface coatings present on interior surfaces of the building were observed to be in fair condition.

Potential Hazardous Materials/Wastes and Universal Wastes

The following potential Hazardous Materials/Wastes and Universal Wastes were identified within the building:

- Fluorescent light bulbs and associated light ballasts
- Mercury-containing thermostats
- Emergency exit signs/batteries

When removed from fixtures for disposal, fluorescent light bulbs are considered a Universal Waste and must be properly handled, packaged, and disposed of under current MDEP Universal Waste Rules (06-096 C.M.R. Chapter 858, 2018). Fluorescent light ballasts contain capacitors that may be filled with PCB-containing dielectric fluid. However, it is unknown whether such PCB-containing ballasts, considered a Universal Waste, are present in the building.

The recommended Best Management Practice (BMP) is to individually remove each light fixture and have individual ballasts evaluated to confirm the presence or absence of PCBs. Non-PCB light ballasts will be clearly labeled as not containing PCBs and may be disposed of as solid waste. If no such labeling is present, the ballast should be treated as PCB-containing and be segregated and handled as Universal Waste.



Emergency exit signs, light batteries, and mercury-containing thermostats should be removed and recycled or disposed of properly.

6.0 REPORT CERTIFICATION

This report was prepared and reviewed by Haley Ward for the use of CHA Architecture, P.C., and should not be reproduced without their full, written authorization.

Deborah A. Kasik

Project Scientist II

MDEP Certified Asbestos Inspector License No. AI-0177

MDEP Certified Lead Risk Assessor License No. LR-0003

Suzanne Yerina, L.G., P.G.

Senior Project Geologist

MDEP Certified Asbestos Inspector License No. AI-0451

Michael D. Sauda, MPH, CSP

Senior Project Manager

DAK/SLY/MDS/lmb
Attachments



FIGURES

- H100 – Ground Floor Plan
- H101 – First Floor Plan
- H102 – Second Floor Plan
- H103 – Third Floor Plan
- H104 – Fourth Floor Plan

CONTRACTOR COPY

PLAN REFERENCE:
FLOOR PLAN DERIVED FROM DRAWINGS BY OTHERS PROVIDED TO
HALEY WARD, INC AND ARE NOT WARRANTED AS TO ACCURACY AND
ARE INTENDED TO BE SCHEMATIC.


ASBESTOS LEGEND

- PH1-001A SAMPLE NUMBER AND LOCATION TESTING POSITIVE FOR ASBESTOS
- PH1-002A SAMPLE NUMBER AND LOCATION TESTING NEGATIVE FOR ASBESTOS
- PH-001B SAMPLE NUMBER AND LOCATION NOT ANALYZED (POSITIVE STOP)
- NON-ACM FLOOR TILE WITH ASSOCIATED ACM ADHESIVE
- ACM FLOOR TILE WITH ASSOCIATED ACM ADHESIVE
- ACM INSULATED PIPE EXPOSED
- ⊗-1 ACM INSULATED PIPE FITTING ABOVE CEILING
- X-3 ACM INSULATED PIPE FITTING
- ACM ASPHALT VAPOR BARRIER
- ACM TANK INSULATION

NOTE:
ALL EXTERIOR WINDOWS HAVE ASBESTOS CONTAINING CAULKING. (REFER TO SAMPLE PH1-030A)



CONTRACTOR COPY



GROUND FLOOR PLAN
SCALE: 1/16"=1'-0"

REV.	DATE	DESCRIPTION	BY	CHK.
NOT FOR CONSTRUCTION				
		HALEY WARD ENGINEERING ENVIRONMENTAL SURVEYING One Merchants Plaza, Suite 701 Bangor, Maine 04401 207.987.4824		
PROJECT CURTIS HALL Maine Maritime Academy, Castine, Maine 04421				
TITLE GROUND FLOOR PLAN HAZARDOUS MATERIAL ASSESSMENT				
DATE: 2023.09.14		SCALE: AS NOTED		
DRAWN BY: MEB	DESIGNED BY: DAK	CHECKED BY: DAK		
PROJECT No.: 13150.007				
DRAWING No.:		H100		


FILE LOCATION: P:\13150\CHA_ARCHITECTURE\07 MAIN CURTIS HALL - HMA - DRWG\CAD_FILES\ENVIRONMENTAL\13150.007 H100.DWG, 2023.09.14, 4:08 PM

PLAN REFERENCE:
FLOOR PLAN DERIVED FROM DRAWINGS BY OTHERS PROVIDED TO
HALEY WARD, INC AND ARE NOT WARRANTED AS TO ACCURACY AND
ARE INTENDED TO BE SCHEMATIC.

ASBESTOS LEGEND

- PH1-001A SAMPLE NUMBER AND LOCATION TESTING POSITIVE FOR ASBESTOS
- PH1-002A SAMPLE NUMBER AND LOCATION TESTING NEGATIVE FOR ASBESTOS
- ACM FLOOR TILE WITH ASSOCIATED ACM ADHESIVE
- ⊗-1 ACM INSULATED PIPE FITTING ABOVE CEILING

NOTE:
ALL EXTERIOR WINDOWS HAVE ASBESTOS
CONTAINING CAULKING. (REFER TO SAMPLE
PH1-036A)



CONTRACTOR COPY

FIRST FLOOR PLAN
SCALE: 1/16"=1'-0"


REV.	DATE	DESCRIPTION	BY	CHK.
NOT FOR CONSTRUCTION				
		HALEY WARD ENGINEERING ENVIRONMENTAL SURVEYING One Merchants Plaza, Suite 701 Bangor, Maine 04401 207.987.4824		
PROJECT MMA CURTIS HALL Maine Maritime Academy, Castine, Maine 04421				
TITLE FIRST FLOOR PLAN HAZARDOUS MATERIAL ASSESSMENT				
DATE: 2023.09.14		SCALE: AS NOTED		
DRAWN BY: MEB	DESIGNED BY: DAK	CHECKED BY: DAK		
PROJECT No.: 13150.007				
DRAWING No.: H101		REV.		

PLAN REFERENCE:
FLOOR PLAN DERIVED FROM DRAWINGS BY OTHERS PROVIDED TO
HALEY WARD, INC AND ARE NOT WARRANTED AS TO ACCURACY AND
ARE INTENDED TO BE SCHEMATIC.


ASBESTOS LEGEND

- PH1-001A SAMPLE NUMBER AND LOCATION
TESTING POSITIVE FOR ASBESTOS
- PH1-002A SAMPLE NUMBER AND LOCATION
TESTING NEGATIVE FOR ASBESTOS
- 1 ACM INSULATED PIPE FITTING ABOVE CEILING

NOTE:
ALL EXTERIOR WINDOWS HAVE ASBESTOS
CONTAINING CAULKING. (REFER TO SAMPLE
PH1-030A)



SECOND FLOOR PLAN
SCALE: 1/16"=1'-0"



REV.	DATE	DESCRIPTION	BY	CHK.
DRAWING ISSUE STATUS				
NOT FOR CONSTRUCTION				
		HALEY WARD		
ENGINEERING ENVIRONMENTAL SURVEYING				
One Merchants Plaza, Suite 701 Bangor, Maine 04401 207-987-4824				
PROJECT				
CURTIS HALL				
Maine Maritime Academy, Castine, Maine 04421				
TITLE				
SECOND FLOOR PLAN				
HAZARDOUS MATERIAL ASSESSMENT				
DATE		SCALE		
2023.09.14		AS NOTED		
DRAWN BY	DESIGNED BY	CHECKED BY		
MEB	DAK	DAK		
PROJECT No.		13150.007		
DRAWING No.		H102		

PLAN REFERENCE:
 FLOOR PLAN DERIVED FROM DRAWINGS BY OTHERS PROVIDED TO
 HALEY WARD, INC AND ARE NOT WARRANTED AS TO ACCURACY AND
 ARE INTENDED TO BE SCHEMATIC.


ASBESTOS LEGEND

- PH-002A SAMPLE NUMBER AND LOCATION TESTING NEGATIVE FOR ASBESTOS
- PH-001B SAMPLE NUMBER AND LOCATION NOT ANALYZED (POSITIVE STOP)
- ⊗-1 ACM INSULATED PIPE FITTING ABOVE CEILING

NOTE:
 ALL EXTERIOR WINDOWS HAVE ASBESTOS
 CONTAINING CAULKING. (REFER TO SAMPLE
 PH1-030A)



THIRD FLOOR PLAN
 SCALE: 1/16"=1'-0"


REV.	DATE	DESCRIPTION	BY	CHK.
DRAWING ISSUE STATUS				
NOT FOR CONSTRUCTION				
		HALEY WARD ENGINEERING ENVIRONMENTAL SURVEYING One Merchants Plaza, Suite 701 Bangor, Maine 04401 207.987.4824		
PROJECT				
CURTIS HALL Maine Maritime Academy, Castine, Maine 04421				
TITLE				
THIRD FLOOR PLAN HAZARDOUS MATERIAL ASSESSMENT				
DATE		2023.09.14		SCALE
DRAWN BY		MEB		AS NOTED
DESIGNED BY		DAK		CHECKED BY
PROJECT No.		13150.007		DAK
DRAWING No.		H103		REV.

PLAN REFERENCE:
FLOOR PLAN DERIVED FROM DRAWINGS BY OTHERS PROVIDED TO
HALEY WARD, INC AND ARE NOT WARRANTED AS TO ACCURACY AND
ARE INTENDED TO BE SCHEMATIC.

ASBESTOS LEGEND


- PH1-001A SAMPLE NUMBER AND LOCATION
TESTING POSITIVE FOR ASBESTOS
- PH-002A SAMPLE NUMBER AND LOCATION
TESTING NEGATIVE FOR ASBESTOS
- 1 ACM INSULATED PIPE FITTING ABOVE CEILING

NOTE:
ALL EXTERIOR WINDOWS HAVE ASBESTOS
CONTAINING CAULKING. (REFER TO SAMPLE
PH1-030A)



CONTRACT COPY

FOURTH FLOOR PLAN
SCALE: 1/16"=1'-0"

REV.	DATE	DESCRIPTION	BY	CHK.
NOT FOR CONSTRUCTION				
		HALEY WARD ENGINEERING ENVIRONMENTAL SURVEYING One Merchants Plaza, Suite 701 Bangor, Maine 04401 207.987.4824		
PROJECT MMA CURTIS HALL Maine Maritime Academy, Castine, Maine 04421				
TITLE FOURTH FLOOR PLAN HAZARDOUS MATERIAL ASSESSMENT				
DATE: 2023.09.14		SCALE: AS NOTED		
DRAWN BY: MEB	DESIGNED BY: DAK	CHECKED BY: DAK		
PROJECT No.: 13150.007				
DRAWING No.: H104		REV.		



TABLES

Table 1. Summary of Identified Asbestos-Containing Materials

Table 2. Hazardous Materials Inventory

CONTRACTOR COPY



**TABLE 1 | SUMMARY OF IDENTIFIED ASBESTOS CONTAINING MATERIALS (ACM) AND ESTIMATED QUANTITIES
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE, MAINE**

Room Section/Number	Sample #:	Pipe Insulation and Associated Mud Pipe Fittings (LF)	Tank Insulation (SF)	Mud Pipe Fittings Insulation on Fiberglass-insulated lines (EA)	Gasket on stored equipment (SF)	Asphalt Vapor Barrier (SF)	Floor Tile Adhesive beneath Non-ACM Floor Tile (SF)	Floor Tile and associated ACM adhesive (SF)	Exterior Caulk Associated with Window Frames (EA)	Comment
GROUND FLOOR										
Boiler Room - Mezzanine	PH1-002C PH1-003A	30								
	PH1-004A			25						
	PH1-005A		50							
Boiler Room	PH1-004A			26						
Electrical Room	PH1-004A			7						
Armory Chase	PH1-004A			10						
	PH2-043A					40				
Armory	PH2-043A					60				
Rifle Range (B34)	PH2-043A					180				
	PH2-041A				2					
Hallway (B10)	PH1-012A			4						Above ceiling files
The Bilge (G1)	PH4-047A						625			
Kitchen (G2)	PH4-047A						55			
Men's Room (G4)	PH1-012A			20						Chase inaccessible
Women (G5)	PH1-012A			5						located within a pipe enclosure
Bookstore Storage (G17)	PH1-012A			10						
Bookstore (G106)	PH1-012A			7						
FIRST FLOOR										
Tele Equip TE001	PH1-016A							60		
Storage S111	PH1-016A							50		
Conf Dept Office (F115)	PH1-016A							180		



**TABLE 1 | SUMMARY OF IDENTIFIED ASBESTOS CONTAINING MATERIALS (ACM) AND ESTIMATED QUANTITIES
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE, MAINE**

Room Section/Number	Sample #:	Pipe Insulation and Associated Mud Pipe Fittings (LF)	Tank Insulation (SF)	Mud Pipe Fittings Insulation on Fiberglass-insulated lines (EA)	Gasket on stored equipment (SF)	Asphalt Vapor Barrier (SF)	Floor Tile Adhesive beneath Non-ACM Floor Tile (SF)	Floor Tile and associated ACM adhesive (SF)	Exterior Caulk Associated with Window Frames (EA)	Comment
Hallway near F107	PH1-012A			15						
Anchor Lounge (R101)	PH1-012A			4						
SECOND FLOOR										
H203	PH1-012A			2						
Hallway outside T235/T236	PH1-012A			4						
T202	PH1-012A			3						
Hallway outside T204	PH1-012A			2						
Hallway outside S203	PH1-012A			2						
S207	PH1-012A			2						
THIRD FLOOR										
T319				4						
H303				1						
Hall outside T338				4						
FOURTH FLOOR										
Hall outside L404				2						
EXTERIOR										
Exterior	PH1-030A								475	
TOTALS:		30	50	159	2	280	680	290	475	



TABLE 2
HAZARDOUS MATERIALS INVENTORY
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE, MAINE

Identified Hazardous Materials	Estimated Quantity (Each)
Fluorescent Light Tubes - 2 foot*	240
Fluorescent Light Tubes - 4 foot	3,200
Suspect PCB-Containing Light Ballasts	2,000
Mercury-containing Thermostat	10
Exit Light Signs/Batteries	5

CONTRACTOR COPY



APPENDIX A

ASBESTOS INSPECTOR CERTIFICATION
LEAD RISK ASSESSOR CERTIFICATION

CONTRACTOR COPY

State of Maine
Asbestos Abatement Program

Suzanne L. Yerina



Inspector

Cert No. AI-0451

Trn. Exp Date 11/10/2023

Expiration Date 11/30/2023

This is not a legal form of official identification.



CONTRACTOR COPY



STATE OF MAINE
DEPARTMENT OF ENVIRONMENTAL PROTECTION



JANET T. MILLS
GOVERNOR

MELANIE LOYZIM
COMMISSIONER

December 4, 2022

Haley Ward, Inc.
1 Merchants Plaza, Suite 701
Bangor, Maine 04401

Dear Licensee:

Asbestos application(s) for individual certification of the **two** employee(s) listed below have been received and **approved**. Individual certification numbers are listed below and wallet card(s) are enclosed. Card(s) are property of the individual to whom each is issued. Your responsibility as a licensee is to ensure delivery of the cards to persons in your employment. This letter should be retained for your company files as record of certification. **Please attach 1 updated passport size photo with every application.**

Remember, in Maine all **certified employees** working on an asbestos abatement project, whether conducting removal/repair, air monitoring, design, inspection, or analysis functions, **must work for a State of Maine licensed asbestos firm** and carry his/her wallet card(s) on the job site.

As a reminder, prior to renewing your asbestos certification, the State of Maine **requires** an annual refresher course to be taken before submitting a renewal application. A certificate shall expire one year from the last day of the month from the date of issuance, **or on the last day of the month that the training certificate expires**, whichever is sooner.

All our asbestos forms can be found at <https://www.maine.gov/dep/waste/asbestos/forms.html>
Thank you for your cooperation and your completed application(s).

<u>Name</u>	<u>Category</u>	<u>Certification #</u>	<u>Exp. Date</u>
Deborah A. Kasik	Inspector	AI-0177	11/30/2023
Dennis B. Kingman, Jr.	Inspector	AI-0034	11/30/2023

Sincerely,

Sandra J. Moody, Environmental Specialist
Division of Remediation
Bureau of Remediation and Waste Management

State of Maine
Asbestos Abatement Program

Deborah A. Kasik

Inspector

Cert No. AI-0177

Trn.Exp.Date 11/10/2023

Expiration Date 11/30/2023

This is not a legal form of official identification



AUGUSTA
17 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0017
(207) 287-7688 FAX: (207) 287-7826

BANGOR
106 HOGAN ROAD, SUITE 6
BANGOR, MAINE 04401
(207) 941-4570 FAX: (207) 941-4584

PORTLAND
312 CANCO ROAD
PORTLAND, MAINE 04103
(207) 822-6300 FAX: (207) 822-6303

PORTLAND
1000 WATER STREET
PORTLAND, MAINE 04103
(207) 764-0477 FAX: (207) 760-3143



STATE OF MAINE
DEPARTMENT OF ENVIRONMENTAL PROTECTION

JANET T. MILLS
GOVERNOR

MELANIE LOYZIM
COMMISSIONER

January 28, 2023

Attn.: Deborah A. Kasik
Haley Ward, Inc.
1 Merchant's Plaza, 7th Floor
Bangor, Maine 04401

Dear Ms. Kasik,

Your lead application for certification has been received and **approved**. You have been granted certification as a **Lead Risk Assessor LR-0003**. Enclosed is your wallet card, with an expiration date of **January 05, 2024**. All employees working on a lead abatement project must carry this photo ID wallet card. The card is property of the individual to whom it is issued. Your responsibility as a licensee is to ensure delivery of the card to person in your employment. This letter should be retained for your company files as record of certification. **Please attach 1 updated passport size photo with every application.**

Thank you for your cooperation and your completed application(s). Applications can now be found on our DEP webpage at the following:

<https://www.maine.gov/dep/waste/lead/forms/index.html>


If you have any questions on this certification or on any other aspect of DEP's lead abatement licensing program, please call Sandy Moody (207) 242-0877 or email sandy.j.moody@maine.gov

Sincerely,

Sandra J. Moody, Environmental Specialist
Division of Remediation
Bureau of Remediation and Waste Management


Enclosure

State of Maine
Lead Abatement Program



Deborah A. Kasik

Risk Assessor
Cert No. LR-0003
Trn.Exp.Date 01/05/2024
Expiration Date 01/05/2024



This is not a legal form of official identification

AUGUSTA
17 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0017
(207) 287-7688 FAX: (207) 287-7826
RAY BLDG., HOSPITAL ST.

BANGOR
106 HOGAN ROAD, SUITE 6
BANGOR, MAINE 04401
(207) 941-4570 FAX: (207) 941-4584

PORTLAND
312 CANCO ROAD
PORTLAND, MAINE 04103
(207) 822-6300 FAX: (207) 822-6303

PRESQUE ISLE
1235 CENTRAL DRIVE, SKYWAY PARK
PRESQUE ISLE, MAINE 04679-2094
(207) 764-0477 FAX: (207) 760-3143



APPENDIX B

ASBESTOS ANALYTICAL LABORATORY CERTIFICATIONS

CONTRACTOR COPY



STATE OF MAINE
DEPARTMENT OF ENVIRONMENTAL PROTECTION

JANET T. MILLS
GOVERNOR

MELANIE LOYZIM
COMMISSIONER

September 14, 2022

Attn: Lorie Dennis, Quality Assurance Administrative Assistant
EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077

Dear Ms. Dennis,

This is to confirm that the Maine Department of Environmental Protection is in receipt of your request to add the following labs to your licensing of Analytical Laboratories: Boston, MA., **South Portland, Maine** and Wallingford, CT.

LA-0038 for Asbestos Analytical Laboratory (Air), expires on 10/31/2023
LB-0039 for Asbestos Analytical Laboratory (Bulk), expires on 10/31/2023

Remember each laboratory must have certified individual(s) within the lab to perform analyses.

If you need any further assistance please feel free to contact me at (207) 242-0877 or e-mail at sandy.j.moody@maine.gov.

Sincerely,

Sandra J. Moody, Environmental Specialist
Division of Remediation
Bureau of Remediation and Waste Management

AUGUSTA
17 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0017
(207) 287-7688 FAX: (207) 287-7826
RAY BLDG., HOSPITAL ST.

BANGOR
106 HOGAN ROAD, SUITE 6
BANGOR, MAINE 04401
(207) 941-4570 FAX: (207) 941-4584

PORTLAND
312 CANCO ROAD
PORTLAND, MAINE 04103
(207) 822-6300 FAX: (207) 822-6303

PRESQUE ISLE
1235 CENTRAL DRIVE, SKYWAY PARK
PRESQUE ISLE, MAINE 04679-2094
(207) 764-0477 FAX: (207) 760-3143



State of Maine
Department of Environmental Protection

LICENSE

EMSL Analytical, Inc.

Asbestos Analytical Laboratory
(Bulk)

License Number: LB-0039

Expiration Date: 10/31/2023



State of Maine
Department of Environmental Protection

LICENSE

EMSL Analytical, Inc.

Asbestos Analytical Laboratory

(Air)

License Number: **LA-0038**

Expiration Date: **10/31/2023**

S. PORTLAND - INDIVIDUAL ANALYST CERTIFICATIONS

State of Maine

May 12, 2023

<i>Employee Name</i>	<i>Lab Location</i>	<i>State Certified</i>	<i>Certification No.</i>	<i>Type of Cert.</i>	<i>Exp. Date</i>
Stephen Severn	S. Portland	Maine	AA-0497	Air Asbestos Analyst	11/30/2023
Stephen Severn	S. Portland	Maine	BA-0178	Bulk Asbestos Analyst	11/30/2023
Stefan Reis	S. Portland	Maine	BA-0233	Bulk Asbestos Analyst	5/31/2024

United States Department of Commerce
National Institute of Standards and Technology

NVLAP[®]



Certificate of Accreditation to ISO/IEC 17025:2017

NVLAP LAB CODE: 500094-0

EMSL Analytical, Inc.
South Portland, ME

*is accredited by the National Voluntary Laboratory Accreditation Program for specific services,
listed on the Scope of Accreditation, for:*

Asbestos Fiber Analysis

*This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2017.
This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality
management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).*

2022-10-01 through 2023-09-30

Effective Dates



A handwritten signature in black ink, appearing to read "Dana S. Glaman".

For the National Voluntary Laboratory Accreditation Program

SCOPE OF ACCREDITATION TO ISO/IEC 17025:2017

EMSL Analytical, Inc.
161 John Roberts Road
South Portland, ME 04106
Ms. Samantha Voigt
Phone: 207-517-6921
Email: svoigt@emsl.com
http://www.emsl.com

ASBESTOS FIBER ANALYSIS


NVLAP LAB CODE 500094-0

Bulk Asbestos Analysis

<u>Code</u>	<u>Description</u>
18/A01	EPA -- 40 CFR Appendix E to Subpart E of Part 763, Interim Method of the Determination of Asbestos in Bulk Insulation Samples
18/A03	EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials

Airborne Asbestos Analysis

<u>Code</u>	<u>Description</u>
18/A02	U.S. EPA's "Interim Transmission Electron Microscopy Analytical Methods-Mandatory and Nonmandatory-and Mandatory Section to Determine Completion of Response Actions" as found in 40 CFR, Part 763, Subpart E, Appendix A.



For the National Voluntary Laboratory Accreditation Program



APPENDIX C

ASBESTOS LABORATORY ANALYTICAL RESULTS

CONTRACTOR COPY



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Attn: Deb Kasik
Haley Ward
1 Merchant's Plaza
7th Floor
Bangor, ME 04401
Proj: 13150.007
Phone: (207) 989-4824
Fax: (207) 989-4881
Collected:
Received: 8/28/2023
Analyzed: 9/05/2023

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-001A **Lab Sample ID:** 622300938-0001
Sample Description: Boiler Rm/Ceiling Plaster - Ceiling Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/28/2023	Gray/White	0.0%	100.0%	None Detected	

Client Sample ID: PH1-001B **Lab Sample ID:** 622300938-0002
Sample Description: Boiler Rm/Ceiling Plaster - Ceiling Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/28/2023	Gray/White	0.0%	100.0%	None Detected	

Client Sample ID: PH1-001C **Lab Sample ID:** 622300938-0003
Sample Description: Boiler Rm/Ceiling Plaster - Ceiling Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/28/2023	Gray/White	0.0%	100.0%	None Detected	

Client Sample ID: PH1-002A **Lab Sample ID:** 622300938-0004
Sample Description: Boiler Rm (Mezz)/Mud Fittings - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/28/2023	White	35.0%	65.0%	None Detected	

Client Sample ID: PH1-002B **Lab Sample ID:** 622300938-0005
Sample Description: Boiler Rm (Mezz)/Mud Fittings - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/28/2023	White	40.0%	60.0%	None Detected	

Client Sample ID: PH1-002C **Lab Sample ID:** 622300938-0006
Sample Description: Boiler Rm (Mezz)/Mud Fittings - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/28/2023	Gray/White	0.0%	50.0%	50% Chrysotile	

Client Sample ID: PH1-003A **Lab Sample ID:** 622300938-0007
Sample Description: Boiler Rm (Mezz)/Pipe Insulation - Pipe Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray	0.0%	88.0%	12% Amosite	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-003B **Lab Sample ID:** 622300938-0008

Sample Description: Boiler Rm (Mezz)/Pipe Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023					Positive Stop (Not Analyzed)

Client Sample ID: PH1-003C **Lab Sample ID:** 622300938-0009

Sample Description: Boiler Rm (Mezz)/Pipe Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023					Positive Stop (Not Analyzed)

Client Sample ID: PH1-004A **Lab Sample ID:** 622300938-0010

Sample Description: Boiler Rm (Mezz)/Mud Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Tan/White	70.0%	30.0%	None Detected	

Client Sample ID: PH1-004B **Lab Sample ID:** 622300938-0011

Sample Description: Boiler Rm (Mezz)/Mud Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/White	18.0%	82.0%	None Detected	

Client Sample ID: PH1-004C **Lab Sample ID:** 622300938-0012

Sample Description: Boiler Rm (Mezz)/Mud Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray/White	70.0%	30.0%	None Detected	

Client Sample ID: PH1-005A **Lab Sample ID:** 622300938-0013

Sample Description: Boiler Rm (Mezz)/Tank Insulation - Tank Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Orange	0.0%	60.0%	40% Chrysotile	

Client Sample ID: PH1-005B **Lab Sample ID:** 622300938-0014

Sample Description: Boiler Rm (Mezz)/Tank Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023					Positive Stop (Not Analyzed)

Client Sample ID: PH1-005C **Lab Sample ID:** 622300938-0015

Sample Description: Boiler Rm (Mezz)/Tank Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023					Positive Stop (Not Analyzed)



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-006A **Lab Sample ID:** 622300938-0016

Sample Description: PH1-1st Security/12" Orange Mottled - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Red	0.0%	100%	None Detected	

Client Sample ID: PH1-006B **Lab Sample ID:** 622300938-0017

Sample Description: PH1-1st Security/12" Orange Mottled - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Red	0.0%	100%	None Detected	

Client Sample ID: PH1-006C **Lab Sample ID:** 622300938-0018

Sample Description: PH1-1st Security/12" Orange Mottled - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Red	0.0%	100%	None Detected	

Client Sample ID: PH1-007A **Lab Sample ID:** 622300938-0019

Sample Description: PH1-1st Security/Brown/Black Adh - Adhesive

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH1-007B **Lab Sample ID:** 622300938-0020

Sample Description: PH1-1st Security/Brown/Black Adh - Adhesive

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH1-007C **Lab Sample ID:** 622300938-0021

Sample Description: PH1-1st Security/Brown/Black Adh - Adhesive

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH1-008A **Lab Sample ID:** 622300938-0022

Sample Description: PH1-1st Security/CT1 4x2 Pinhole Groove - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	70.0%	30.0%	None Detected	

Client Sample ID: PH1-008B **Lab Sample ID:** 622300938-0023

Sample Description: PH1-1st Security/CT1t 4x2 Pinhole Groove - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Tan	80.0%	20.0%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-008C **Lab Sample ID:** 622300938-0024

Sample Description: PH1-1st Security/CT1 4x2 Pinhole Groove - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Tan	75.0%	25.0%	None Detected	

Client Sample ID: PH1-008D **Lab Sample ID:** 622300938-0025

Sample Description: 2nd Floor by Bedroom 203/CT1 - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray/White	70.0%	30.0%	None Detected	

Client Sample ID: PH1-009A **Lab Sample ID:** 622300938-0026

Sample Description: Quarter Deck by Security/CT2 2x2 Pinhole - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	55.0%	45.0%	None Detected	

Client Sample ID: PH1-009B **Lab Sample ID:** 622300938-0027

Sample Description: Quarter Deck by Security/CT2 2x2 Pinhole - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	55.0%	45.0%	None Detected	

Client Sample ID: PH1-009C **Lab Sample ID:** 622300938-0028

Sample Description: Quarter Deck by Security/CT2 2x2 Pinhole - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	68.0%	32.0%	None Detected	

Client Sample ID: PH1-010A **Lab Sample ID:** 622300938-0029

Sample Description: Hallway by Security/CT3 2x2 Text w/ Pinhole - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	65.0%	35.0%	None Detected	

Client Sample ID: PH1-010B **Lab Sample ID:** 622300938-0030

Sample Description: Hallway by Security/CT3 2x2 Text w/ Pinhole - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	58.0%	42.0%	None Detected	

Client Sample ID: PH1-010C **Lab Sample ID:** 622300938-0031

Sample Description: Hallway by Security/CT3 2x2 Text w/ Pinhole - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	50.0%	50.0%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-010D **Lab Sample ID:** 622300938-0032

Sample Description: 2nd Floor by Bedroom 203/CT3 - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Tan/White	45.0%	55.0%	None Detected	

Client Sample ID: PH1-011A **Lab Sample ID:** 622300938-0033

Sample Description: Bathroom by Security/CT4 2x2 Pinhole Groove - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/White	80.0%	20.0%	None Detected	

Client Sample ID: PH1-011B **Lab Sample ID:** 622300938-0034

Sample Description: Bathroom by Security/CT4 2x2 Pinhole Groove - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray/White	55.0%	45.0%	None Detected	

Client Sample ID: PH1-011C **Lab Sample ID:** 622300938-0035

Sample Description: Bathroom by Security/CT4 2x2 Pinhole Groove - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray/White	60.0%	40.0%	None Detected	

Client Sample ID: PH1-012A **Lab Sample ID:** 622300938-0036

Sample Description: Bathroom by Security/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray	40.0%	52.0%	8% Chrysotile	

Client Sample ID: PH1-012B **Lab Sample ID:** 622300938-0037

Sample Description: Anchor Lounge/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	9/05/2023	Gray	40.0%	54.0%	6% Chrysotile	

Client Sample ID: PH1-012C **Lab Sample ID:** 622300938-0038

Sample Description: Janitor/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	9/05/2023	Gray/Tan	60.0%	30.0%	10% Chrysotile	

Client Sample ID: PH1-012D **Lab Sample ID:** 622300938-0039

Sample Description: Bath T208/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	9/05/2023	Gray	60.0%	35.0%	5% Chrysotile	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-012E **Lab Sample ID:** 622300938-0040

Sample Description: Bath T214/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray	50.0%	45.0%	5% Chrysotile	

Client Sample ID: PH1-012F **Lab Sample ID:** 622300938-0041

Sample Description: Bath T214/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	9/05/2023	Gray/White	40.0%	57.0%	3% Chrysotile	

Client Sample ID: PH3-012G **Lab Sample ID:** 622300938-0042

Sample Description: Outside 4th Laundry by 490/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Tan/White	55.0%	45.0%	None Detected	

Client Sample ID: PH3-012H **Lab Sample ID:** 622300938-0043

Sample Description: Outside 4th Laundry by 490/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray	43.0%	57.0%	None Detected	

Client Sample ID: PH2-012I **Lab Sample ID:** 622300938-0044

Sample Description: S102/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Black	60.0%	40.0%	None Detected	

Client Sample ID: PH2-012J **Lab Sample ID:** 622300938-0045

Sample Description: Rifle Range/Mudded Fitting - Mud Fitting

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray	50.0%	50.0%	None Detected	

Client Sample ID: PH1-013A **Lab Sample ID:** 622300938-0046

Sample Description: Storage by Security/Carpet Mastic - Carpet Mastic

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-013B **Lab Sample ID:** 622300938-0047

Sample Description: Conference Room F114/Carpet Mastic - Carpet Mastic

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Yellow	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-013C **Lab Sample ID:** 622300938-0048

Sample Description: Housekeeping B64/Carpet Mastic - Carpet Mastic

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-013D **Lab Sample ID:** 622300938-0049

Sample Description: R204/Carpet Adhesive - Carpet Mastic

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-014A **Lab Sample ID:** 622300938-0050

Sample Description: Conference Room F114/2x2 Phole CT - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray/White	45.0%	55.0%	None Detected	

Client Sample ID: PH1-014B **Lab Sample ID:** 622300938-0051

Sample Description: Conference Room F114/2x2 Phole CT - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray/White	40.0%	60.0%	None Detected	

Client Sample ID: PH1-014C **Lab Sample ID:** 622300938-0052

Sample Description: Conference Room F114/2x2 Phole CT - Ceiling Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray/White	55.0%	45.0%	None Detected	

Client Sample ID: PH1-014D **Lab Sample ID:** 622300938-0053

Sample Description: By 243/2x2 Pin Groove

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM					Not Submitted	

Client Sample ID: PH1-015A **Lab Sample ID:** 622300938-0054

Sample Description: Conference Room F114 above CT/Sheetrock - Sheetrock

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray	11.0%	89.0%	None Detected	

Client Sample ID: PH1-015B **Lab Sample ID:** 622300938-0055

Sample Description: Housekeeping B64 Above CT/Sheetrock - Sheetrock

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Tan	18.0%	82.0%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-015C **Lab Sample ID:** 622300938-0056

Sample Description: Housekeeping B64 Above CT/Sheetrock - Sheetrock

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Tan	19.0%	81.0%	None Detected	

Client Sample ID: PH1-016A **Lab Sample ID:** 622300938-0057

Sample Description: Storage S111/dk brown mottled FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Black	0.0%	98.6%	1.4% Chrysotile	

Client Sample ID: PH1-016B **Lab Sample ID:** 622300938-0058

Sample Description: Storage S111/dk brown mottled FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023				Positive Stop (Not Analyzed)	

Client Sample ID: PH1-016C **Lab Sample ID:** 622300938-0059

Sample Description: Storage S111/dk brown mottled FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023				Positive Stop (Not Analyzed)	

Client Sample ID: PH1-017A **Lab Sample ID:** 622300938-0060

Sample Description: Storage S111/Mastic 016A - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Black	0.0%	95.3%	4.7% Chrysotile	

Client Sample ID: PH1-017B **Lab Sample ID:** 622300938-0061

Sample Description: Storage S111/Mastic 016B - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023				Positive Stop (Not Analyzed)	

Client Sample ID: PH1-017C **Lab Sample ID:** 622300938-0062

Sample Description: Storage S111/Mastic 016C - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023				Positive Stop (Not Analyzed)	

Client Sample ID: PH1-018A **Lab Sample ID:** 622300938-0063

Sample Description: Room F112/Light Green Mottled FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Green	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-018B **Lab Sample ID:** 622300938-0064

Sample Description: Room F112/Light Green Mottled FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Green	0.0%	100%	None Detected	

Client Sample ID: PH1-018C **Lab Sample ID:** 622300938-0065

Sample Description: Room F112/Light Green Mottled FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Green	0.0%	100%	None Detected	

Client Sample ID: PH1-019A **Lab Sample ID:** 622300938-0066

Sample Description: Room F112/Mastic 018A - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Various	0.0%	100%	None Detected	

Client Sample ID: PH1-019B **Lab Sample ID:** 622300938-0067

Sample Description: Room F112/Mastic 018B - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Various	0.0%	100%	None Detected	

Client Sample ID: PH1-019C **Lab Sample ID:** 622300938-0068

Sample Description: Room F112/Mastic 018C - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Various	0.0%	100%	None Detected	

Client Sample ID: PH1-020A **Lab Sample ID:** 622300938-0069

Sample Description: Rec Room/Wall Glue - Wall Glue

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Tan	0.0%	100%	None Detected	

Client Sample ID: PH1-020B **Lab Sample ID:** 622300938-0070

Sample Description: Rec Room/Wall Glue - Wall Glue

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/30/2023	Tan	0.0%	100%	None Detected	

Client Sample ID: PH1-020C **Lab Sample ID:** 622300938-0071

Sample Description: Rec Room/Wall Glue - Wall Glue

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Tan	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-021A **Lab Sample ID:** 622300938-0072

Sample Description: Chapel/White 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	White	0.0%	100%	None Detected	

Client Sample ID: PH1-021B **Lab Sample ID:** 622300938-0073

Sample Description: Chapel/White 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	White	0.0%	100%	None Detected	

Client Sample ID: PH1-021C **Lab Sample ID:** 622300938-0074

Sample Description: Chapel/White 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	White	0.0%	100%	None Detected	

Client Sample ID: PH1-022A **Lab Sample ID:** 622300938-0075

Sample Description: Chapel/Black 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Black	0.0%	100%	None Detected	

Client Sample ID: PH1-022B **Lab Sample ID:** 622300938-0076

Sample Description: Chapel/Black 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Black	0.0%	100%	None Detected	

Client Sample ID: PH1-022C **Lab Sample ID:** 622300938-0077

Sample Description: Chapel/Black 12x12 FT - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH1-023A **Lab Sample ID:** 622300938-0078

Sample Description: Chapel/Mastic 021A-022A - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH1-023B **Lab Sample ID:** 622300938-0079

Sample Description: Chapel/Mastic 021B-022B - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-023C **Lab Sample ID:** 622300938-0080

Sample Description: Chapel/Mastic 021C-022C - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH1-024A **Lab Sample ID:** 622300938-0081

Sample Description: Exterior Chapel/Ceiling Exterior Skimcoat - Skimcoat

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	0.0%	100.0%	None Detected	

Client Sample ID: PH1-024B **Lab Sample ID:** 622300938-0082

Sample Description: Exterior Chapel/Ceiling Exterior Skimcoat - Skimcoat

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	0.0%	100.0%	None Detected	

Client Sample ID: PH1-024C **Lab Sample ID:** 622300938-0083

Sample Description: Exterior Chapel/Ceiling Exterior Skimcoat - Skim Coat

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/White	0.0%	100.0%	None Detected	

Client Sample ID: PH1-025A **Lab Sample ID:** 622300938-0084

Sample Description: Exterior Chapel/Column Skimcoat - Skimcoat

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray	0.0%	100.0%	None Detected	

Client Sample ID: PH1-025B **Lab Sample ID:** 622300938-0085

Sample Description: Exterior Chapel/Column Skimcoat - Skimcoat

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Green	8.0%	92.0%	None Detected	

Client Sample ID: PH1-025C **Lab Sample ID:** 622300938-0086

Sample Description: Exterior Chapel/Column Skimcoat - Skimcoat

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Gray/Tan/Green	0.0%	100.0%	None Detected	

Client Sample ID: PH1-026A **Lab Sample ID:** 622300938-0087

Sample Description: 2nd Floor by 206/Grey 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-026B **Lab Sample ID:** 622300938-0088

Sample Description: 3rd Floor by 306/Grey 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH1-026C **Lab Sample ID:** 622300938-0089

Sample Description: 4th Floor by 406/Grey 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH1-027A **Lab Sample ID:** 622300938-0090

Sample Description: 2nd Floor by 206/Mastic 26A - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH1-027B **Lab Sample ID:** 622300938-0091

Sample Description: 3rd Floor by 306/Mastic 26B - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH1-027C **Lab Sample ID:** 622300938-0092

Sample Description: 4th Floor by 406/Mastic 26C - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH1-028A **Lab Sample ID:** 622300938-0093

Sample Description: Room 205/Grey Swirl 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH1-028B **Lab Sample ID:** 622300938-0094

Sample Description: Room 205/Grey Swirl 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH1-028C **Lab Sample ID:** 622300938-0095

Sample Description: Room 205/Grey Swirl 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-029A **Lab Sample ID:** 622300938-0096

Sample Description: Room 205/Mastic 028A - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-029B **Lab Sample ID:** 622300938-0097

Sample Description: Room 205/Mastic 028B - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-029C **Lab Sample ID:** 622300938-0098

Sample Description: Room 205/Mastic 028C - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-030A **Lab Sample ID:** 622300938-0099

Sample Description: Room 212/Window Caulk - Caulk

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	97.6%	2.4% Chrysotile	

Client Sample ID: PH1-030B **Lab Sample ID:** 622300938-0100

Sample Description: Room 353/Window Caulk - Caulk

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023				Positive Stop (Not Analyzed)	

Client Sample ID: PH1-030C **Lab Sample ID:** 622300938-0101

Sample Description: Room 342/Window Caulk - Caulk

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023				Positive Stop (Not Analyzed)	

Client Sample ID: PH1-031A **Lab Sample ID:** 622300938-0102

Sample Description: Room 212/Window Glaze - Glaze

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH1-031B **Lab Sample ID:** 622300938-0103

Sample Description: Room 228/Window Glaze - Glaze

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	99.6%	0.35% Chrysotile	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-031C **Lab Sample ID:** 622300938-0104

Sample Description: Room 329/Window Glaze - Glaze

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH3-031D **Lab Sample ID:** 622300938-0105

Sample Description: Room 280/Window Glaze - Glaze

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	<0.25% Chrysotile	

Client Sample ID: PH3-031E **Lab Sample ID:** 622300938-0106

Sample Description: Room 391/Window Glaze - Glaze

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	8/31/2023	Gray	0.0%	100%	<0.25% Chrysotile	

Client Sample ID: PH1-032A **Lab Sample ID:** 622300938-0107

Sample Description: By Room 230/Five Stop Caulk - Caulk

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Red	0.74%	99.3%	None Detected	

Client Sample ID: PH1-032B **Lab Sample ID:** 622300938-0108

Sample Description: By Room 230/Five Stop Caulk - Caulk

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Red	0.88%	99.1%	None Detected	

Client Sample ID: PH1-032C **Lab Sample ID:** 622300938-0109

Sample Description: By Room 230/Five Stop Caulk - Caulk

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Red	0.49%	99.5%	None Detected	

Client Sample ID: PH1-033A **Lab Sample ID:** 622300938-0110

Sample Description: Room 234/Green Swirl 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Green	0.0%	100%	None Detected	

Client Sample ID: PH1-033B **Lab Sample ID:** 622300938-0111

Sample Description: Room 234/Green Swirl 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Green	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-033C **Lab Sample ID:** 622300938-0112

Sample Description: Room 234/Green Swirl 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Green	0.0%	100%	None Detected	

Client Sample ID: PH1-034A **Lab Sample ID:** 622300938-0113

Sample Description: Room 234/Mastic 33A - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-034B **Lab Sample ID:** 622300938-0114

Sample Description: Room 234/Mastic 33B - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-034C **Lab Sample ID:** 622300938-0115

Sample Description: Room 234/Mastic 33C - Mastic from Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-035A **Lab Sample ID:** 622300938-0116

Sample Description: Room 410/White 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	White	0.0%	100%	None Detected	

Client Sample ID: PH1-035B **Lab Sample ID:** 622300938-0117

Sample Description: Room 410/White 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	White	0.0%	100%	None Detected	

Client Sample ID: PH1-035C **Lab Sample ID:** 622300938-0118

Sample Description: Room 410/White 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	White	0.0%	100%	None Detected	

Client Sample ID: PH1-036A **Lab Sample ID:** 622300938-0119

Sample Description: Room 410/Mastic 35A - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH1-036B **Lab Sample ID:** 622300938-0120

Sample Description: Room 410/Mastic 35B - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH1-036C **Lab Sample ID:** 622300938-0121

Sample Description: Room 410/Mastic 35C - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH2-037A **Lab Sample ID:** 622300938-0122

Sample Description: Room 458/Tan 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Beige	0.0%	100%	None Detected	

Client Sample ID: PH2-037B **Lab Sample ID:** 622300938-0123

Sample Description: Room 458/Tan 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Beige	0.0%	100%	None Detected	

Client Sample ID: PH2-037C **Lab Sample ID:** 622300938-0124

Sample Description: Room 458/Tan 12x24 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Beige	0.0%	100%	None Detected	

Client Sample ID: PH2-038A **Lab Sample ID:** 622300938-0125

Sample Description: Room 458/Mastic 37A - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH2-038B **Lab Sample ID:** 622300938-0126

Sample Description: Room 458/Mastic 37B - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH2-038C **Lab Sample ID:** 622300938-0127

Sample Description: Room 458/Mastic 37C - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Brown	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH2-039A **Lab Sample ID:** 622300938-0128

Sample Description: L001/Grey Mottled SF - SF

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH2-039B **Lab Sample ID:** 622300938-0129

Sample Description: L001/Grey Mottled SF - SF

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH2-039C **Lab Sample ID:** 622300938-0130

Sample Description: L001/Grey Mottled SF - SF

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Gray	0.0%	100%	None Detected	

Client Sample ID: PH2-040A **Lab Sample ID:** 622300938-0131

Sample Description: Rifle Range/Glue Daubs - Glue Daubs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH2-040B **Lab Sample ID:** 622300938-0132

Sample Description: Rifle Range/Glue Daubs - Glue Daubs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH2-040C **Lab Sample ID:** 622300938-0133

Sample Description: Rifle Range/Glue Daubs - Glue Daubs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Brown	0.0%	100%	None Detected	

Client Sample ID: PH2-041A **Lab Sample ID:** 622300938-0134

Sample Description: Rifle Range/Gasket - Rope - Gasket Rope

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	White	55.0%	5.0%	40% Chrysotile	

Client Sample ID: PH2-041B **Lab Sample ID:** 622300938-0135

Sample Description: Rifle Range/Gasket - Rope

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023					Positive Stop (Not Analyzed)



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH2-041C **Lab Sample ID:** 622300938-0136

Sample Description: Rifle Range/Gasket - Rope

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023					Positive Stop (Not Analyzed)

Client Sample ID: PH2-042A **Lab Sample ID:** 622300938-0137

Sample Description: Rifle Range/Blown In Insulation - Blown in Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray/Tan	80.0%	20.0%	None Detected	

Client Sample ID: PH2-042B **Lab Sample ID:** 622300938-0138

Sample Description: Rifle Range/Blown In Insulation - Blown in Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray	95.0%	5.0%	None Detected	

Client Sample ID: PH2-042C **Lab Sample ID:** 622300938-0139

Sample Description: Rifle Range/Blown In Insulation - Blown in Insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	Brown/Gray	98.0%	2.0%	None Detected	

Client Sample ID: PH2-043A **Lab Sample ID:** 622300938-0140

Sample Description: Rifle Range/Vapor Barrier - Vapor Barrier

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Black	0.0%	93.4%	6.6% Chrysotile	

Client Sample ID: PH2-043B **Lab Sample ID:** 622300938-0141

Sample Description: Rifle Range/Vapor Barrier - Vapor Barrier

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023					Positive Stop (Not Analyzed)

Client Sample ID: PH2-043C **Lab Sample ID:** 622300938-0142

Sample Description: Rifle Range/Vapor Barrier - Vapor Barrier

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023					Positive Stop (Not Analyzed)

Client Sample ID: PH2-044A **Lab Sample ID:** 622300938-0143

Sample Description: By B06/Joint Compound - Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	White	0.0%	100.0%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH2-044B **Lab Sample ID:** 622300938-0144

Sample Description: By B06/Joint Compound - Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	White	0.0%	100.0%	None Detected	

Client Sample ID: PH2-044C **Lab Sample ID:** 622300938-0145

Sample Description: By B06/Joint Compound - Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	8/29/2023	White	0.0%	100.0%	None Detected	

Client Sample ID: PH2-045A **Lab Sample ID:** 622300938-0146

Sample Description: T101/Tan Sheet Flooring - Sheet Flooring

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Tan	<0.25%	100%	None Detected	

Client Sample ID: PH2-045B **Lab Sample ID:** 622300938-0147

Sample Description: T103/Tan Sheet Flooring - Sheet Flooring

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Tan	0.74%	99.3%	None Detected	

Client Sample ID: PH2-045C **Lab Sample ID:** 622300938-0148

Sample Description: T103/Tan Sheet Flooring - Sheet Flooring

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Tan	0.47%	99.5%	None Detected	

Client Sample ID: PH3-046A **Lab Sample ID:** 622300938-0149

Sample Description: G7 Bilge/Tan 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Tan	0.0%	100%	None Detected	

Client Sample ID: PH3-046B **Lab Sample ID:** 622300938-0150

Sample Description: G7 Bilge/Tan 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Tan	0.0%	100%	None Detected	

Client Sample ID: PH3-046C **Lab Sample ID:** 622300938-0151

Sample Description: G7 Bilge/Tan 12x12 FT - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Tan	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH3-047A **Lab Sample ID:** 622300938-0152

Sample Description: G7 Bilge/Black Mastic 46A - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Black	0.0%	95.3%	4.7% Chrysotile	

Client Sample ID: PH3-047B **Lab Sample ID:** 622300938-0153

Sample Description: G7 Bilge/Black Mastic 46B - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023				Positive Stop (Not Analyzed)	

Client Sample ID: PH3-047C **Lab Sample ID:** 622300938-0154

Sample Description: G7 Bilge/Black Mastic 46C - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023				Positive Stop (Not Analyzed)	

Client Sample ID: PH2-048A **Lab Sample ID:** 622300938-0155

Sample Description: H104/FT Cream w/ Green - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Beige	0.0%	100%	None Detected	

Client Sample ID: PH2-048B **Lab Sample ID:** 622300938-0156

Sample Description: H104/FT Cream w/ Green - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Beige	0.0%	100%	None Detected	

Client Sample ID: PH2-048C **Lab Sample ID:** 622300938-0157

Sample Description: H104/FT Cream w/ Green - Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Beige	0.0%	100%	None Detected	

Client Sample ID: PH2-049A **Lab Sample ID:** 622300938-0158

Sample Description: H104/Mastic 048A - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	

Client Sample ID: PH2-049B **Lab Sample ID:** 622300938-0159

Sample Description: H104/Mastic 048B - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106
Phone/Fax: (207) 517-6921 / (207) 517-6922
<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order ID: 622300938
Customer ID: CESI62
Customer PO:
Project ID:

Summary Test Report for Asbestos Analysis of Bulk Material

Client Sample ID: PH2-049C **Lab Sample ID:** 622300938-0160

Sample Description: H104/Mastic 048C - Mastic on Floor Tile

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM Grav. Reduction	9/01/2023	Yellow	0.0%	100%	None Detected	

CONTRACTOR COPY

PLM: ME CERT # BA-0233
PLM EPA NOB: ME CERT # BA-0233

Analyst(s):
Stefan Reis PLM (54)
PLM Grav. Reduction (89)

Reviewed and approved by:

Stephen Severn, Technical Manager
or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This is a summary report; official reports are available on LabConnect or upon request and relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. South Portland, ME NVLAP Lab Code 500094-0, VT AL197271, ME LM-0039, CT PH-0346, AZ AZ-0959, MA AA000236

Initial report from: 09/05/2023 15:23:15



EMSL ANALYTICAL, INC.
LABORATORY PRODUCTS TRAINING

Asbestos Bulk Building Materials - Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
161 John Roberts Road

South Portland, ME 04106
PHONE (207) 517-6921
EMAIL portlandlab@emsl.com

622300938

Customer Information		Billing Information	
Customer ID		Billing ID	
Company Name	Haley Ward	Company Name	Haley Ward
Contact Name	Deb Kasik	Billing Contact	Deb Kasik
Street Address	1 Merchant's Plaza 7th Floor	Street Address	1 Merchant's Plaza, 7th Floor
City, State, Zip	Bangor ME 04401	City, State, Zip	Bangor ME Country US
Phone	207-989-4824	Phone	207-989-4824
Email(s) for Report	dkasik@haleyward.com	Email(s) for Invoice	

Project Information

Project Name/No: 13150, 000-007

EMSL LIMS Project ID (if applicable, ENGL use previous):

US State where samples collected: ME

State of Connecticut (CT) must select project location: Commercial (Taxable) Residential (Non-Taxable)

Sampled By Name: Deborah A Kasik

Sampled By Signature: *Deborah A Kasik*

Date Sampled:

No. of Samples in Shipment: 160

Turn-Around-Time (TAT)

3 Hour 6 Hour 24 Hour 32 Hour 48 Hour 72 Hour 96 Hour 1 Week 2 Week

Please call ahead for large projects and/or turnaround times 8 Hours or Less. *32 Hour TAT available for select tests only, samples must be submitted by 11:30am

Test Selection

PLM - Bulk (reporting limit)

PLM EPA 600/R-93/115 (<1%)

PLM EPA NOB (<1%)

POINT COUNT

400 (<0.25%) 1,000 (<0.1%)

POINT COUNT w/ GRAVIMETRIC

400 (<0.25%) 1,000 (<0.1%)

NIOSH 9002 (<1%)

NYS 198.1 (Friable - NY)

NYS 198.6 NOB (Non-Friable - NY)

NYS 198.8 (Vermiculite SM-V)

TEM - Bulk

TEM EPA NOB

NYS NOB 198.4 (Non-Friable - NY)

TEM EPA 600/R-93/116 w Milling Prep (0.1%)

Other Tests (please specify)

Positive Stop - Clearly Identified Homogeneous Areas (HA)

Sample Number	HA Number	Sample Location	Material Description
PHI-001A		Boiler Rm	Ceiling Plaster
B		"	"
C		"	"
PHI-002A		Boiler Rm (Mezz)	Mud Fittings on PG
B		" (Mezz)	"
C		"	"
003A		Boiler Rm (Mezz)	Pipe Insulation
B		"	"
C		"	"
004A		"	Mud fittings on AC

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

NOB per MEDEP

PLEASE ANALYZE ALL 012A-J

Method of Shipment: Fed Exp.

Sample Condition Upon Receipt:

Relinquished by: *Deborah A Kasik* Date/Time: 8/23/23 3:55 pm

Received by: *[Signature]* Date/Time: 8/28/23 10:00 am

Controlled Document - Asbestos Bulk R7 9/14/2021

AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.

RECEIVED Page 1 of 1

AUG 28 2023

BY: *SR*



EMSL ANALYTICAL, INC.
LABORATORY • PRODUCTS • TRAINING

Asbestos Bulk Building Materials - Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
161 John Roberts Road

South Portland, ME 04106
PHONE: (207) 517-6921
EMAIL: portlandlab@emsl.com

622300938

Customer Information	Customer ID:	Billing ID:
	Company Name: Haley Ward	Company Name: Haley Ward
	Contact Name: Deb Kasik	Billing Contact: Deb Kasik
	Street Address: 1 Merchant's Plaza 7th Floor	Street Address: 1 Merchant's Plaza, 7th Floor
	City, State, Zip: Bangor ME 04401 Country: US	City, State, Zip: Bangor ME Country: US
	Phone: 207-989-4824	Phone: 207-989-4824
Email(s) for Report: dkasik@haleyward.com	Email(s) for Invoice:	

Project Information

Project Name/No: 13150.006 Purchase Order:

EMSL LIMS Project ID: (If applicable, EMSL will provide) US State where samples collected: ME State of Connecticut (CT) must select project location: Commercial (Taxable) Residential (Non-Taxable)

Sampled By Name: S. Yerina Deborah A Kasik Sampled By Signature: S. Yerina/D. Kasik Date Sampled: No. of Samples in Shipment: 160

Turn-Around-Time (TAT)

3 Hour 6 Hour 24 Hour 32 Hour 48 Hour 72 Hour 96 Hour 1 Week 2 Week

Please call ahead for large projects and/or turnaround times 6 Hours or Less. *32 Hour TAT available for select tests only, samples must be submitted by 11:30am.

Test Selection

PLM - Bulk (reporting limit)

PLM EPA 600/R-93/116 (<1%)
 PLM EPA NOB (<1%)
 POINT COUNT
 400 (<0.25%) 1,000 (<0.1%)
 POINT COUNT w/ GRAVIMETRIC
 400 (<0.25%) 1,000 (<0.1%)
 NIOSH 9002 (<1%)
 NYS 198.1 (Friable - NY)
 NYS 198.6 NOB (Non-Friable - NY)
 NYS 198.8 (Vermiculite SM-V)

TEM - Bulk

TEM EPA NOB
 NYS NOB 198.4 (Non-Friable - NY)
 TEM EPA 600/R-93/116 w/ Milling Pres. (9.1%)

Other Tests (please specify)

Positive Stop - Clearly Identified Homogeneous Areas (HA)

RECEIVED
AUG 28 2023
BY: AR

Sample Number	HA Number	Sample Location	Material Description
PHI-001A		Boiler Rm	Ceiling Plaster
		"	"
		"	"
PHI-002A		Boiler Rm (Mezz)	Mud Fittings on PG
		" (Mezz)	"
		"	"
003A		Boiler Rm (Mezz)	Pipe Insulation
		"	"
		"	"
004A		"	Mud fitting on pipe

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

NOB per MEDEP
PLEASE ANALYZE ALL 012A → J

Method of Shipment: Fed Exp.	Sample Condition Upon Receipt:
Relinquished by: Deborah Kasik	Received by: AR
Date/Time: 8/25/23 3:55 pm	Date/Time: 8/28/23 10:00
Relinquished by:	Received by:
Date/Time:	Date/Time:

Controlled Document - Asbestos Bulk R7 9/14/2021 AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



Asbestos Bulk Building Materials - Chain of Custody

EMSL Analytical, Inc.
161 John Roberts Road

EMSL ANALYTICAL, INC.
LABORATORY • PRODUCTS • TRAINING

622300938

South Portland, ME 04106
PHONE: (207) 517-6921
EMAIL: portlandlab@emsl.com

RECEIVED

AUG 28 2023

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

BY: AR

Sample Number	HA Number	Sample Location	Material Description
004 B C		Boiler Rm / Mezz	Mud fitting on tank
005 A B C		Boiler Rm / Mezz	Tank insulation
006 A B C		PH1 - 1 st Security	12" orange mottled (52102)
007 A B C		"	Brown/Black Ash
008 A B C		"	CT 4x2 pinhole groove
009 A B C		Quarter Deck Entry by Security	CT 2x2 pinhole
010 A B C		Hallway by Security	CT 3 2x2 text w/ pinhole
011 A B C		bathroom by Security	CT 4 2x2 pinhole groove
012 A 012 B		bathroom by Security Anchor Lounge	Mud Fitting on Fiberglass

CONTRACTOR COPY

Method of Shipment:		Sample Condition Upon Receipt:	
Relinquished by:	Date/Time:	Received by: <u>AA</u>	Date/Time: <u>8/28/23 10:00</u>
Relinquished by:	Date/Time:	Received by:	Date/Time:

Controlled Document - Asbestos Bulk R7 09/14/2021

AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



EMSL ANALYTICAL, INC.
LABORATORY-PRODUCTS-TRAINING

Asbestos Bulk Building Materials - Chain of Custody
EMSL Order Number / Lab Use Only

622300938

EMSL Analytical, Inc.
161 John Roberts Road
South Portland, ME 04106
(207) 517-6928
portlandlab@emsl.com
RECEIVED
AUG 28 2023

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc)

BY: AR

Sample Number	HA Number	Sample Location	Material Description
012C ✓		Janitor	
013A		Storage by security	Carpot mastic
013B		conference room F114	"
013C ✓		Housekeeping B64	"
014A		conference room F114	2x4 phole CT
014B		"	"
014C		"	"
015A		" above CT	Sheetrock
015B ✓		Housekeeping B64 above CT	"
015C ✓		" "	"
016A		Storage S111	dk brown matted FT
016B		"	"
016C		"	"
017A		"	mastic 016A
017B		"	" 016B
017C		"	" 016C
018A		Room F112	Light green matted FT
018B		"	"
018C		"	"
019A		"	mastic 018A
019B		"	018B
019C 019C		"	018C
020A 020B		Rec Room	wall glue 018E
020B 020C		"	"
020C		"	"

Method of Shipment		Sample Condition Upon Receipt	
Relinquished by:	Date/Time:	Received by: <u>AR</u>	Date/Time: <u>8/28/23 10:00</u>
Relinquished by:	Date/Time:	Received by:	Date/Time:

Controlled Document - Asbestos Bulk R7 09/14/2021

AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



EMSL ANALYTICAL, INC.
LABORATORY PRODUCTS TRAINING

Asbestos Bulk Building Materials - Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
161 John Roberts Road

South Portland, ME 04106
(207) 517-8921

portlandlab@emsl.com

AUG 28 2023

BY: AR

622300938

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

PH

Sample Number	HA Number	Sample Location	Material Description
021A		Chapel	White 12x12 FT
021B		"	"
021C		"	"
022A		"	Black 12x12 FT
022B		"	"
022C		"	"
023A		"	Mastic 021A-022A
023B		"	" 021B-022B
023C		"	" 021C-022C
024A		exterior chapel	ceiling exterior skim coat
024B		"	"
024C		"	"
0250025A		"	column skim coat
025B		"	"
025C		"	"
026A		2nd Floor by 206	grey 12x12 FT
026B		3rd Floor by 306	"
026C		4th Floor by 406	"
027A		2nd Floor by 206	Mastic 26A
027B		3rd Floor by 306	26B
027C		4th Floor by 406	26C
008D		2nd Floor by Bedroom 203	CT1
010D		" "	CT3
013D		R 205 204	carpet adhesive - brown
012D		Bath T208	mud filling

CONTRACTOR COPY

Method of Shipment:		Sample Condition Upon Receipt:	
Relinquished by:	Date/Time:	Received by: <u>AR</u>	Date/Time: <u>8/28/23 10:00</u>
Relinquished by:	Date/Time:	Received by:	Date/Time:

Controlled Document - Asbestos Bulk R7 09/14/2021

AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



EMSL ANALYTICAL, INC.
LABORATORY • PRODUCTS • TRAINING

Asbestos Bulk Building Materials - Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
161 John Roberts Road

South Portland, ME 04106
RECEIVED
(207) 517-6921
portlandlab@emsl.com
AUG 28 2023

622300938

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

BY: AR

PHI
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50

Sample Number	HA Number	Sample Location	Material Description
028A		Room 205	grey swirl 12x24 FT
028B		"	"
028C		"	"
029A		"	mastic 028A
029B		"	028B
029C		"	028C
030A		Room 212	Window caulk
030B		353	"
030C		342	"
031A		Room 212	Window glaze
031B		Room 228	
031C		Room 329	
032A		By Room 230	Firestop caulk
032B		"	
032C		"	
033A		Room 234	green swirl 12x24 FT
033B		"	"
033C		"	"
034A		"	mastic 33A
034B		"	33B
034C		"	33C
012E		Bath T214	Mudded elbow
012F		" "	mudded elbow
014D		By 243	2x4 pin groove

Method of Shipment		Sample Condition Upon Receipt	
Relinquished by:	Date/Time:	Received by: <u>AR</u>	Date/Time: <u>8/28/23 10:00</u>
Relinquished by:	Date/Time:	Received by:	Date/Time:

Controlled Document - Asbestos Bulk R7 09/14/2021

AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



Asbestos Bulk Building Materials - Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
161 John Roberts Road

EMSL ANALYTICAL, INC.
LABORATORY-PRODUCTS-TRAINING

622300938

RECEIVED
South Portland, ME 04106
PHONE: (207) 517-6921
EMAIL: portlandlab@emsl.com

AUG 28 2023

BY: AR

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

Sample Number	HA Number	Sample Location	Material Description
PH1: 035A		Room 410	white 12x24 Ft
035B		↓	↓
035C			
036A			
036B			
036C			mastic 035A
PH3: 031D		Room 280	windaw glaze
PH3: 031E		" 391	" "
PH2: 037A		Room 438	tan 12x24 FT
037B		↓	↓
037C			
038A			
038B			
038C			mastic 37A
PH3: 012G		outside 4 th laundry by 490	mudded fitting
PH3: 012H		" "	mudded fitting
PH2: 012I		5102	mudded fitting
PH2: 039A		L001	grey mottled SF
PH2: 039B		"	"
PH2: 039C		"	"
PH2: 040A		rifle range	glue daubs
PH2: 040B		"	"
PH2: 040C		"	"
PH2: 012J		rifle range	mudded fitting

CONTRACTOR COPY

Method of Shipment		Sample Condition Upon Receipt:	
Relinquished by:	Date/Time:	Received by: <u>AR</u>	Date/Time: <u>8/28/23 10:00</u>
Relinquished by:	Date/Time:	Received by:	Date/Time:

Controlled Document - COC-01 Asbestos Bulk RE 05/09/2021 AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

6 of 8



EMSL ANALYTICAL, INC.
LABORATORY-PRODUCTS-TRAINING

Asbestos Bulk Building Materials - Chain of Custody

EMSL Order Number / Lab Use Only

EMSL Analytical, Inc.
161 John Roberts Road

6223 00 938

RECEIVED
South Portland, ME 04106
(207) 517-6921

portlandlab@emsl.com

AUG 28 2023

Additional Pages of the Chain of Custody are only necessary if needed for additional sample information

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

BY: AR

Sample Number	HA Number	Sample Location	Material Description
PH2 041A		R. Fire Range	gasket - rope
PH2 041B		"	"
PH2 041C		"	"
PH2 042A		"	Blown In insulation
PH2 042B		"	"
PH2 042C		"	"
PH2 043A			vapor barrier
PH2 043B			"
PH2 043C			"
PH2 044A		By Bob	Joint Compound (sales surface)
PH2 044B		"	"
PH2 044C		"	"
PH2 045A		T101	tan Sheet flooring
PH2 045B		T103	"
PH2 045C		T103	"
PH3 046A		A7 Bridge	tan 12x12 FT
PH3 046B			"
PH3 046C			"
PH3 047A			Black mastic 46A
PH3 047B		"	46B
PH3 047C		"	46C
PH2 048A		A104	FT cream w/green
PH2 048B		"	"
PH2 048C		"	"

Method of Shipment		Sample Condition Upon Receipt	
Relinquished by:	Date/Time:	Received by: <u>AR</u>	Date/Time: <u>8/28/23 10:00</u>
Relinquished by:	Date/Time:	Received by:	Date/Time:

Controlled Document - Asbestos Bulk R7 09/14/2021

AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.



APPENDIX D

PHOTOGRAPHIC LOG

CONTRACTOR COPY



CHA ARCHITECTURE, P.C.
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE MAINE

Photo No. 1	
Photo Date: August 24, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Fiberglass-insulated piping beneath sinks in restrooms. Mud fitting insulation was not observed.	
Photo By: DAK	

Photo No. 2	
Photo Date: August 24, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Mud pipe fitting insulation located in ceiling plenum near restrooms.	
Photo By: DAK	



CHA ARCHITECTURE, P.C.
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE MAINE



Photo No. 3	
Photo Date: August 24, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Mud pipe fitting insulation located in ceiling plenum.	
Photo By: DAK	

Photo No. 4	
Photo Date: August 24, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Mud pipe fitting insulation located in ceiling plenum.	
Photo By: DAK	



CHA ARCHITECTURE, P.C.
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE MAINE



Photo No. 5	
Photo Date: August 25, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Mud pipe fitting insulation on fiberglass-insulated piping.	
Photo By: DAK	

Photo No. 6	
Photo Date: August 25, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Pipe chase located in Ground Floor Armory.	
Photo By: DAK	



CHA ARCHITECTURE, P.C.
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE MAINE


Photo No. 7	
Photo Date: August 25, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Pipe chase in Men's Room located off the Bilge on the Ground Floor.	
Photo By: DAK	

Photo No. 8	
Photo Date: August 24, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Exterior caulk associated with the windows.	
Photo By: DAK	



CHA ARCHITECTURE, P.C.
CURTIS HALL, MAINE MARITIME ACADEMY, CASTINE MAINE

Photo No. 9	
Photo Date: August 24, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Non lead-containing interior and exterior windowsills.	
Photo By: DAK	

Photo No. 10	
Photo Date: August 24, 2023	
Site Location: Maine Maritime Academy Curtis Hall	
Description: Non Asbestos-containing Window Glazing	
Photo By: DAK	



HALEY WARD®

ENGINEERING | ENVIRONMENTAL | SURVEYING

November 17, 2023

Mr. Nathaniel A. Cram, AIA, LEED AP
CHA Consulting, Inc.
49 Dartmouth Street
Portland, Maine 04101
ncram@chacompanies.com

Re: Supplemental ACM Roof Sample Results | Curtis Hall Roof | Maine Maritime Academy | Castine, Maine

Dear Mr. Cram:

At your request, Haley Ward, Inc. (Haley Ward) received on October 23, 2023, at our Bangor office, four "roof core" samples from Curtis Hall located at the Maine Maritime Academy (MMA) in Castine, Maine. The roof core samples were collected by a qualified roofing contractor and delivered by Mr. Carl Olson, Facilities Operations Manager for MMA. Haley Ward reviewed, packaged, and submitted the roof core samples for to a Maine Department of Environmental Protection (MDEP) licensed laboratory for analysis.

A total of four roof core bulk samples of suspect ACM were received. MMA provided a site map with the approximate locations where the roof samples were collected and notes describing the samples. The notes are summarized, as follows:

- Sample 1 – high end of insulation (wet)
- Sample 2 – low end of insulation; (location changed due to puddle in the proposed location)
- Sample 3 – middle depth of insulation
- Sample 4 – middle depth of insulation.

The received bulk samples were submitted to EMSL Analytical, Inc. (EMSL) of South Portland, Maine for analysis. Bulk samples were analyzed using the MDEP required analytical method: PLM NOB-EPA 600/R-93/116 (for Non-Friable Organically Bound Materials (NOBs)). EMSL's laboratory is certified to perform asbestos analysis by both the National Voluntary Laboratory Accreditation Program (NVLAP) and the American

CHA Companies, Inc | 11.17.2023 | 13150.007.03 | Page 1



One Merchants Plaza, Suite 701, Bangor, ME 04401
T: 207.989.4824 | HALEYWARD.COM



Industrial Hygiene Association (AIHA). EMSL is a MDEP licensed Asbestos Analytical Laboratory. Laboratory analytical results and chain of custodies are included as **Attachment A**.

Laboratory analytical results did not identify the received roof bulk samples as asbestos-containing.

If you have any questions or if additional services are needed, please feel free to contact either of the undersigned at (207) 989-4824.

Sincerely,
Haley Ward, Inc.

Deborah A. Kasik
Project Scientist II
MDEP Asbestos Inspector (AI-0177)

Michael D. Sauda, MPH, CSP
Senior Project Scientist

DAK/MDS/
Attachments

Contractor COPY



ATTACHMENT A

LABORATORY ANALYTICAL RESULTS

Contractor Copy



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106

Tel/Fax: (207) 517-6921 / (207) 517-6922

<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order: 622301177

Customer ID: CESI62

Customer PO:

Project ID:

Attention: Deb Kasik
Haley Ward
1 Merchant's Plaza
7th Floor
Bangor, ME 04401

Phone: (207) 989-4824

Fax: (207) 989-4881

Received Date: 10/25/2023 4:30 PM

Analysis Date: 10/30/2023

Collected Date:

Project: 10955.016 ROOF CORE SAMPLES

Test Report: Asbestos Analysis of Bulk Materials via AHERA Method 40CFR 763 Subpart E Appendix E supplemented with EPA 600/R-93/116 using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
1-Foam 622301177-0001	SAMPLE #1 - HIGH END OF INSULATION (WET)	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
1-Foam Backing 622301177-0001A	SAMPLE #1 - HIGH END OF INSULATION (WET)	Gray Fibrous Homogeneous	70% Cellulose 20% Glass	10% Non-fibrous (Other)	None Detected
1-Fiberboard 622301177-0001B	SAMPLE #1 - HIGH END OF INSULATION (WET)	Brown Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (Other)	None Detected
2-Foam 622301177-0002	SAMPLE #2 - LOW END OF INSULATION - PROPOSED LOCATION REMOVED DUE TO PUDDLE	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
2-Foam Backing 622301177-0002A	SAMPLE #2 - LOW END OF INSULATION - PROPOSED LOCATION REMOVED DUE TO PUDDLE	Gray Non-Fibrous Homogeneous	70% Cellulose 20% Glass	10% Non-fibrous (Other)	None Detected
2-Fiberboard 622301177-0002B	SAMPLE #2 - LOW END OF INSULATION - PROPOSED LOCATION REMOVED DUE TO PUDDLE	Brown Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (Other)	None Detected
3-Foam 622301177-0003	SAMPLE #3 - MIDDLE DEPTH OF INSULATION	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
3-Foam Backing 622301177-0003A	SAMPLE #3 - MIDDLE DEPTH OF INSULATION	Gray Fibrous Homogeneous	70% Cellulose 20% Glass	10% Non-fibrous (Other)	None Detected
3-Fiberboard 622301177-0003B	SAMPLE #3 - MIDDLE DEPTH OF INSULATION	Brown Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (Other)	None Detected
4-Foam 622301177-0004	SAMPLE #4 MIDDLE DEPTH OF INSULATION	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
4-Foam Backing 622301177-0004A	SAMPLE #4 MIDDLE DEPTH OF INSULATION	Gray Fibrous Homogeneous	70% Cellulose 20% Glass	10% Non-fibrous (Other)	None Detected
4-Fiberboard 622301177-0004B	SAMPLE #4 MIDDLE DEPTH OF INSULATION	Brown Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (Other)	None Detected

Report Comment: ME CERT # BA-0178

Initial report from: 10/30/2023 16:02:13



EMSL Analytical, Inc.

161 John Roberts Road South Portland, ME 04106

Tel/Fax: (207) 517-6921 / (207) 517-6922

<http://www.EMSL.com> / portlandlab@emsl.com

EMSL Order: 622301177
Customer ID: CESI62
Customer PO:
Project ID:

Contractor Copy

Analyst(s)

Stephen Severn (12)

Stephen Severn, Technical Manager
or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method") but augmented with procedures outlined in the 1993 ("final") version of the method. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. South Portland, ME NVLAP Lab Code 500094-0, VT AL197271, ME LM-0039, CT PH-0346, AZ AZ-0959, MA AA000236

Initial report from: 10/30/2023 16:02:13



EMSL ANALYTICAL, INC.
LABORATORY • PRODUCTS • TRAINING

Asbestos Bulk Building Materials - Chain of Custody

EMSL Analytical, Inc.
161 John Roberts Road

EMSL Order Number / Lab Use Only

622301177

South Portland, ME 04106
PHONE: (207) 517-6921
EMAIL: portlandlab@emsl.com

Customer Information	Customer ID:	Billing ID:
	Company Name: Haley Ward	Company Name: Haley Ward
	Contact Name: Deb Kasik	Billing Contact: Deb Kasik
	Street Address: 1 Merchant's Plaza 7th Floor	Street Address: 1 Merchant's Plaza, 7th Floor
	City, State, Zip: Bangor ME 04401 Country: US	City, State, Zip: Bangor ME Country: US
Phone: 207-989-4824	Phone: 207-989-4824	
Email(s) for Report: dkasik@haleyward.com	Email(s) for Invoice:	

Project Information

Project Name/No: 10955.016 (Roof core samples) Purchase Order:

EMSL LIMS Project ID: (if applicable, EMSL will provide) US State where samples collected: ME State of Connecticut (CT) must select project location: Commercial (Taxable) Residential (Non-Taxable)

Submitted By Name: Deborah A Kasik Sampled By Signature: *Deborah A Kasik* Date Sampled: No. of Samples in Shipment: 4

Turn-Around-Time (TAT)

3 Hour 6 Hour 24 Hour 32 Hour 48 Hour 72 Hour 96 Hour 1 Week 2 Week

Please call ahead for large projects and/or turnaround times 6 Hours or Less. *32 Hour TAT available for select tests only, samples must be submitted by 11:30am.

Test Selection

PLM - Bulk (reporting limit)

PLM EPA 600/R-93/116 (<1%)
 PLM EPA NOB (<1%)
 POINT COUNT
 400 (<0.25%) 1,000 (<0.1%)
 POINT COUNT w/ GRAVIMETRIC
 400 (<0.25%) 1,000 (<0.1%)
 NIOSH 9002 (<1%)
 NYS 198.1 (Friable - NY)
 NYS 198.6 NOB (Non-Friable - NY)
 NYS 198.8 (Vermiculite SM-V)

TEM - Bulk

TEM EPA NOB
 NYS NOB 198.4 (Non-Friable - NY)
 TEM EPA 600/R-93/116 w Milling Prep (0.1%)

Other Tests (please specify)

Positive Stop - Clearly Identified Homogeneous Areas (HA)

Sample Number	HA Number	Sample Location	Material Description
1		Sample #1 - High End of insulation (WET)	Roof Insulation
2		Sample #2 - Low End of insulation; Proposed location moved	"
3		Sample #3 - Middle depth of insulation due to puddle	"
4		Sample #4 - Middle depth of insulation	"

Special Instructions and/or Regulatory Requirements (Sample Specifications, Processing Methods, Limits of Detection, etc.)

NOB per MDEP Asphalt Paper

RECEIVED

OCT 24 2023

Method of Shipment: FedEx Sample Condition Upon Receipt:

Relinquished by: Deborah Kasik Date/Time: 10/23/23 2pm Received by: [Signature] Date/Time: 10/24/23 9:30

Controlled Document - Asbestos Bulk R7 9/14/2021 AGREE TO ELECTRONIC SIGNATURE (By checking, I consent to signing this Chain of Custody document by electronic signature.)

EMSL Analytical, Inc.'s Laboratory Terms and Conditions are incorporated into this Chain of Custody by reference in their entirety. Submission of samples to EMSL Analytical, Inc. constitutes acceptance and acknowledgment of all terms and conditions by Customer.

FedEx 7967 2855



STATE OF MAINE
DEPARTMENT OF ENVIRONMENTAL PROTECTION

JANET T. MILLS
GOVERNOR

MELANIE LOYZIM
COMMISSIONER

September 2, 2023

Attn: Lorie Dennis, QA Certification Coordinator
EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077

Dear Ms. Dennis,

This is to confirm that the Maine Department of Environmental Protection is in receipt of your request to add the following labs to your licensing of Analytical Laboratories: Boston, MA., South Portland, Maine, Wallingford, CT and Carle Place, NY.

LA-0038 for Asbestos Analytical Laboratory (Air), expires on 10/31/2024
LB-0039 for Asbestos Analytical Laboratory (Bulk), expires on 10/31/2024

Remember each laboratory must have certified individual(s) within the lab to perform analyses.

If you need any further assistance please feel free to contact me at (207) 242-0877 or e-mail at sandy.j.moody@maine.gov.

Sincerely,

Sandra J. Moody, Environmental Specialist
Division of Remediation
Bureau of Remediation and Waste Management

S. PORTLAND - INDIVIDUAL ANALYST CERTIFICATIONS

State of Maine

October 30, 2023

<i>Employee Name</i>	<i>Lab Location</i>	<i>State Certified</i>	<i>Certification No.</i>	<i>Type of Cert.</i>	<i>Exp. Date</i>
Stephen Severn	S. Portland	Maine	AA-0497	Air Asbestos Analyst	10/31/2024
Stephen Severn	S. Portland	Maine	BA-0178	Bulk Asbestos Analyst	10/31/2024
Stefan Reis	S. Portland	Maine	BA-0233	Bulk Asbestos Analyst	5/31/2024

Contractor Copy

United States Department of Commerce
National Institute of Standards and Technology



Certificate of Accreditation to ISO/IEC 17025:2017

NVLAP LAB CODE: 500094-0

EMSL Analytical, Inc.
South Portland, ME

*is accredited by the National Voluntary Laboratory Accreditation Program for specific services,
listed on the Scope of Accreditation, for:*

Asbestos Fiber Analysis

*This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2017.
This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality
management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).*

2023-10-01 through 2024-09-30

Effective Dates



A handwritten signature in blue ink, appearing to read 'Dana S. Haman', positioned above a horizontal line.

For the National Voluntary Laboratory Accreditation Program

SCOPE OF ACCREDITATION TO ISO/IEC 17025:2017

EMSL Analytical, Inc.

161 John Roberts Road
South Portland, ME 04106
Stephen Severn
Phone: 207-517-6921
Email: ssevern@emsl.com
<http://www.emsl.com>

ASBESTOS FIBER ANALYSIS

NVLAP LAB CODE 500094-0

Bulk Asbestos Analysis

Code

Description


18/A01

EPA -- 40 CFR Appendix E to Subpart E of Part 763, Interim Method of the Determination of Asbestos in Bulk Insulation Samples

18/A03

EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials

Contractor Copy



For the National Voluntary Laboratory Accreditation Program



AIHA Laboratory Accreditation Programs, LLC

acknowledges that

EMSL Analytical, Inc.

200 Route 130 North Cinnaminson, NJ 08077

Laboratory ID: LAP-100194

along with all premises from which key activities are performed, as listed above, has fulfilled the requirements of the AIHA Laboratory Accreditation Programs (AIHA LAP), LLC accreditation to the ISO/IEC 17025:2017 international standard, General Requirements for the Competence of Testing and Calibration Laboratories in the following:

LABORATORY ACCREDITATION PROGRAMS

<input checked="" type="checkbox"/>	INDUSTRIAL HYGIENE	Accreditation Expires: January 01, 2025
<input checked="" type="checkbox"/>	ENVIRONMENTAL LEAD	Accreditation Expires: January 01, 2025
<input checked="" type="checkbox"/>	ENVIRONMENTAL MICROBIOLOGY	Accreditation Expires: January 01, 2025
<input type="checkbox"/>	FOOD	Accreditation Expires:
<input type="checkbox"/>	UNIQUE SCOPES	Accreditation Expires:

Specific Field(s) of Testing (FoT)/Method(s) within each Accreditation Program for which the above named laboratory maintains accreditation is outlined on the attached Scope of Accreditation. Continued accreditation is contingent upon successful on-going compliance with ISO/IEC 17025:2017 and AIHA LAP, LLC requirements. This certificate is not valid without the attached Scope of Accreditation. Please review the AIHA LAP, LLC website (www.aihaaccreditedlabs.org) for the most current Scope.

Cheryl O Morton
Managing Director, AIHA Laboratory Accreditation Programs, LLC