

MAINE DEPARTMENT OF ADMINISTRATIVE AND FINANCIAL SERVICES

DOLBY LANDFILL COVER UPGRADE

PHASE 4

EAST MILLINOCKET, MAINE

BGS PROJECT 3754

TITLE	DWG NO
COVER SHEET	
SYMBOLS & ABBREVIATIONS	C-100
PHASED CLOSURE PLAN	C-101
EXISTING CONDITIONS PLAN	C-102
TEMPORARY CELL WASTE MIXING PLAN	C-103
SITE BASE GRADING PLAN	C-104
GAS COLLECTION PIPING PLAN	C-105
UNDERDRAIN PIPING PLAN	C-106
SITE PLAN	C-107
SECTIONS AND DETAILS	C-300
SECTIONS AND DETAILS	C-301
SECTIONS AND DETAILS	C-302
SECTIONS AND DETAILS	C-303
SECTIONS AND DETAILS	C-304


LOCATION MAP



SEVEE & MAHER
ENGINEERS

ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE

4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021
Phone 207.829.5016 • Fax 207.829.5692 • smemaine.com




SYMBOLS

EXISTING	PROPOSED	EXISTING	PROPOSED	EXISTING	PROPOSED


- ### GENERAL NOTES
- THE CONTRACTOR SHALL COMPLY FULLY WITH CONDITIONS OF THE MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION (MEDEP) OPERATING PERMIT, BOARD ORDER, MEDEP "MAINE EROSION AND SEDIMENT CONTROL HANDBOOK FOR CONSTRUCTION: BEST MANAGEMENT PRACTICES", AND MAINE DEPARTMENT OF TRANSPORTATION (MDOT) ENTRANCE PERMIT REQUIREMENTS, AS APPLICABLE.
 - THE CONTRACTOR AND ITS SUBCONTRACTORS SHALL ABIDE BY ALL SAFETY REQUIREMENTS ASSOCIATED WITH WORKING AT AN ACTIVE SOLID WASTE LANDFILL FACILITY (i.e., RISK OF WORKER EXPOSURE TO LANDFILL GASES, LEACHATE, SOLID WASTE) INCLUDING THE FOLLOWING:
 - COMPLY WITH ALL OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS;
 - INCLUDING, BUT NOT LIMITED TO, USE OF HARD HATS, SAFETY GLASSES, AND FLUORESCENT SAFETY VESTS AT ALL TIMES;
 - FOLLOW ALL APPLICABLE OSHA RULES, INCLUDING, BUT NOT LIMITED TO, THOSE RELATED TO MANHOLES, CATCH BASINS, PUMP STATIONS, TEST PITS, TRENCHES, ETC.
 - THE CONTRACTOR SHALL TAKE EVERY PRECAUTION TO ENSURE THAT NO SILTATION OF STORMWATER DRAINAGE COURSES OCCURS AS A RESULT OF SOIL DISTURBANCE ASSOCIATED WITH THE CONTRACT SCOPE OF WORK.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING COMPLETE PROTECTION OF THE PROJECT DURING CONSTRUCTION FROM ANY ACTS OF NATURE OR MAN, SUCH AS, BUT NOT LIMITED TO, FLOODS, WIND DAMAGE, EARTH SLIDES, AND SLOPE FAILURES. DAMAGE TO THE PROJECT CAUSED BY SUCH ACTS WILL NOT BE SUFFICIENT CAUSE TO INCREASE CONTRACT COSTS TO THE OWNER.
 - THE CONTRACTOR SHALL PROTECT EXISTING ON-SITE STRUCTURES FROM DAMAGE DURING CONSTRUCTION, INCLUDING: MONITORING WELLS, POWER LINES, MAINTENANCE FACILITIES, EXISTING LEACHATE COLLECTION, LINER AND TRANSPORT SYSTEMS, ETC. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL REPAIRS REQUIRED TO CORRECT DAMAGE MADE TO EXISTING ON-SITE STRUCTURES DESCRIBED ABOVE RESULTING FROM ANY CONSTRUCTION ACTIVITY.
 - THE DESIGN INTENT, AS DETERMINED BY THE ENGINEER, WILL GOVERN IN THE CASE OF DISCREPANCY IN OR BETWEEN THE DRAWINGS AND SPECIFICATIONS. THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT AND CLARIFY THE WORK SHOWN IN THE DRAWINGS, AS SOMETIMES WORK IS CALLED FOR IN THE SPECIFICATIONS THAT IS NOT SHOWN ON THE DRAWINGS AND SOMETIMES THE DRAWINGS INDICATE WORK THAT IS NOT MENTIONED IN THE SPECIFICATIONS. BOTH DRAWINGS AND SPECIFICATIONS MUST BE COMPLIED WITH IN ORDER TO FULFILL THE CONTRACT REQUIREMENTS, AND ANY WORK CALLED FOR BY EITHER IS AS BINDING AS THOUGH IT WERE CALLED FOR BY BOTH. THE CONTRACTOR SHALL TAKE NO ADVANTAGE OF ANY ERROR OR OMISSION IN THE DRAWINGS OR OF ANY DISCREPANCY BETWEEN THE DRAWINGS AND SPECIFICATIONS. IN ALL CASES OF DOUBT AS TO THE TRUE MEANING OF THE DRAWINGS AND SPECIFICATIONS, THE DECISION OF THE ENGINEER WILL BE FINAL AND CONCLUSIVE.

ACCPM	ASPHALT COATED CMP	D	DEGREE OF CURVE	HDRP	HIGH DENSITY POLYETHYLENE	PERF	PERFORATED
ACP	ASBESTOS CEMENT PIPE	DBL	DOUBLE	HORIZ	HORIZONTAL	PP	POWER POLE
AC	ACRE	DEG OR °	DEGREE	HP	HORSEPOWER	PSI	POUNDS PER SQUARE INCH
AGG	AGGREGATE	DEPT	DEPTH	HYD	HYDRANT	PVC	POLYVINYL CHLORIDE
ALUM	ALUMINUM	DI	DUCTILE IRON	ID	INSIDE DIAMETER	PVMT	PAVEMENT
APPD	APPROVED	DIA OR Ø	DIAMETER	IN OR "	INCHES	QTY	QUANTITY
APPROX	APPROXIMATE	DIM	DIMENSION	INVERT	INVERT	RCP	REINFORCED CONCRETE PIPE
ARMH	AIR RELEASE MANHOLE	DIST	DISTANCE	INVERT EL	INVERT ELEVATION	ROW	RIGHT OF WAY
ASB	ASBESTOS	DN	DOWN	LB	POUND	RAD	RADIUS
ASP	ASPHALT	DR	DRAIN	LC	LEACHATE COLLECTION	REQD	REQUIRED
AUTO	AUTOMATIC	DWG	DRAWING	LD	LEAK DETECTION	RT	ROUTE
AUX	AUXILIARY	EA	EACH	LF	LINEAR FEET	RTE	ROUTE
AVE	AVENUE	EG	EXISTING GROUND OR GRADE	LOC	LOCATION	S	SLOPE
AZ	AZIMUTH	ELEC	ELECTRIC	LT	LEACHATE TRANSPORT	SCH	SCHEDULE
BCOMP	BITUMINOUS COATED CMP	ELB	ELBOW	MH	MANHOLE	SF	SQUARE FEET
BM	BENCH MARK	EOP	EDGE OF PAVEMENT	MJ	MECHANICAL JOINT	SHT	SHEET
BET	BITUMINOUS	EQUIP	EQUIPMENT	MATL	MATERIAL	SMH	SANITARY MANHOLE
BLDG	BUILDING	EST	ESTIMATED	MAK	MAXIMUM	ST	STREET
BOT	BOTTOM	EGC	ECCENTRIC	MFR	MANUFACTURE	STA	STATION
BRG	BEARING	EXIST	EXISTING	MIN	MINIMUM	SY	SQUARE YARD
BV	BALL VALVE	FG	FINISH GRADE	MISC	MISCELLANEOUS	TAN	TANGENT
CB	CATCH BASIN	FBRGL	FIBERGLASS	MON	MONUMENT	TDH	TOTAL DYNAMIC HEAD
CEN	CENTER	FLR	FLOOR	NITC	NOT IN THIS CONTRACT	TEMP	TEMPORARY
CEM LIN	CEMENT LINED	FLEX	FLEXIBLE	NTS	NOT TO SCALE	TYP	TYPICAL
CMP	CORRUGATED METAL PIPE	FLG	FLANGE	NF	NOW OR FORMERLY	UD	UNDERDRAIN
CO	CLEAN OUT	FLR	FLOOR	NO OR #	NUMBER	V	VOLTS
CF	CUBIC FEET	FPS	FEET PER SECOND	OC	ON CENTER	VA TEE	VALVE ANCHORING TEE
CFS	CUBIC FEET PER SECOND	FT OR'	FEET	OD	OUTSIDE DIAMETER	VERT	VERTICAL
CI	CAST IRON	FTG	FOOTING	PC	POINT OF CURVE	WG	WATER GATE
CL	CLASS	GA	GALUZE	PD	POINT OF INTERSECTION	W/	WITH
CONC	CONCRETE	GAL	GALLON	PI	POINT OF INTERSECTION	W/O	WITHOUT
CONST	CONSTRUCTION	GALV	GALVANIZED	PIV	POST INDICATOR VALVE	YD	YARD
CONTR	CONTRACTOR	GPD	GALLONS PER DAY	PT	POINT OF TANGENT		
CS	CURB STOP	GPM	GALLONS PER MINUTE				
CTR	CENTER						
CU	COPPER						
CY	CUBIC YARD						

VIEW MARKERS & IDENTIFICATION



BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW		
REV.	BY	DATE	STATUS	
MAINE BUREAU OF GENERAL SERVICES DOLBY LANDFILL COVER UPGRADE PHASE 4 EAST MILLINOCKET, MAINE BGS PROJECT 3754				
SYMBOLS AND ABBREVIATIONS				
			DESIGN BY: TJM DRAWN BY: BWB DATE: 12/2023 CHECKED BY: BDP LMN: NONE CTB: SME-STD	
ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com			JOB NO. 231265.00 DWG FILE SYMSHT C-100	



APPROX. 5,000 C.Y. OF TOPSOIL REMAINING FROM THE PHASE 3 COVER UPGRADE PROJECT SEE NOTE 8

EXISTING TOPSOIL STOCKPILE AREA (TYP) SEE NOTE 7

APPROXIMATE LANDFILL BOUNDARY (TYP)

DOLBY II

DOLBY III

PHASE 2
14.2 ACRES
COMPLETED 2022

PHASE 1
25.2 ACRES
COMPLETED 2016

PHASE 3
18.2 ACRES
COMPLETED 2023

PHASE 4
10.6 ACRES

EXISTING LANDFILL ACCESS ROAD (TYP)


AVAILABLE COVER SOIL STOCKPILE
SEE NOTE 8, DWG C-102

PROPOSED COVER SOIL STOCKPILE AREA (TYP) SEE NOTE 7


APPROX. 7,700 C.Y. OF COVER SOIL REMAINING FROM THE PHASE 3 COVER UPGRADE PROJECT SEE NOTE 8



- NOTE:
1. BASE MAP PREPARED BY AERIAL SURVEY & PHOTO OF NORRIDGEWOCK, MAINE. PHOTO DATE 10/15/2015. HORIZONTAL DATUM HORIZONTAL DATUM MAINE STATE COORDINATE SYSTEM EAST ZONE, NAD 83. STANDARD PRACTICE DICTATES THAT PLANS COMPILED IN THIS MANNER SHOULD BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
 2. TOPOGRAPHY WITHIN LANDFILL LIMITS AND OUTSIDE PHASES 2 THROUGH 4 COVER UPGRADE AREAS FROM AERIAL SURVEY PERFORMED BY SEVEE AND MAHER ENGINEERS DATED 5/4/2021. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023.
 3. VERTICAL DATUM: NAVD 1929.
 4. TOPOGRAPHY WITHIN PHASE 4 CONSTRUCTION LIMITS BASED ON LOW ALTITUDE AERIAL SURVEY AND GROUND SURVEY BY SEVEE & MAHER ENGINEERS, INC. IN OCTOBER 2023.
 5. PHASED CLOSURE AREAS ARE APPROXIMATE AND ARE SUBJECT TO CHANGE.
 6. ALL SITE AND CONSTRUCTION ACTIVITIES SHALL BE IN COMPLIANCE WITH MEDEP BEST MANAGEMENT PRACTICES AND EXISTING FEDERAL, STATE, AND LOCAL PERMITS AND PERMITTING REQUIREMENTS FOR THE SITE.
 7. AREAS USED FOR STOCKPILING SHOULD FOLLOW MEDEP BEST MANAGEMENT PRACTICES. ONCE CONSTRUCTION ACTIVITIES ARE CONCLUDED, AREAS SHOULD BE RE-GRADED AND RE-SEEDED.
 8. QUANTITIES WERE PROVIDED BY GORDON CONTRACTING. PHASE 4 CONSTRUCTION CONTRACTOR SHALL FIELD VERIFY BEFORE START OF CONSTRUCTION AND REPORT DISCREPANCIES TO THE ENGINEER.




REV.	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW
	BY		STATUS
MAINE BUREAU OF GENERAL SERVICES DOLBY LANDFILL COVER UPGRADE PHASE 4 EAST MILLINOCKET, MAINE BGS PROJECT 3754 PHASED CLOSURE PLAN			
		DESIGN BY: TJM DRAWN BY: BWB DATE: 1/2024 CHECKED BY: NMT LMN: CLOSURE CTB: SME-STD.CTB	
SME SEVEE & MAHER ENGINEERS <small>ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE</small> 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com		JOB NO. 231265.00 DWG FILE BASE C-101	



- NOTES
1. BASE MAP PREPARED BY AERIAL SURVEY & PHOTO OF NORRIDGEWOCK, MAINE. PHOTO DATE 10/15/2015. HORIZONTAL DATUM HORIZONTAL DATUM MAINE STATE COORDINATE SYSTEM EAST ZONE, NAD 83. STANDARD PRACTICE DICTATES THAT PLANS COMPILED IN THIS MANNER SHOULD BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
 2. TOPOGRAPHY WITHIN LANDFILL LIMITS AND PHASE 3 COVER UPGRADE AREA FROM AERIAL SURVEY PERFORMED BY SEVEE & MAHER ENGINEERS DATED 5/4/2021. TOPOGRAPHY WITHIN PHASE 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023. TOPOGRAPHY WITHIN PHASE 4 CONSTRUCTION LIMITS BASED ON LOW ALTITUDE AERIAL SURVEY AND GROUND SURVEY BY SEVEE & MAHER ENGINEERS, INC. IN OCTOBER 2023.
 3. VERTICAL DATUM: NAVD 1929.
 4. BORINGS PERFORMED BY MAINE TEST BORING. TEST PITS, FIELD LOCATIONS, AND LOGS BY SEVEE & MAHER ENGINEERS.
 5. CATCH BASIN DATA AS SHOWN ON HISTORICAL DRAWINGS FOR SITE DEVELOPMENT PLAN CELL 2, CELL 9 AND CELL 14 CONSTRUCTION AND CELL 12 CLOSURE.
 6. ALL SITE AND CONSTRUCTION ACTIVITIES (INCLUDING SOIL STOCKPILE AREAS) SHALL BE IN COMPLIANCE WITH MEDEP BEST MANAGEMENT PRACTICES AND EXISTING FEDERAL, STATE, AND LOCAL PERMITS AND PERMITTING REQUIREMENTS FOR THE SITE.
 7. SEDIMENT POND OUTLET PROTECTIONS SHOULD BE REMOVED ONCE CONSTRUCTION ACTIVITIES ARE CONCLUDED AND SITE HAS ACHIEVED SUITABLE GRASS GROWTH AS DETERMINED BY THE ENGINEER.
 8. EXISTING COVER SOIL STOCKPILE SHOULD BE CLEARED, STUMPED, AND GRUBBED PRIOR TO USE. EROSION CONTROL MEASURES SHOULD BE INSTALLED AND DISTURBED AREAS SHALL BE STABILIZED AT COMPLETION OF WORK PER MEDEP BEST MANAGEMENT PRACTICES.
 9. TEST PITS SHOULD BE PERFORMED WITHIN TWO WEEKS OF SITE MOBILIZATION. CONDUCT TEST PITS TO LOCATE EXISTING GAS COLLECTION SAND AND REPORT LOCATION AND ELEVATION TO ENGINEER.

PHASE 4 CATCH BASIN SCHEDULE		
CB ID	INV IN	INV OUT
CB#13	405.6 (12")	405.4 (12")
CB#14	411.6 (12")	411.40 (12")
CB#17	426.00 (8") 425.05 (12")	425.01 (12")
CB#21	448.9 (6") 449.1(6") 436.9(12") 445.4(12")	445.5 (12")
CB#22	435.3 (6") 437.0 (6")	433.9 (12")
CB#23	435.5 (6") 435.0 (8") 434.8 (6")	433.9 (12")
CB#24	432.8 (6") 434.4 (6") 433.0 (18")	432.3 (12")
CB#25	429.3 (6") 430.1 (6")	427.8 (12")
TEMPORARY CELL DMH-1	462.2 (4") 459.3 (4")	457.37 (8")
TEMPORARY CELL DMH-2	458.8 (4") 458.8 (4")	457.04 (8")



REV.	BY	DATE	STATUS
	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW

MAINE BUREAU OF GENERAL SERVICES
DOLBY LANDFILL COVER UPGRADE
 PHASE 4
 EAST MILLINOCKET, MAINE
 BGS PROJECT 3754


EXISTING CONDITIONS PLAN

ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE
 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021
 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com

DESIGN BY: TJM
 DRAWN BY: BWB
 DATE: 1/2024
 CHECKED BY: NMT
 LMN: EXCON
 CTB: SME-STD.CTB

JOB NO. 231265.00 DWG FILE BASE **C-102**

I:\Projects\2024\01\231265\DWG\C-102_20240115_1018.PLT



NOTES

1. BASE MAP PREPARED BY AERIAL SURVEY & PHOTO OF NORRIDGEWOCK, MAINE. PHOTO DATE 10/15/2015. HORIZONTAL DATUM HORIZONTAL DATUM MAINE STATE COORDINATE SYSTEM EAST ZONE, NAD 83. STANDARD PRACTICE DICTATES THAT PLANS COMPILED IN THIS MANNER SHOULD BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
2. TOPOGRAPHY WITHIN LANDFILL LIMITS AND OUTSIDE PHASE 2 AND 3 COVER UPGRADE AREAS FROM AERIAL SURVEY PERFORMED BY SEVEE AND MAHER ENGINEERS DATED 5/4/2021. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023. TOPOGRAPHY WITHIN PHASE 4 CONSTRUCTION LIMITS BASED ON LOW ALTITUDE AERIAL SURVEY AND GROUND SURVEY BY SEVEE & MAHER ENGINEERS, INC. IN OCTOBER 2023.
3. VERTICAL DATUM: NAVD 1929.
4. BORINGS PERFORMED BY MAINE TEST BORING. FIELD LOCATION. TEST PITTS, AND LOGS BY SEVEE & MAHER ENGINEERS.
5. ALL SITE AND CONSTRUCTION ACTIVITIES SHALL BE IN COMPLIANCE WITH MEDEP BEST MANAGEMENT PRACTICES AND EXISTING FEDERAL, STATE, AND LOCAL PERMITS AND PERMITTING REQUIREMENTS FOR THE SITE.
6. CONTRACTOR SHALL PRESERVE THE EXISTING TEMPORARY CELL TOE DRAIN. EXISTING TOE DRAIN SHALL REMAIN TO COLLECT LEACHATE AND GAS BELOW THE COVER SYSTEM. CONTRACTOR SHALL ADD 8 OZ NON-WOVEN GEOTEXTILE OVER EXISTING CRUSHED STONE PRIOR TO PLACING WASTE/COVER SOIL MIXTURE OVER THE EXISTING TOE DRAIN.
7. CONTRACTOR SHALL PRESERVE THE EXISTING CONTAINMENT BERM THROUGHOUT THE DURATION OF THE WASTE MIXING AND GAS COLLECTION SAND PLACEMENT. AFTER THE WASTE MIXING AND GAS COLLECTION SAND PLACEMENT IS COMPLETED, THE CONTRACTOR SHALL REMOVE THE EXISTING CONTAINMENT BERM AND STRIP THE EXISTING TOPSOIL AND COVER SOIL FROM THE REMAINDER OF PHASE 4.
8. THE EXISTING SLUDGE WASTE IN THE TEMPORARY CELL LOCATED ON THE EAST SIDE OF THE CELL SHALL BE MIXED AT A 1:1 RATIO WITH EXISTING STOCKPILED COVER SOIL MATERIAL FROM THE PHASE 3 COVER UPGRADE PROJECT LOCATION SHOWN ON C-101 AND C-102.

REV.	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW
	BY		STATUS


BRIAN PIERCE
PROFESSIONAL ENGINEER

MAINE BUREAU OF GENERAL SERVICES
DOLBY LANDFILL COVER UPGRADE
PHASE 4
EAST MILLINOCKET, MAINE
BGS PROJECT 3754

TEMPORARY CELL WASTE MIXING

<p>SME SEVEE & MAHER ENGINEERS</p> <p>ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE</p> <p>4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone: 207.829.5016 • Fax: 207.829.5692 • sme-engineers.com</p>	<p>DESIGN BY: TJM</p> <p>DRAWN BY: BWB</p> <p>DATE: 1/2024</p> <p>CHECKED BY: NMT</p> <p>LMN: C-103</p> <p>CTB: SME-STD.CTB</p>
---	---


JOB NO. 231265.00 DWG FILE BASE **C-103**



ABANDONMENT SCHEDULE			
STRUCTURE ID	STRUCTURE TYPE	DIAMETER	MATERIAL
CB #13	CATCH BASIN	4'	CONCRETE
CB #14	CATCH BASIN	4'	CONCRETE
CB #17	CATCH BASIN	4'	CONCRETE
CB #21	CATCH BASIN	4'	CONCRETE
CB #22	CATCH BASIN	4'	CONCRETE
CB #23	CATCH BASIN	4'	CONCRETE
CB #24	CATCH BASIN	4'	CONCRETE
CB #25	CATCH BASIN	4'	CONCRETE
P-08-08	PIEZOMETER	1"	PVC
P-08-11A	PIEZOMETER	1"	PVC
P-08-11B	PIEZOMETER	1"	PVC
TEMPORARY CELL DMH-#1	DRAINAGE MANHOLE	4'	CONCRETE
TEMPORARY CELL DMH-#2	DRAINAGE MANHOLE	4'	CONCRETE

- NOTES**
- BASE MAP PREPARED BY AERIAL SURVEY & PHOTO OF NORRIDGEWOCK, MAINE. PHOTO DATE 10/15/2015. HORIZONTAL DATUM HORIZONTAL DATUM MAINE STATE COORDINATE SYSTEM EAST ZONE, NAD 83. STANDARD PRACTICE DICTATES THAT PLANS COMPILED IN THIS MANNER SHOULD BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
 - TOPOGRAPHY WITHIN LANDFILL LIMITS AND OUTSIDE PHASE 2 AND 3 COVER UPGRADE AREAS FROM AERIAL SURVEY PERFORMED BY SEVEE AND MAHER ENGINEERS DATED 5/4/2021. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023. TOPOGRAPHY WITHIN PHASE 4 CONSTRUCTION LIMITS BASED ON LOW ALTITUDE AERIAL SURVEY AND GROUND SURVEY BY SEVEE & MAHER ENGINEERS, INC. IN OCTOBER 2023.
 - VERTICAL DATUM: NAVD 1929.
 - BORINGS PERFORMED BY MAINE TEST BORING. FIELD LOCATION. TEST PITS, AND LOGS BY SEVEE & MAHER ENGINEERS.
 - CATCH BASIN DATA AS SHOWN ON HISTORICAL PLANS FOR SITE DEVELOPMENT CELL 2, CELL 9, AND CELL 14 CONSTRUCTION AND CELL 12 CLOSURE.
 - ALL SITE AND CONSTRUCTION ACTIVITIES SHALL BE IN COMPLIANCE WITH MEDEP BEST MANAGEMENT PRACTICES AND EXISTING FEDERAL, STATE, AND LOCAL PERMITS AND PERMITTING REQUIREMENTS FOR THE SITE.
 - BASE GRADES REPRESENT THE TOP OF THE GAS COLLECTION SAND LAYER PRIOR TO INSTALLATION OF FINAL COVER SYSTEM 40 MIL TEXTURED HDPE GEOMEMBRANE.
 - CONTRACTOR SHALL PRESERVE THE EXISTING TEMPORARY CELL TOE DRAIN. EXISTING TOE DRAIN SHALL REMAIN TO COLLECT LEACHATE AND GAS BELOW THE COVER SYSTEM. CONTRACTOR SHALL ADD 8 OZ NON-WOVEN GEOTEXTILE OVER EXISTING CRUSHED STONE PRIOR TO PLACING WASTE/COVER SOIL MIXTURE OVER THE EXISTING TOE DRAIN.

REV.	BY	DATE	STATUS
	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW
<p align="center">MAINE BUREAU OF GENERAL SERVICES DOLBY LANDFILL COVER UPGRADE PHASE 4 EAST MILLINOCKET, MAINE BGS PROJECT 3754 SITE BASE GRADING PLAN</p>			
			<p>SME SEVEE & MAHER ENGINEERS <small>ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE</small> 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com</p>
<p>DESIGN BY: TJM DRAWN BY: BWB DATE: 1/2024 CHECKED BY: NMT LMN: C-104 CTB: SME-STD.CTB</p>			<p>JOB NO. 231265.00 DWG FILE BASE C-104</p>



NOTES

1. BASE MAP PREPARED BY AERIAL SURVEY & PHOTO OF NORRIDGEWOCK, MAINE. PHOTO DATE 10/15/2015. HORIZONTAL DATUM HORIZONTAL DATUM MAINE STATE COORDINATE SYSTEM EAST ZONE, NAD 83. STANDARD PRACTICE DICTATES THAT PLANS COMPILED IN THIS MANNER SHOULD BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
2. TOPOGRAPHY WITHIN LANDFILL LIMITS AND OUTSIDE PHASE 2 AND 3 COVER UPGRADE AREAS FROM AERIAL SURVEY PERFORMED BY SEVEE AND MAHER ENGINEERS DATED 5/4/2021. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023.
3. VERTICAL DATUM: NAVD 1929.
4. BORINGS PERFORMED BY MAINE TEST BORING. FIELD LOCATION. TEST PITS, AND LOGS BY SEVEE & MAHER ENGINEERS.
5. ALL SITE AND CONSTRUCTION ACTIVITIES SHALL BE IN COMPLIANCE WITH MEDEP BEST MANAGEMENT PRACTICES AND EXISTING FEDERAL, STATE, AND LOCAL PERMITS AND PERMITTING REQUIREMENTS FOR THE SITE.
6. BASE GRADES REPRESENT THE TOP OF THE GAS COLLECTION SAND LAYER PRIOR TO INSTALLATION OF FINAL COVER SYSTEM 40 MIL TEXTURED HDPE GEOMEMBRANE.
7. CONTRACTOR SHALL PRESERVE THE EXISTING TEMPORARY CELL TOE DRAIN. EXISTING TOE DRAIN SHALL REMAIN TO COLLECT LEACHATE AND GAS BELOW THE COVER SYSTEM. CONTRACTOR SHALL ADD 8 OZ NON-WOVEN GEOTEXTILE OVER EXISTING CRUSHED STONE PRIOR TO PLACING WASTE/COVER SOIL MIXTURE OVER THE EXISTING TOE DRAIN.

REV.	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW
	BY		STATUS

MAINE BUREAU OF GENERAL SERVICES
DOLBY LANDFILL COVER UPGRADE
PHASE 4
EAST MILLINOCKET, MAINE
BGS PROJECT 3754

GAS COLLECTION PIPING PLAN

DESIGN BY: TJM
 DRAWN BY: BWB
 DATE: 1/2024
 CHECKED BY: NMT
 LMN: C-105
 CTB: SME-STD.CTB



SME
SEVEE & MAHER
ENGINEERS

ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE
 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021
 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com



JOB NO. 231265.00

DWG FILE BASE

C-105





GEOCOMPOSITE LEGEND

	TYPE 1
	TYPE 2

NOTES

1. BASE MAP PREPARED BY AERIAL SURVEY & PHOTO OF NORRIDGEWOCK, MAINE. PHOTO DATE 10/15/2015. HORIZONTAL DATUM HORIZONTAL DATUM MAINE STATE COORDINATE SYSTEM EAST ZONE, NAD 83. STANDARD PRACTICE DICTATES THAT PLANS COMPILED IN THIS MANNER SHOULD BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
2. TOPOGRAPHY WITHIN LANDFILL LIMITS AND OUTSIDE PHASE 2 AND 3 COVER UPGRADE AREAS FROM AERIAL SURVEY PERFORMED BY SEVEE AND MAHER ENGINEERS DATED 5/4/2021. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023.
3. VERTICAL DATUM: NAVD 1929.
4. BORINGS PERFORMED BY MAINE TEST BORING. FIELD LOCATION. TEST PITS, AND LOGS BY SEVEE & MAHER ENGINEERS.
5. ALL SITE AND CONSTRUCTION ACTIVITIES SHALL BE IN COMPLIANCE WITH MEDEP BEST MANAGEMENT PRACTICES AND EXISTING FEDERAL, STATE, AND LOCAL PERMITS AND PERMITTING REQUIREMENTS FOR THE SITE.
6. BASE GRADES REPRESENT THE TOP OF THE GAS COLLECTION SAND LAYER PRIOR TO INSTALLATION OF FINAL COVER SYSTEM 40 MIL TEXTURED HDPE GEOMEMBRANE.
7. CONTRACTOR SHALL PRESERVE THE EXISTING TEMPORARY CELL TOE DRAIN. EXISTING TOE DRAIN SHALL REMAIN TO COLLECT LEACHATE AND GAS BELOW THE COVER SYSTEM. CONTRACTOR SHALL ADD 8 OZ NON-WOVEN GEOTEXTILE OVER EXISTING CRUSHED STONE PRIOR TO PLACING WASTE/COVER SOIL MIXTURE OVER THE EXISTING TOE DRAIN.
8. BASE GRADES OUTSIDE THE TEMPORARY CELL REPRESENT THE TOP OF THE GAS COLLECTION SAND LAYER PRIOR TO INSTALLATION OF FINAL COVER SYSTEM 40 MIL TEXTURED HDPE GEOMEMBRANE. CONTRACTOR SHALL STRIP EXISTING COVER SOIL DOWN TO EXISTING GAS COLLECTION SAND AND SMOOTH.

		<p>MAINE BUREAU OF GENERAL SERVICES DOLBY LANDFILL COVER UPGRADE PHASE 4 EAST MILLINOCKET, MAINE BGS PROJECT 3754</p> <p>UNDERDRAIN PIPING PLAN</p>											
<p>DESIGN BY: TJM</p> <p>DRAWN BY: BWB</p> <p>DATE: 1/2024</p> <p>CHECKED BY: NMT</p> <p>LMN: C-106</p> <p>CTB: SME-STD.CTB</p>	<p>REVISIONS:</p> <table border="1"> <thead> <tr> <th>REV.</th> <th>BY</th> <th>DATE</th> <th>STATUS</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>		REV.	BY	DATE	STATUS							
REV.	BY	DATE	STATUS										
<p>ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE</p> <p>4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021</p> <p>Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com</p>		<p>JOB NO. 231265.00 DWG FILE BASE</p>											



FINAL COVER TIE-IN/TERMINATION LEGEND

◆	1	◆	TYPE 1 FINAL COVER TERMINATION
◆	5	◆	TYPE 5 FINAL COVER SYSTEM TIE-IN
◆	6	◆	TYPE 6 FINAL COVER TERMINATION
◆	7	◆	TYPE 7 FINAL COVER TERMINATION

NOTE: FOR DETAILS SEE DWG C-300


NOTES

1. BASE MAP PREPARED BY AERIAL SURVEY & PHOTO OF NORRIDGEWOCK, MAINE. PHOTO DATE 10/15/2015. HORIZONTAL DATUM HORIZONTAL DATUM MAINE STATE COORDINATE SYSTEM EAST ZONE, NAD 83. STANDARD PRACTICE DICTATES THAT PLANS COMPILED IN THIS MANNER SHOULD BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
2. TOPOGRAPHY WITHIN LANDFILL LIMITS AND OUTSIDE PHASE 2 AND 3 COVER UPGRADE AREAS FROM AERIAL SURVEY PERFORMED BY SEVEE AND MAHER ENGINEERS DATED 5/4/2021. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023. TOPOGRAPHY WITHIN PHASE 2 AND 3 COVER UPGRADE AREAS PROVIDED BY GORDON CONTRACTING, INC., OF SANGERVILLE, MAINE ON NOVEMBER 14, 2023.
3. VERTICAL DATUM: NAVD 1929.
4. BORINGS PERFORMED BY MAINE TEST BORING. FIELD LOCATION. TEST PITTS, AND LOGS BY SEVEE & MAHER ENGINEERS.
5. ALL SITE AND CONSTRUCTION ACTIVITIES SHALL BE IN COMPLIANCE WITH MEDEP BEST MANAGEMENT PRACTICES AND EXISTING FEDERAL, STATE, AND LOCAL PERMITS AND PERMITTING REQUIREMENTS FOR THE SITE.
6. BASE GRADES REPRESENT THE TOP OF THE GAS COLLECTION SAND LAYER PRIOR TO INSTALLATION OF FINAL COVER SYSTEM 40 MIL TEXTURED HDPE GEOMEMBRANE.
7. CONTRACTOR SHALL PRESERVE THE EXISTING TEMPORARY CELL TOE DRAIN. EXISTING TOE DRAIN SHALL REMAIN TO COLLECT LEACHATE AND GAS BELOW THE COVER SYSTEM. CONTRACTOR SHALL ADD 8 OZ NON-WOVEN GEOTEXTILE OVER EXISTING CRUSHED STONE PRIOR TO PLACING WASTE/COVER SOIL MIXTURE OVER THE EXISTING TOE DRAIN.
8. BASE GRADES OUTSIDE THE TEMPORARY CELL REPRESENT THE TOP OF THE GAS COLLECTION SAND LAYER PRIOR TO INSTALLATION OF FINAL COVER SYSTEM 40 MIL TEXTURED HDPE GEOMEMBRANE. CONTRACTOR SHALL STRIP EXISTING COVER SOIL DOWN TO EXISTING GAS COLLECTION SAND AND SMOOTH.


REV.	BY	DATE	STATUS
	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW

**MAINE BUREAU OF GENERAL SERVICES
DOLBY LANDFILL COVER UPGRADE
PHASE 4
EAST MILLINOCKET, MAINE
BGS PROJECT 3754
SITE PLAN**

	<p>SME SEVEE & MAHER ENGINEERS</p> <p>ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com</p>	<p>DESIGN BY: TJM DRAWN BY: BWB DATE: 1/2024 CHECKED BY: NMT LMN: C-107 CTB: SME-STD.CTB</p>
	<p>JOB NO. 231265.00 DWG FILE BASE C-107</p>	




DOLBY III - EXISTING COVER 1
NTS




NOTE: BERM FOR INTERMEDIATE UNDERDRAIN SHALL BE CONSTRUCTED WITH DRAINAGE SAND.

INTERMEDIATE UNDERDRAIN
NTS




FINAL COVER SYSTEM
NTS




NOTE: CONTRACTOR SHALL MAKE CONNECTION AT LOCATIONS SHOWN ON THE DRAWINGS.


TYPE II TO TYPE I DRAINAGE GEOCOMPOSITE CONNECTION
NTS




ANCHOR TRENCH
NTS




TYPE 1 FINAL COVER TERMINATION
NTS




TYPE 7 FINAL COVER TERMINATION
NTS




TYPE 5 FINAL COVER TIE-IN
NTS




ACCESS ROAD DRAIN
NTS



TYPE 6 FINAL COVER TERMINATION
NTS




TILL DAM
NTS




SURFACE SWALE AND UNDERDRAIN
NTS

REV.	BY	DATE	STATUS
	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW



<p>MAINE BUREAU OF GENERAL SERVICES DOLBY LANDFILL COVER UPGRADE PHASE 4 EAST MILLINOCKET, MAINE BGS PROJECT 3754</p> <p>SECTIONS AND DETAILS</p>	
	<p>SME SEVEE & MAHER ENGINEERS</p> <p>ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE</p> <p>4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone: 207.829.5016 • Fax: 207.829.5692 • sme-engineers.com</p>
<p>DESIGN BY: TJM DRAWN BY: BWB DATE: 1/2024 CHECKED BY: BDP LMN: NONE CTB: SME-STD</p>	<p>JOB NO. 231265.00 DWG FILE DETAILS C-300</p>




GAS VENTING SYSTEM
NTS



PIPE BOOT
NTS




DRAINAGE MANHOLE ABANDONMENT
NTS



NOTE:
CONTRACTOR SHALL FIELD VERIFY PIPE LOCATIONS AND OTHER EXISTING CONDITIONS PRIOR TO ABANDONMENT.


EXISTING CATCH BASIN ABANDONMENT
NTS




DITCH	"A" (FT)	"B" (FT)	"C"	"D"	"E"	"F"
RD-4	2	2	2	3	14"	6"
RD-6	1.5	2	2	3	18"	8"
RD-9	1.5	2	3	3	14"	6"

RIPRAP DITCH
NTS


REV.	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW
	BY		STATUS
MAINE BUREAU OF GENERAL SERVICES DOLBY LANDFILL COVER UPGRADE PHASE 4 EAST MILLINOCKET, MAINE BGS PROJECT 3754			
SECTIONS AND DETAILS			
		DESIGN BY: TJM DRAWN BY: BWB DATE: 1/2024 CHECKED BY: BDP LMN: NONE CTB: SME-STD	
SME SEVEE & MAHER ENGINEERS ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com		JOB NO. 231265.00 DWG FILE DETAILS C-302	



TYPICAL TRENCH SECTION
NTS



- NOTES:**
1. SLOPE TRACKING SHALL BE PERFORMED BY CONTRACTOR ON ALL FINISHED AREAS TO BE SEEDED.
 2. TRACKING SHALL BE PERFORMED BY RUNNING LOW GROUND PRESSURE TRACKED MACHINERY UP AND DOWN SLOPES LEAVING TREAD MARKS PARALLEL TO THE CONTOUR.





EROSION CONTROL MIX SEDIMENT BARRIER

NOTES:

1. EROSION CONTROL MIX CAN BE MANUFACTURED ON OR OFF THE SITE. IT MUST CONSIST PRIMARILY OF ORGANIC MATERIAL SEPARATED AT THE POINT OF GENERATION, AND MAY INCLUDE: SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR FLUME GRIT AND FRAGMENTED WOOD GENERATED FROM WATER-FLUME LOG HANDLING SYSTEMS, WOOD CHIPS, GROUND CONSTRUCTION DEBRIS, REPROCESSED WOOD PRODUCTS OR BARK CHIPS WILL NOT BE ACCEPTABLE AS THE ORGANIC COMPONENT OF THE MIX. EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. EROSION CONTROL MIX MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH.

THE MIX COMPOSITION SHALL MEET THE FOLLOWING STANDARDS:
A. ORGANIC MATERIAL, BETWEEN 20% - 100% (DRY WEIGHT BASIS)
B. PARTICLE SIZE: BY WEIGHT, 100% PASSING #6 SCREEN, 70-85% PASSING 0.75" SCREEN
C. THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED.
D. LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX.
E. SOLUBLE SALTS CONTENT SHALL BE LESS THAN 4.0 MMHOS/CM.
F. PH: 5.0 - 8.0
2. ON SLOPES LESS THAN 5% OR AT THE BOTTOM OF SLOPES 2:1 OR LESS UP TO 20 FEET LONG, THE BARRIER MUST CONFORM TO THE ABOVE DIMENSIONS. ON THE LONGER OR STEEPER SLOPES, THE BARRIER SHOULD BE WIDER TO ACCOMMODATE THE ADDITIONAL FLOW.
3. THE BARRIER MUST BE PLACED ALONG A RELATIVELY LEVEL ELEVATION. IT MAY BE NECESSARY TO CUT TALL GRASSES OR WOODY VEGETATION TO AVOID CREATING VOIDS AND BRIDGES THAT WOULD ENABLE FINES TO WASH UNDER THE BARRIER THROUGH THE GRASS BLADES OR PLANT STEMS.
4. LOCATIONS WHERE OTHER BMP'S SHOULD BE USED:
A. AT LOW POINTS OF CONCENTRATED FLOW
B. BELOW CULVERT OUTLET APRONS
C. WHERE A PREVIOUS STAND-ALONE EROSION CONTROL MIX APPLICATION HAS FAILED
D. AT THE BOTTOM OF STEEP PERIMETER SLOPES THAT ARE MORE THAN 50 FEET FROM TOP TO BOTTOM (LARGE UPGRADED WATERSHED)
E. AROUND CATCH BASINS AND CLOSED STORM DRAIN SYSTEMS
5. THE EROSION CONTROL MIX BARRIERS SHOULD BE INSPECTED REGULARLY AND AFTER EACH LARGE RAINFALL. REPAIR ALL DAMAGED SECTIONS OF BERM IMMEDIATELY BY REPLACING OR ADDING ADDITIONAL MATERIAL PLACED ON THE BERM TO THE DESIRED HEIGHT AND WIDTH.
6. IT MAY BE NECESSARY TO REINFORCE THE BARRIER WITH SILT FENCE OR STONE CHECK DAMS IF THERE ARE SIGNS OF UNDERCUTTING OR THE IMPOUNDMENT OF LARGE VOLUMES OF WATER.
7. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
8. REPLACE SECTIONS OF BERM THAT DECOMPOSE, BECOME CLOGGED WITH SEDIMENT OR OTHERWISE BECOME INEFFECTIVE. THE BARRIER SHOULD BE RESHAPED AS NEEDED.
9. EROSION CONTROL MIX BARRIERS CAN BE LEFT IN PLACE AFTER CONSTRUCTION. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER BARRIER IS NO LONGER REQUIRED SHOULD BE SPREAD TO CONFORM TO THE EXISTING GRADE AND BE SEEDED AND MULCHED.
10. IF TEMPORARY BERMS ARE USED AS SILT BARRIERS, THEY ARE PROHIBITED AT THE BASE OF SLOPES STEEPER THAN 8% OR WHERE THERE IS FLOWING WATER WITHOUT THE SUPPORT OF ADDITIONAL MEASURES SUCH AS SILT FENCE.



SILT FENCE






NOTE:
CONTRACTORS OPTION TO USE SEDIMENT BARRIER OR SILT FENCE FOR SLOPE PROTECTION.

SURFACE DRAINAGE SEDIMENT CONTROL

NTS

SLOPE TRACKING
NTS

REV.	BDP	2/2024	ISSUED FOR BID AND MEDEP REVIEW
BY	DATE	STATUS	
MAINE BUREAU OF GENERAL SERVICES DOLBY LANDFILL COVER UPGRADE PHASE 4 EAST MILLINOCKET, MAINE BGS PROJECT 3754			
SECTIONS AND DETAILS			
			DESIGN BY: TJM DRAWN BY: BWB DATE: 1/2024 CHECKED BY: BDP LMN: NONE CTB: SME-STD
SME SEVEE & MAHER ENGINEERS ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com			JOB NO. 231265.00 DWG FILE DETAILS C-303



TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL

A. GENERAL

- All soil erosion and sediment control will be done in accordance with the Maine Erosion and Sediment Control Best Management Practices, Maine Department of Environmental Protection, October 2016, and as currently revised.
- The contractor will be responsible for the repair/replacement/maintenance of all erosion control measures until all disturbed areas are stabilized. Contractor shall be responsible for plan preparation, documentation and inspection.
- Disturbed areas will be permanently stabilized within 7 days of final grading. Disturbed areas not to be worked upon within 14 days of disturbance, shall be temporarily stabilized within 7 days of the disturbance.
- In all areas, removal of trees, bushes and other vegetation, as well as disturbance of topsoil will be kept to a minimum while allowing proper site operations.
- Any suitable topsoil or cover soil will be stripped and stockpiled for reuse in final grading. Soil will be stockpiled in a manner such that natural drainage is not obstructed and no off-site sediment damage will result. If a stockpile is necessary, the side slopes of the stockpile will not exceed 2:1. Silt fence will be installed around the perimeter of all stockpiles. Stockpiles will be surrounded with siltation fencing and will be temporarily seeded with arrostook rye, annual or perennial ryegrass, within 7 days of formation, or temporarily mulched if seeding cannot be done within the recommended seeding dates. Recommended seeding dates and application rates are as follows:
Arrostook Rye: Recommended Seeding Dates: 4/15 - 8/15
Application Rate: 112 lbs/acre
Perennial Ryegrass: Recommended Seeding Dates: 4/15 - 8/15
Application Rate: 85 lbs/acre
Mulch: o Hay or Straw
Application Rate: 2 - 3 tons/acre.
Anchor with tack or 300 lbs/acre fiber mulch
o Wood Fiber Cellulose (4/15 - 7/15) Temporary mulch only
Application Rate: 4,000 lbs/acre.
Anchoring not required

B. TEMPORARY MEASURES

- Silt Fence**
 - Silt fence will be installed prior to and downgradient of all construction activity where soil disturbance may result in erosion.
 - The height of a silt fence will not exceed 36 inches.
 - The filter fabric will be purchased in a continuous roll cut to the length of the barrier to avoid the use of joints. When joints are necessary, filter cloth will be spliced together only at a support post, with a minimum 6-inch overlap, and securely sealed.
 - Posts will be spaced a maximum of 10 feet apart at the barrier location and driven securely into the ground (minimum of 12 inches). When extra strength fabric is used without the wire support fence, post spacing will not exceed 6 feet.
 - A trench will be excavated approximately 6 inches wide and 6 inches deep along the line of posts and upgradient from the barrier.
 - The standard strength of filter fabric will be stapled or wired to the fence, and 8 inches of the fabric will be extended into the trench. The fabric will not extend more than 36 inches above the original ground surface. Filter fabric will not be stapled to existing trees.
 - When extra strength filter fabric and closer post spacing are used, the wire mesh support fence may be eliminated. In such a case, the filter fabric will be stapled or wired directly to the posts with all other provisions of item (f) applying.
 - The trench will be backfilled and the soil compacted over the filter fabric.
- Stone Check Dams**
 - Stone check dams should be constructed of 2 to 3-inch crushed stone. The stone should be placed according to the configuration shown on the drawing. Hand or mechanical placement will be necessary to achieve complete coverage of the ditch or swale and to ensure that the center of the dam is lower than the edges.
 - Check dams should be installed as the swale is being constructed.
 - Sediment will be removed from behind the check dams when it has accumulated to one half of the original height of the dam.
 - Check dams will be removed when the grass has matured sufficiently to protect the ditch or swale. The area beneath the check dams will be seeded and mulched immediately after they are removed.
 - Regular inspections will be made to ensure that the center of the dam is lower than the edges. Erosion caused by high flows around the edges of the dam will be corrected. If evidence of siltation in the water is apparent downstream from the check dam, the check dam will be inspected and adjusted. Check dams will be checked for sediment accumulation after each significant rainfall.

3. **Erosion control mix and sediment barrier**

- The filter berm shall consist of an approved wood waste compost/bark mulch mix or recycled composted bark flume grit and fragmented wood generated from water-flume log handling systems or small shredding of stumpage (6 inches long x 1 1/2" dia.). The mixture needs to be a well-graded blend of organic and mineral substance. The composition is usually manufactured on or off site and by blending it with a well graded sand and gravel. The objective is a light, heavy, non-erodible mixture that is not composed of one uniform material, i.e. just bark mulch will not suffice. Comparable composted mixes can be used upon approval of the Department of Environmental Protection, Bureau of Land and Water Quality.
- The mix shall conform to standards shown on the detail:
- Installation and Size of Berm: The dimensions of the berm are more a function of the strength of the material than the flows (forces) it will encounter. At a minimum the berm shall be 4 feet wide and 18 inches high. The berm shall be placed, uncompacted along a relatively level contour. Wherever possible the existing surface must be scoured and the mixture keyed in like any other sediment control measure.
- Maintenance: All deficiencies shall be immediately corrected with additional material place on top of the berm to reach the desired height. When the berm is decomposed, clogged with sediment, eroded, or becomes ineffective, it shall be replaced.
- Clean up and Retrieval: At the end of the job, an erosion control berm shall be removed or spread out so that the native earth can be seen below.

4. **Erosion Control Mats**

- During the growing season (April 15 to August 15) use mats indicated on drawings on channel bottoms and steep slopes >3H:1V.
- During the fall and winter (August 15 to April 15) use heavy grade mats as recommended by the engineer on all channel bottoms and slopes >4H:1V.
- Install mats in accordance with the manufacturer's recommendations.

5. **Erosion Control Measures**

- The smallest practical area of land shall be exposed to construction at any one time.
- The temporary erosion control measures shall be maintained until the permanent erosion control measures are present.
- All areas disturbed by construction shall have available loam placed before seeding (or an acceptable alternative).
- After construction is terminated, all temporary erosion control measures shall be removed and accumulated sediment disposed of in a secure location.
- Mulch shall be mowings of acceptable herbaceous growth, free from noxious weeds or woody stems, and shall be dry.

6. **Permanent Measures**

- Riprapped Ditches, Aprons and Plunge Pools
 - Construct riprapped ditches, aprons and plunge pools in accordance with the details shown on the Drawings.
 - Stone for riprap will consist of sub-angular field stone or rough unwhew quarry stone. The stone will be hard and of such quality that it will not disintegrate on exposure to water or weathering, be chemically stable and suitable in all other respects for the purpose intended. The bulk specific gravity (saturated surface-dry basis) of the individual stones will be at least 2.5.
 - The riprap should be placed so that it produces a dense well-graded mass of stone with a minimum of voids. The desired distribution of stones throughout the mass may be obtained by selective loading at the quarry, controlled dumping of successive loads during final placing, or by combination of these methods. The riprap should be placed to its full thickness on one operation. The riprap should not be placed in layers. The riprap should not be placed by dumping into chutes or similar methods which are likely to cause segregation of the various stone sizes. Care should be taken not to dislodge the underlying material when placing the stones.
- The finished slope should be free of pockets of small stone or clusters of large stones. Hand placing may be necessary to achieve the required grades and a good distribution of stone sizes. Final thickness of the riprap blanket should be within plus or minus 1/4 of the specified thickness.
- Riprap will be inspected periodically to determine if high flows have caused scour beneath the riprap or dislodged any of the stone. If repairs are needed, they should be accomplished immediately.

- Topsoil, Seed, Mulch**
- Topsoil: Use stockpiled materials spread to the depths shown on the plans, if available.
- Seeding should be completed by August 15 of each year. Areas not seeded or which do not obtain satisfactory growth by August 1, will be seeded with Arrostook Rye or mulched at rates previously specified herein. After October 1, or the first killing frost, disturbed areas should be treated as indicated in C below.

7. **Additional requirements. Additional requirements may be applied on a site-specific basis.**

D. MAINTENANCE PLAN

- Routine Maintenance Inspection shall be performed annually by a qualified person during wet weather to ensure that the facility performs as intended. Inspection priorities shall include checking erosion controls for accumulation of sediments.
- Grassed Areas
 - Lime according to a soil test or at a minimum of every five years using a rate of 2 tons per acre (100 pounds per 1,000 sq ft)
 - Topdress with fertilizer in the early spring (before May 15) one year after planting with a balanced fertilizer, applying 50 pounds of nitrogen/acre (500 pounds of 10-20-20 per acre). Thereafter, fertilize according to a soil test or broadcast biennially, 300 pounds of 10-10-10 or equivalent per acre (7.5 pounds per 1,000 sq ft).

E. INSPECTIONS

- Inspections will be undertaken by qualified personnel to ensure that temporary and permanent erosion and sedimentation controls are properly installed and correctly functioning, and that additional erosion control measures are installed if needed. Such inspections will occur weekly and before and after each significant rainfall event (1 inch or more within a 24 hour period) during construction until permanent erosion control measures have been properly installed and the site is stabilized.
- A log (report) must be kept summarizing the scope of the inspection, name(s) and qualifications of the personnel making the inspection, the date(s) of the inspection, and the major observations relating to the operation of erosion and sedimentation controls and pollution prevention measures. Major observations must include: BMP's that need to be maintained; location(s) of BMP's that failed to operate as designed or proved inadequate for a particular location; and location(s) of where additional BMP's area needed that did not exist at the time of inspection. Follow-up to correct deficiencies or enhance controls must also be indicated in the log and dated, including what action was taken and when.

Seed	SEEDING SPECIFICATIONS	
	Permanent Seeding (180 lbs/acre)	Temporary Seeding (112 lbs/acre)
Red Fescue	50% by weight	Winter Rye
Red Top	2% by weight	100% by weight
White Clover	5% by weight	
Annual Ryegrass	25% by weight	
Birdsfoot Trefoil	3% by weight	
Kentucky Bluegrass	15% by weight	

Fertilizer: Apply 2 pounds per unit (87 lbs/acre) of nitrogen, phosphoric acid, and potash, or 413 lbs/acre of 19-19-19 fertilizer.

Lime: Apply liquid limestone at a rate of 3 tons per acre (138 lbs/1,000 sq ft).

Mulch: Mulch with weed-free hay or straw at 2-3 tons per acre with engineer approved tack or fiber mulch to completely cover hay/straw mulch.

(c) If permanent vegetated stabilization cannot be established due to the season of the year, all exposed and disturbed areas not to undergo further disturbance are to have dormant seeding applied and be temporarily mulched to protect the site. The following methods may be used to perform a dormant seeding:

- Prepare the seedbed, add the required amounts of lime and fertilizer, then mulch and anchor. After the first killing frost and before snow fall, broadcast or hydroseed the selected seed mixture. Double the regular seeding rates for this type seeding.
- When soil conditions permit, between the first killing frost and before snow fall, prepare the seedbed, lime and fertilize, apply the selected seed mixture, and mulch and anchor. Double the regular seeding rates for this type of seeding.

Dormant seedings need to be anchored extremely well on slopes, ditch bases and areas of concentrated flows.

Dormant seeding requires inspection and reseeded as needed in the spring. All areas where cover is inadequate must be immediately reseeded and mulched as soon as possible.

(3) Erosion Control Mats

- Install mats as indicated on drawings and in accordance with manufacturers' recommendations.

REV.				BDP				2/2024				ISSUED FOR BID AND MEDEF REVIEW			
BY				DATE				STATUS							
MAINE BUREAU OF GENERAL SERVICES DOLBY LANDFILL COVER UPGRADE PHASE 4 EAST MILLINOCKET, MAINE BGS PROJECT 3754															
SECTIONS AND DETAILS															
												DESIGN BY: TJM			
SME SEVEE & MAHER ENGINEERS												DRAWN BY: BWB			
ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE												DATE: 1/2024			
4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • sme-engineers.com												CHECKED BY: BDP			
JOB NO. 231265.00 DWG FILE DETAILS												LMN: NONE			
												CTB: SME-STD			
C-304															