TOWN OF SOUTHWEST HARBOR

LOWER TOWN PIER IMPROVEMENTS
SOUTHWEST HARBOR, MAINE

ADDENDUM #1

MAY 26, 2009

1. Change in Construction Schedule – Invitations to Bid and Bid Form

    a. The Town will change the schedule to allow construction to start September 15, 2009 with substantial completion before April 1, 2010. The facility must be fully operational and accessible for fishermen for the months of November and December, 2009, including the parking area and hoist, except that floats and ramps may be removed anytime during the period. Closure of the facility may not exceed 60 days within the overall construction period. The schedule for paving is not changed and shall be completed prior to May 31, 2010

2. Additional Electrical Conduit

    a. Provide an additional section of PVC electrical conduit from near the power service panel in the building, crossing the new pavement area to the existing hoist location on the south side of the granite filled pier.. Install the conduit 6" under pavement and extend 2' up the existing hoist pile Conduit shall have both ends capped with a pull string. Conduit size to be determined by electrician. Conduit may be used to power a second hoist in the future, similar to the existing hoist.

Enclosures: None

End of Addendum #1

J:\1510\002\Docs\ADDENDDUM #1.doc